

✓ **METALWORKING OUTLOOK, 29**

The Editor's Views, 33

Steel, Copper, Aluminum: Inventories Shrinking, 35  
Deliveries are slower, too, STEEL's quarterly survey shows

Canada Joins Economic Upswing, 38  
Construction and mining lead way

Valves Register Moderate Gains, 39  
Producers see 10 per cent shipment increase in '55

Metalworking, Steel Earnings Rise, 40, 41  
First half returns point toward record year

Management at Work, 45  
What a suggestion did for Cherry-Burrell's Lackner

Industrial Diamonds: New Sales Sparkle, 47  
Synthetics will not hurt expanding market

Windows of Washington, 42 Behind the Scenes, 6  
Mirrors of Motordom, 49 Letters to the Editors, 10  
The Business Trend, 53 Calendar of Meetings, 25  
Men of Industry, 57 New Literature, 97  
New Products, 93

✓ **TECHNICAL OUTLOOK, 71**

Beyond the Metals, 72  
What to expect of superrefractories on tough jobs  
Sleeve Bearing Applications, 76  
Part 1. How to get the right ones in the right places  
Prairie Steel Plant Still Growing, 80  
Sheffield's Kansas City, Mo., plant is geared to area  
Machine Gets Automatic Loader, 86  
Almost-human claws keep this lathe busy  
New Jobs for Alloy Plating, 90  
Corrosion protection for low-alloy jet parts at 1000°F

✓ **MARKET OUTLOOK, 99**

Steel Operations, 99 Nonferrous Prices, 104  
Price Comparisons, 100 Steel Prices, begin 106  
Nonferrous Roundup, 102 Scrap Prices, 124

Editorial & Business Staffs, 16. Advertising Index, 129. Editorial Index available semiannually. STEEL also is indexed by Engineering Index Inc., 29 W. 39th St., New York 18, N.Y.

Published every Monday by Penton Publishing Co., Penton Bldg., Cleveland 13, O. Subscription in the United States and possessions, Canada, Mexico, Cuba, Central and South America, one year, \$5.00; two years, \$15; all other countries, one year, \$20. Single copies (current issues), 50 cents. Metalworking Yearbook issue, \$2. Accepted as controlled circulation publication at Cleveland. Copyright, 1955, Penton Publishing Co.

**SEYMOUR**

*means*

**SERVICE**

*with a  
Big*



In every important industrial center, Seymour Distributors or Branch Offices are ready to fill your needs in NICKEL SILVER • PHOSPHOR BRONZE • BRASS • NICKEL ANODES • BRIGHT NICKEL & WELDING ROD

**BRANCH OFFICES**

**NEW YORK**

H. S. Samson, Mgr.  
122 E. 42nd St.  
New York 17, N. Y.  
OXford 7-2390

**PROVIDENCE, R. I.**

G. M. Crawford  
Box 418  
Providence 1, R. I.  
REgent 7-5458

**DISTRIBUTORS**

**THE COREY STEEL COMPANY**

Home Office Address:  
Cicero 50, Ill., 2800 S. 61st St.  
Appleton, Wisconsin, 1631 So. Douglas St.  
Davenport, Iowa, 405 Union Arcade Bldg.  
Detroit, 19, Mich., 16772 Shaftsbury Rd.  
Grand Rapids 3, Mich., 547 Cherry St.  
Indianapolis 20, Ind., 6068 N. Keystone Ave.  
Milwaukee 11, Wisc., 4028 No. Wilson Drive  
Minneapolis, Minn., 6524 West Walker St.  
Rockford, Ill., 2719 Auburn St.  
South Bend, Ind., 1113 Beale St.

**WILLIAMS & COMPANY**

Cincinnati 19, Ohio, 3231 Fredonia Ave.  
Cleveland 14, Ohio, 3700 Perkins Ave.  
Columbus 8, Ohio, 851 Williams Ave.  
Louisville 3, Ky., 1109 S. Preston St.  
Pittsburgh 33, Pa., 901 Pennsylvania Ave.  
Toledo 2, Ohio, 650 E. Woodruff Ave.

**NICKEL ANODE DISTRIBUTORS**

Bart-Messing Corp.  
229 Main St., Belleville 9, N. J.  
Crown Rheostat & Supply Co.  
3465 N. Kimball Ave., Chicago, Ill.  
Eaton Chemical & Dyestuff Co.  
1490 Franklin St., Detroit, Mich.  
Enthone, Inc.  
442 Elm St., New Haven, Conn.  
W. M. Fotheringham  
977 Niagara St., Buffalo 13, N. Y.  
Munning & Munning, Inc.  
202-208 Emmett Ave., Newark 5, N. J.  
Smith Chemical & Supply Co.  
668 Eddy St., Providence 3, R. I.

*Nonferrous Alloys Since 1878*

**The Seymour Manufacturing Co.**  
SEYMOUR, CONNECTICUT





Specialists in Precision High Quality  
**ALLOY STUDS**

**ERIE BOLT & NUT CO.**  
ERIE • PA.  
ONE OF THE

**16**  
INTEGRATED COMPANIES  
**BARIUM**  
STEEL CORPORATION

WORKING IN  
STEEL, ALUMINUM  
MAGNESIUM, FIBERGLASS

**STUDS • BOLTS • NUTS • ALLOYS**  
**STAINLESS • CARBON • BRONZE**

REPRESENTATION IN PRINCIPAL CITIES

## behind the scenes



### Cracks from Caracas

Maybe it was Percy Bysshe Shelley (how would *you* like to have a middle name like that?) who begged the west wind to scatter his words about the world. He didn't care where they went; just scatter 'em, he said. Well, the editors of STEEL are not so prodigal as Bysshe; they would like to have their words scattered about the world, but they would prefer to have their reports flutter to rest before the eyes of metalworking personnel, particularly the management and supervisory segments.

You'd be surprised how far STEEL flutters about the world. Percy's west wind wasn't one, two, three compared to modern postal systems. Moreover, the widespread desire for information on methods, metals and markets in the world of metalworking transcends planned circulation lists. Let us call to the stand Professor Dusan Zanko, librarian in a Jesuit university in Caracas, Venezuela.

Professor Zanko directs himself to our Readers Service Department, thanks it in advance for the attention he is about to receive and states that his university's collection of STEEL presents some lamentable gaps. He would appreciate receiving the missing copies.

How about that? Our excellent and admirable metalworking weekly setting primly on the shelves of a Jesuit library in a South American university! One might say:

*From Caracas in old Venezuela  
Wrote a Jesuit monk, "Ah, you fuela  
To send us our STEEL—  
Thees is terrible deal!  
Do you theenk it was lost in the  
muela?"*

### Unique Survey

The inventory and delivery situation in steel, copper and aluminum products is reported carefully on page 25. This unique survey, conducted quarterly by STEEL, condenses a world of vital information into a few inches of 9 point type. One of the impressive points about this survey is that STEEL assembles its facts from a pretty consistent 50 per cent return

on its questionnaire. Returns are treated confidentially; only averages and aggregates are published. After all, that's how the Kinsey report was handled, too. Unlike that report, however, which was based essentially on bad reports, STEEL's quarterly survey is based on good reports. If your business is geared to any of these metals, better make your next stop page 35.

### To Ease Your Eyes

A moment ago we mentioned 9 point type. This was done on purpose, so we could casually bring up the subject of type without appearing to drag it in too abruptly. The conversational gambit would go something like this: Speaking of 9 point type a moment ago reminds us that Art Director Bill Kellogg persuaded management to purchase some new type for STEEL.

"We used to use 30 point Tempo heavy for headings," Kellogg explained, in terms that mean exactly nothing to persons not hep to the printers' jive. "Now we use 36 point Tempo bold condensed. The first was heavier, but you'll notice the second is lighter, rounder and easier on the eye. We consider its use a distinct improvement."

The new type for headings was substituted several weeks ago. If your eyes are stronger and brighter today you can thank W. G. Kellogg.

### Looking for a Number

There was no intent to pose as a mathematician on that Einstein deal. The equations were sent in, and we wondered if anybody ever bothered to remember them. They are (and you're welcome):

$$g_{ik,i} = 0; \Gamma_i = 0; R_{ik} = 0; g_{,i}^i = 0$$

Here's a simple one for hot weather: The integer 844596301 is the 5th power of what number?

*Shradu*

(Metalworking Outlook—Page 29)





20<sup>th</sup>

Century  
*the  
persuasive  
abrasive*

This is *your* key. Take it . . . use it . . . and open the door to a real production asset . . .

20th Century \*Normalized abrasives.

They're top quality, highly uniform and wear as much as five times longer than other abrasives.

Remember, 20th Century \*Normalized is *your* key to better, more economical production.

\* Copyrighted trade name

**The CLEVELAND METAL ABRASIVE Co.**

802 East 67th St., Cleveland 8, Ohio

Howell Works: Howell, Michigan

One of the world's largest producers of quality shot, grit and powder —  
Hard Iron — Malleable (\*Normalized) — Cut Wire — Cast Steel (Realsteel)



*You can spot productive hands by the*



*A few scenes from  
the Behr-Manning  
color and sound  
motion picture . . .*




company they keep...

# Polishing production "rockets" ahead with Behr-Manning abrasive belts


It's a cinch to bring up superior finishes in record breaking time with BEHR-MANNING abrasive belts. For example, the O.D. of the box end of a wrench (left) is polished in one pass on the belt. Though your operations may be different, chances are these smooth-cutting, versatile abrasive belts will cut man hours and increase output. Try them.

**SEE THIS COLOR MOVIE,** "Coated Abrasive Belts Speed Metalworking Production". Contains 26 minutes of the latest coated abrasive methods, techniques and machinery. Address Behr-Manning, Troy, N. Y., Dept. S-8.

In Canada: Behr-Manning (Canada) Ltd., Brantford.  
For Export: Norton Behr-Manning Overseas Inc., New Rochelle, N. Y., U. S. A.



Polishing fluted areas of bits on a 1/2" wide coated abrasive belt.



Removing weld bead on tubing with a free-running abrasive belt.



Mirrors for boroscopes are being shaped on this wet abrasive belt grinder.



## BEHR-MANNING

division of NORTON Company


- ▲ COATED ABRASIVES
- ▲ SHARPENING STONES
- ▲ PRESSURE-SENSITIVE TAPES




# COAL TO COKE VIA ATLAS CARS

Making coke is a specialized business, and requires special equipment like the cars below. Coke plant operators prefer Atlas Cars because they are dependable.


**3 HOPPER  
COAL  
CHARGING  
CAR**




**COKE  
QUENCHER**



**HYDRAULIC  
DOOR  
MACHINE**



**40-TON  
COKE  
TRANSFER  
CAR**



## THE ATLAS CAR & MFG. CO.

ENGINEERS

MANUFACTURERS

1140 IVANHOE RD.

CLEVELAND 10, OHIO, U. S. A.

## LETTERS TO THE EDITORS

### Aid to Industry

We value STEEL as an indispensable medium of the entire metalworking industry.

Arthur Folker  
Advertising Manager  
Stanat Mfg. Co. Inc.  
Long Island City, N. Y.

### Away We Go?



Your editorial, "Inflationary Bias" (July 11, page 43), refers to the recent increase in steel prices. You say: "How much inflation we have depends on how the increased costs are passed along."

No one wants inflation, but the steel fabricator is hit two ways—first, on the steel increase itself. Second, on wage increases. He has no alternative but to pass on these increases. His competition will regulate any run-away prices.

In our forging industry, we find prices on similar jobs vary greatly, but steel prices are the same no matter where we buy.

The steel fabricator who is caught in the middle when steel goes up needs someone to champion his cause.

Edwin J. Carlson  
President  
Indiana Forge & Machine Co.  
East Chicago, Ind.

### Increased Longevity

In the Technical Outlook column of June 6 (page 79), I read of the "Dalton-Dize" process for increasing die life. I want more information, but have been unable to find the address of the Dalton Steel Co. I would be grateful for this information if you have it.

G. L. Clegg  
Manufacturing Research Dept. 551  
International Business Machines Corp.  
Poughkeepsie, N. Y.

• We suggest you contact Bart McIntyre, vice president, Dalton Steel Corp., 1101 NBC Bldg., Cleveland 14, O.

### Request from Belgium

We are the Belgian representatives of Greenlee Bros. & Co., automatic screw machines manufacturer of Rockford, Ill. We understand from D. E. Hawkinson, company vice president, that a summary of a report he made at the Tool Engineers' show at Los Angeles has been published in the Machine Topics column of Apr. 4 (page 97).


We have not read this article and would appreciate a copy of it. This (Please turn to page 12)



# Here's a **NEW, FAR BETTER** **ACTUATION METHOD!**


**Saginaw ball/bearing Screws assure precision positioning with minimum power, size and cost**

**EXCLUSIVE FAIL-SAFE  
MULTIPLE CIRCUITS**



If one circuit should fail, the rest will function without interruption, sharing the load between them. In critical applications this exclusive feature has no equal.

## WHAT IT IS AND HOW IT WORKS



Let's start at the beginning, with the familiar principle that there's far less friction in *rolling* than in *sliding*. By applying this principle,



Like stripes on a barber pole, the balls travel toward end of nut through spiral "tunnel" formed by concave threads in both screw and mating nut.




the *Safety ball/bearing Screw* radically increases the efficiency of rotary-to-linear motion (and vice versa). Instead of *sliding*, mating surfaces *glide* on rolling steel balls.



At end of trip, one or more tubular guides lead balls diagonally back across outside of nut to starting point, forming closed circuit through which balls recirculate.

## TREMENDOUS ADVANTAGES FOR MACHINE DESIGNERS

Conventional Acme screw's efficiency is less than 25%; *Safety ball/bearing Screw's* ranges from 90 to 95%! Combined with electric, hydraulic or pneumatic power source, it forms an actuator with unprecedented capabilities, that:



**SAVES POWER**—*Safety b/b Screw* requires only 1/3 as much torque for same lineal output as conventional Acme screw. With far lower static break-away, it operates with much less starting and driving power. This permits the use of much smaller motors with less load on the electrical system.

**ASSURES POSITIVE POSITIONING**—permits precision control within thousandths of an inch, plus perfect synchronization.

**INCREASES DEPENDABILITY**—offers longer life and added security of *exclusive multiple circuits*, plus greatly decreased dirt sensitivity of special "Gothic arch"-shaped races.

**SAVES SPACE**—Permits use of smaller motors and gear boxes; eliminates pumps, accumulators, piping, etc.

**REDUCES PART AND INSTALLATION COSTS**—savings in weight, motor size, power and auxiliary equipment cut cost, too.

**UNITS HAVE BEEN BUILT FROM 1½ INCHES TO 39½ FEET LONG**  
Every *Safety b/b Screw* is individually engineered for its particular application. Our engineers are eager to help solve your actuator problems *now*.

**MAIL COUPON TODAY FOR  
YOUR ENGINEERING DATA BOOK**

(or see our section in *Sweet's  
Product Design File*)

Saginaw Steering Gear Div.  
General Motors Corp.  
Dept. 11N, Saginaw, Michigan  
Please send your Engineering Data Book to:

Name—Title.....  
Firm.....  
Address.....  
City.....Zone.....State.....

**Safety**  
**ball/bearing Screw**

by **Saginaw**



**THE FERRY SCREW PRODUCTS**

*You*

**BELONG IN THIS PICTURE!**

We'd like to have you visit us.

And, if you use stainless or alloy steel, brass or bronze fasteners, you'll enjoy seeing America's most modern and most efficient fastener plant.

Let us show you how expert plant layout, automatic materials handling and experienced know-how combine to keep our costs down.

That's why the World's Leading Producer of Stainless Steel Screws can sell you

**PREMIUM QUALITY**  
**AT "MARKET" PRICES.**

**The E. W. FERRY**  
**SCREW PRODUCTS Inc.**  
Smith Road, Brookpark, Cleveland 30, Ohio


## LETTERS

(Concluded from page 10)

is also a good opportunity for us to become better acquainted with your magazine.

J. R. Ponchaut  
Etablissements J. R. Ponchaut, S.A.  
Houdeng-Goegnies  
Belgium

### Lead Vs. Aluminum



I noticed in the Nonferrous Metals column of June 13 (page 172) the attractive collapsible tubes chart and the shipment figures, as reported by the Collapsible Tube Manufacturers Council.

In the column, the statement is made that lead "is still the most-used metal" on the basis of poundage. Since the number of tubes used is more significant than the tonnage, it would be interesting to see how aluminum compares on this basis (especially since lead is 4.2 times heavier than aluminum on an equivalent cubic volume basis).

Irving Lipkowitz  
Assistant to the President  
Reynolds Metals Co.  
New York

• Robert Laffan, vice president of Carl Byoir & Associates Inc., tells us aluminum unit sales are greater than lead unit sales. Gross figures for the first four months of 1955 are: Aluminum, 1,596,279, and lead, 1,010,335 (including tin-coated lead and tin-lead alloy).

### Plastic for Masking

I have read the article, "Shot Peening for Safety" (May 23, page 102), and am interested in the plastic solution used for masking parts prior to shot peening. What is its name and manufacturer?

W. C. Neagley  
Metallurgist  
Chicago Pneumatic Tool Co.  
Utica, N. Y.

• For this information, contact the plant superintendent, Hamilton Standard Division, United Aircraft Corp., Windsor Locks, Conn.

### Metal Revealing

Where can we secure additional information on the item, "Inside Eye," carried in the Technical Outlook column of May 9 (page 77). It concerns use of infra-red radiation to reveal internal structure of metals.

H. P. Kragiel  
Stanley Works  
New Britain, Conn.

• Write Dr. William C. Dash, staff physicist, General Electric Research Laboratory, Schenectady, N. Y. He developed this application.






## "Battery Performance is my Business!"

Your Gould Field Engineer has one job—to make sure you get greatest possible service from your batteries. In performing that job he sees to it that your batteries are properly cared for and maintained; he instructs your personnel in systematic maintenance methods; he helps you anticipate battery needs; he makes sure you get maximum battery performance.

Gould Field Engineering Service is nationwide. Every member is factory-trained . . . has plenty of on-the-job know-how. There's a Gould Field Engineer in your area. He's as near to you as your telephone. Call him. And when you see him, ask him for the new Gould Plus-Performance Plan material for your battery maintenance staff.



America's Finest!  
GOULD  
Industrial  
Truck Batteries

©1955 Gould-National Batteries, Inc.

# GOULD Batteries


■ GOULD-NATIONAL BATTERIES, INC.

TRENTON 7, N. J.


BETTER BATTERIES THROUGH RESEARCH"

Always Use Gould-National Automobile and Truck Batteries






Sheet Steel is fed into a blanking press and sheared to fender outline.



Smoothly Contoured door panels, each shaped from a sheet of steel, move steadily on conveyors.



**Eight-a-Minute**—Steel sheets are deep drawn to fender contours in this huge, 450-ton double acting ram press where the cold steel flows evenly under tremendous pressure.

## Shapeliness

## The New Give

When you look at the low, smooth flowing lines of today's automobiles and admire their graceful styling, do you ever wonder how steel comes so shapely?

The appeal of an automobile's design is far more than just the dream of a designer worked out from artistic sketches and mock-up models he creates. It is the translation of his clay models by engineers and production men into practical, contoured curves of steel sheet.

In the early days, the design was limited by what steel could do and restricted by his own product equipment.

Today, automation has improved and speeded production. The techniques for making steel have advanced apace. Automakers can draw on the resources of technical knowledge and steelmaking facilities equipped with the latest in technological controls, such as the new rolling mills at Pittsburgh Steel Company, for producing hot and cold rolled steel sheet.

So today the designer's range of ideas is becoming increasingly unlimited because better product and new quality in steel are giving





**Complex Automatic** equipment enables inner and outer door panel free automation speeds production.



**Assembled Doors**, solidly constructed, yet gracefully styled, are ground and polished for perfect surface.

## Fashion In Steel Quality Designers Vast Horizons

ever-widening horizons for the creation of practical new designs. Pittsburgh Steel this new quality steel is called shapeliness.

**What Is It?** Shapeliness is the ability of steel to be drawn under tremendous pressure to the severest contours of design, while retaining strength and giving a consistently smooth surface. Beyond that, it must maintain this quality uniformly in sheet after sheet and coil after coil to provide smooth, trouble-free performance on high-speed production.


You will quickly grasp the importance of this quality if you will look at today's production of sleekly-designed fenders and doors of beautiful new automobile styles. The sheet from Pittsburgh Steel provides these shapes has the necessary internal qualities: exact mechanical analysis, cleanliness, and grain size. And it has the most needed external qualities: uniform dimensional accuracy and surface shapeliness.

must have these qualifications throughout each sheet and from part to sheet as it is fed into power-

ful, high-speed press operations in order to minimize the possibility of grainy surface, buckles, wrinkles, tears, stretcher strains, or skin breaks.

It is shapeliness, then, that assures a snug-fitting door or fender with a clean, smooth surface for painting . . . one that is attractive on the showroom floor and a stand-out on the road.

• **How It Pays**—Not every steel-maker can produce this quality of shapeliness in steel with the same success. Some, by reason of new equipment and technical experience, can meet the manufacturers' requirements more consistently than others.



In the Showroom and on the road, designer's creation becomes a beautifully practical reality of steel shapeliness.

If the production of your products requires better than average quality sheet steel, why not explore the opportunities Pittsburgh Steel offers you? Your orders will get personal attention from the time they are entered on the books until your product is completed. A phone call today to the district office nearest you may prove worthwhile.

*"Everything New But The Name"*

## Pittsburgh Steel Company

**Grant Building • Pittsburgh 30, Pa.**

**DISTRICT SALES OFFICES:** Atlanta • Chicago • Cleveland • Columbus • Dallas • Dayton • Detroit • Houston • Los Angeles • New York • Philadelphia • Pittsburgh • San Francisco • Tulsa • Warren, Ohio. **PLANTS:** Monessen, Pa. • Allenport, Pa. • Akron • Los Angeles • Unionville, Conn. • Warren, Ohio • Worcester, Mass.



Write for your copy of the color brochure "The New Pittsburgh Steel Company."

(Advertisement)



**TMI  
DEVELOPED  
BROAD  
SHOULDERS**

**Serving**

**TUBING CUSTOMERS**

**WITH IMPOSSIBLE PROBLEMS**



**We** realized long years ago that strong loyalties grow in the quality field.

To earn its share of that loyalty, TMI is devoted to a two-fold ideal: delivering the finest small diameter precision tubing and learning how to do the impossible.

TMI acquired this know-how with tireless effort, infinite patience, scrupulous care and an engineering appetite for problems no one else wanted to solve. The results justified the effort. In management, designing, purchasing... the word among manufacturers of quality products requiring small diameter tubing is easy to remember—"if anyone can do it, TMI

can. They have broad shoulders; put the responsibility on TMI and forget your troubles."



**TUBE METHODS INC.**

METALLURGISTS • ENGINEERS • MANUFACTURERS

BRIDGEPORT (Montgomery County), PA.

**STEEL**  
The  
**Metalworking Weekly**

Editor, IRWIN H. SUCH

Managing Editor, WALTER J. CAMPBELL

Assistant Managing Editors, VANCE BELL, JOHN S. MORGAN

WILLIAM M. ROONEY	Market Editor	ALLEN G. GRAY	Technical Editor
J. D. KNOX	Steel Plant Editor	ROBERT F. HUBER	Machine Tool Editor
		HARRY CHANDLER	Copy Editor

FRANK R. BRIGGS	Associate Editor	ROBERT O. JAYNES	Associate Editor
THOMAS F. HRUBY	Associate Editor	VAN CALDWELL	Associate Editor
JAMES P. MORRISSEY	Associate Editor		

AUSTIN E. BRANT	Assistant Editor	STANLEY B. STEWART	Assistant Editor
MICHAEL A. L. WEBSTER	Assistant Editor	HEINZ VON KOSCHEMBAHR	Assistant Editor
BYRON E. KENNEL	Assistant Editor	MARY T. BORGERHOFF	Assistant Editor
		MARY ALICE LYMAN	Assistant Editor

JEAN MCNAMEE	Editorial Assistant	MARY ANN STUVE	Editorial Assistant
		EILEEN CORTES	Editorial Assistant

**Resident Editors**

New York 17	60 East 42nd St.	Detroit 26	1249 Washington Blvd.
	B. K. PRICE, L. E. BROWNE		FLOYD G. LAWRENCE
	Murray Hill 2-2581		Woodward 3-3488
Chicago 11	520 North Michigan Ave.	Washington 4	1123 National Press Bldg.
	ERLE F. ROSS, WILLIAM E. DEAN		E. C. KREUTZBERG
	Whitehall 4-1234		Executive 3-6849
Pittsburgh 19	2837 Koppers Bldg.	London, 2 Caxton St., Westminster S. W. 1	VINCENT DELPORT
	ROBERT M. LOVE		European Editor
	Atlantic 1-3211		

**Editorial Correspondents**

Birmingham	R. W. KINCEY	Seattle	R. C. HILL
	Birmingham 3-1121		Melrose 1895
Buffalo	L. G. FELDMANN	Cincinnati	JACK DUDLEY
	Cleveland 5353		Beechmont 7598
St. Louis	MAC L. HUTCHENS	Toronto, Canada	F. S. TOBIN
	Republic 7752		Empire 4-9655
Youngstown	GEORGE R. REISS	Birmingham, England	J. A. HORTON
	Riverside 7-1471	Paris, France	LEON JAUDON-PROM
Los Angeles	NORMAN LYNN	Liege, Belgium	JACQUES FOULON
	Webster 5-3040	Dusseldorf, Germany	DR. HERBERT GROSS
San Francisco	EDWIN HAVERY		
	Yukon 6-5151		

**BUSINESS STAFF**

Advertising Director	H. G. ROWLAND	Marketing Director	D. C. KIEFER
Advertising Service Mgr.	DORIS ROBBINS	Market Research Dir.	N. R. LADABOUCHE
Production Manager	A. V. ANDERSON	Direct Mail Service	AMY LOMBARDO
Circulation & Promotion Dir.	S. F. MARINO	Reprints	JUNE SCHILENS
Circulation Manager	G. R. EBERSOLE	Classified Advertising	BETTY MARKWORTH

**Advertising Representatives**

New York 17	60 East 42nd St.	Cincinnati 6	2215 Victory Pky.
	K. A. ZOLLNER, GUY LABAW		E. L. FRANKE—Parkway 1-3640
	Murray Hill 2-2581	Detroit 26	1249 Washington Blvd.
Philadelphia	200 Wynnwood Ave.		C. A. TALLINGER JR.—Woodward 3-3488
	Wynnwood, Pa.	Chicago 11	520 North Michigan Ave.
	WM. J. VERSCHOOR		L. C. PELOTT, W. L. POLAND
	Midway 2-6512		JOHN W. VAUGHAN
Farmington, Conn.	12 Farmstead Lane		Whitehall 4-1234
	CALVIN FISHER JR.	Los Angeles 48	6262 Commodore Sloat Dr.
	Orchard 7-1756		F. J. FULLER—Webster 1-6865
Pittsburgh 19	2837 Koppers Bldg.	San Francisco 4	57 Post St.
	J. C. SULLIVAN		F. J. FULLER, Robert W. Walker Co.
	Atlantic 1-3211		Sutter 1-5568
Cleveland 13	Penton Building	Griffin, Georgia	331 South 12th St.
	J. K. GILLAM, WM. J. D'ALEXANDER		FRED J. ALLEN—Griffin 7854
	Main 1-8260		

**BPA**



**NBP**

Published Every Monday by

**THE PENTON PUBLISHING CO.,** Penton Bldg., Cleveland 13, Ohio  
Main 1-8260


G. O. HAYS	President and Treasurer
R. C. JAENKE	Executive Vice President
F. G. STEINEBACH	Vice President and Secretary
F. O. RICE	Vice President
J. P. LIPKA	Asst. Secy. and Asst. Treas.

Also Publisher of


FOUNDRY, MACHINE DESIGN, NEW EQUIPMENT DIGEST, AUTOMATION

Member of Business Publications Audit of Circulation Inc., Society of Business Magazine Editors and National Business Publications Inc.





Close-up of the control panel built into the base of a Model A Burgmaster drill press manufactured by Burg Tool Mfg. Co., Los Angeles, Cal.



The Allen-Bradley special control is supplied with an enclosure designed to fit into the machine frame.



# The ALLEN-BRADLEY "QUALITY" TRADEMARK IS A BIG SALES ASSET TO YOUR MOTORIZED MACHINES

## QUALITY COMPONENTS for A-B Control Panels



Size 1  
Automatic Starter



Size 1  
Manual Starter



Bulletin 849  
Pneumatic Timer



Bulletin 700 Uni-  
versal 4-pole Relay

Wherever possible, control apparatus ought to be built into the machine frame. The modern, streamlined appearance will appeal to your customers.

See how neatly the Burg Tool Mfg. Co. has integrated the compact Allen-Bradley control panel into their machine pedestal. The panel is assembled from Allen-Bradley standard, catalog listed items known to be good for millions of trouble free operations.

Let us help you add a real sales asset to your machines!

Allen-Bradley Co.  
1316 S. Second St.  
Milwaukee 4, Wis.

In Canada—  
Allen-Bradley Canada Ltd.  
Galt, Ont.

7-55-R



# ALLEN-BRADLEY

## MOTOR CONTROL






Type C-200 A-C  
2-pole relay




Type B-400 normally  
open 4-pole relay



Type B-800 normally  
open 8-pole relay




Type BX-840 universal  
8-pole relay



Type BXL-440 uni-  
versal relay with latch

# QUALITY RELAYS

for Long, Trouble Free Service  
in Critical Control Circuits



Type BX-44  
Universal 4-  
pole relay in  
NEMA Type 1  
general purpose  
enclosure. To  
change from  
N.O. to N.C.  
contacts, or  
vice versa, just  
change terminal  
connections.  
Max. rating—  
10 amperes.

Here is a line of small relays that is ruggedly built for tough industrial service. The simple solenoid design... with **ONLY ONE MOVING PART**... guarantees millions of failure free switching operations. The double break, silver alloy contacts need no cleaning, filing, or other maintenance. For complete Allen-Bradley relay data, please write for Bulletin 700.

Allen-Bradley Co.  
1316 S. Second St., Milwaukee 4, Wis.

In Canada—  
Allen-Bradley Canada Ltd., Galt, Ont.



Type EX-440 D-C uni-  
versal relay



Type BX-220 universal  
2-pole relay




Type BM-200 mechan-  
ically held relay



Type BA-20 2-pole  
thermostat relay




Relay in watertight  
enclosure



Relay in explosion-  
proof enclosure

**ALLEN-BRADLEY**  
**BULLETIN 700 RELAYS**  
QUALITY





*How a*  
*special wire cloth*  
**"wraps up"**  
**better crops**

Like other producers, the Reynolds Wire Division of National-Standard had been supplying cloth of bright galvanized wire. Could it be improved upon? After prolonged research with various finishes and types of wire, Reynolds hit on the idea of developing cloth of National-Standard's Copperply® wire for this special use.

Copperply fanning mill cloth, now available, offers re-

markable new advantages. Its soft, electroplated copper coating "sets" better, permitting extreme accuracy in weaving and greater stability in use. Slick and bright, it speeds the flow of seeds in screening. Finally, its conductivity permits effective grounding to avoid seed accumulation due to static electricity.

Here's only one of many, many examples of how Reynolds undertakes new developments to help customers solve problems and produce *better* products, often at *lower* cost. But problem or no problem, Reynolds customers, and National-Standard customers in general, know the satisfaction, the value, of exceptional service and cooperation. Try us; you'll see.



**NATIONAL-STANDARD COMPANY • NILES, MICHIGAN**  
Tire Wire, Stainless, Fabricated Braids and Tape

**ATHENIA STEEL DIVISION • CLIFTON, N. J.**  
Flat, High Carbon, Cold Rolled Spring Steel


**REYNOLDS WIRE DIVISION • DIXON, ILLINOIS**  
Industrial Wire Cloth

**WAGNER LITHO MACHINERY DIVISION • JERSEY CITY, N. J.**  
Special Machinery for Metal Decorating

**WORCESTER WIRE WORKS DIVISION • WORCESTER, MASS.**  
Round and Shaped Steel Wire, Small Sizes



For increased d-c power . . .



N. W. Geist, Rectifier Department Sales Manager, presents one of the new, sealed Ignitron rectifiers, now available in greatly extended ranges. It is the same type used in this metal-enclosed rectifier unit, rated at 1500 kw, 250 volts, for steel mill service.

## NOW! GET WESTINGHOUSE SEALED IGNITRONS IN HIGHER RATINGS, COMPLETELY ENCLOSED UNITS

You can now get d-c power conversion for *any* application with the new, higher rated Westinghouse sealed Ignitron rectifiers. These Ignitrons, through the entire load range, have a clear-cut efficiency advantage over other forms of conversion equipment.

Westinghouse sealed Ignitrons are basically simple . . . there are no major moving parts; all vacuum connections and indicating equipment have been eliminated. Here is a big bonus in less maintenance, lower operating cost. Tubes are permanently sealed at the factory; replacements can be obtained without delay from stock, insuring a minimum of outage time. Ignitron

cubicles are completely preassembled and wired—ready for installation upon delivery.

As a Westinghouse unit substation—with associated dry-type or liquid-filled transformers and a-c and d-c switchgear—the new Ignitron rectifiers are more compact, *require less floor space per kw*, than any other conversion equipment. And, with the grounded, dead-front metal enclosure, all personnel hazards are eliminated.

For further data, call your Westinghouse sales engineer, or write to Westinghouse Electric Corporation, Box 868, 3 Gateway Center, Pittsburgh 30, Pa.

J-10443


YOU CAN BE SURE...IF IT'S  
**Westinghouse**





# NO down time

in **16** years



- Flour Storage Bins—each 1000 lbs. capacity

*Photos courtesy Century Machine Company,  
4344 Marburg Avenue, Cincinnati 9, Ohio*



The records of the Century Machine Company show "no down time in sixteen years use" on this Cincinnati Press Brake.

This machine, working a 9½ hour day, forms light gauge sheets in mild and stainless steel up to ¼" thickness. It is constantly producing accurate parts for easy assembly of Century's baking ovens and bakery machinery.

**Write for new Press Brake Catalog B-4 describing Cincinnati Interlocking All-Steel construction, Centerline Loading, deep rigid beds and rams.**


## THE CINCINNATI SHAPER CO.

CINCINNATI 25, OHIO, U.S.A.

SHAPERS • SHEARS • BRAKES







# HOW ALLOY STEEL HELPS JOHN DEERE BUILD A STRONGER BEET HARVESTER




**STRENGTH TO WITHSTAND SHOCK AND TWISTING** is provided by Republic ELECTRUNITE Mechanical Tubing in this pilot tube which acts as a bearing for a tractor seat assembly. The tube is flared on each end and rubber grommets inserted. In this application, the tube must withstand constant shock and twisting caused by the uneven surface of furrows and plowed ground. ELECTRUNITE also provides uniform wall thickness, uniform concentricity, and is available with close I.D. and O.D. tolerances. Available in carbon and stainless analyses from Republic's Steel and Tubes Division.

**HIGH STRENGTH** and fine surface, toughness, hardenability, close tolerance, accuracy of section are cost-cutting qualities you can take full advantage of in steel parts production. Cold Drawn Alloy Bars supplied by Republic's Union Drawn Steel Division give you all six of these properties—plus **UNIFORM MACHINABILITY**. That's why so many manufacturers have come to Republic with their machining problems. Republic metallurgists and machining experts are always ready to help uncover the answers to tough cost and production problems. Write for information, there's no obligation.







Use of alloy steel permits tines on the John Deere No. 100 Beet Harvester to be made thin enough to penetrate hard ground, yet strong enough to withstand side pressure developed in squeezing the beets loose.

Field experience during the 1953 sugar beet harvest indicated that strengthening of the beet digger tines on the John Deere No. 100 Beet Harvester was necessary to prevent bending.

A change in the shape of the tine or tooth accomplished part of the strength increase. Deere's Engineering Department also felt that by increasing the surface hardness of the tooth, its performance would be improved.

But it was not possible to go to a higher hardness on the carbon steel previously used because the tines became so brittle that they would break under stress. So Deere switched to alloy steel, of which Republic is a supplier.

By taking full advantage of the superior strength and hardenability of alloy steel, bending and abrasion problems have been eliminated. The tines are 24% stronger than those previously made from carbon steel, and with-

out loss in toughness or wearing qualities. Field experience in the 1954 harvest indicates that the alloy steel tine is completely satisfactory and has a much better service life than the previous types.

Alloy steels provide an outstanding combination of qualities essential to designing smaller sections to carry heavier loads with no sacrifice of strength or safety. They resist fatigue, shock and stress. They respond uniformly to heat treatment, producing hard, wear-resistant surfaces around tough cores.

Perhaps you have a problem involving one or more of these factors. Republic—world's largest producer of alloy steels—offers you metallurgical and engineering assistance to help you get the most from alloy steels at the lowest possible cost. Mail the coupon for complete information.

# REPUBLIC STEEL

*World's Widest Range  
of Standard Steels and Steel Products*

REPUBLIC STEEL CORPORATION  
3120 East 45th Street  
Cleveland 27, Ohio



Please send me information on:

- ☐ Alloy Steels ☐ ELECTRUNITE® Steel Tubing  
☐ Cold Finished Steels

Name \_\_\_\_\_ Title \_\_\_\_\_

Company \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ Zone \_\_\_\_\_ State \_\_\_\_\_

K-8917




THE  
MACHINE TOOL  
SHOW  
BOOTH  
1406




CUTTING  
GRINDING  
TAPPING  
ROLLING


THREADS



CUTTING



The 8C LANDMACO—one of five new Thread-Cutting machines to be demonstrated. These machines are designed for precision threading of workpieces from  $\frac{3}{16}$ " to  $6\frac{5}{8}$ " in diameter. Above is the new 2" LANDMATIC—one of the many Standard and Special Thread-Cutting Heads on display designed for application to Automatics and Turret Lathes.




GRINDING

The CENTERLESS Thread Grinder—to be shown in operation—for infeed and thrufeed grinding of threads from  $\frac{1}{16}$ " to 4" in diameter at mass production rates.




TAPPING

The LL Collapsible Tap for producing internal tapered threads featuring detachable heads for wide range coverage. On display will be Rotary or Stationary Standard Taps for straight or tapered threads, Solid Adjustable Taps, Valve Taps, and Taps for other special applications.



ROLLING



The new LANHYROL Thread Rolling Machine—shown in a variety of demonstrations—revolutionary in its output, accuracy, and flexibility. Above is the #20 LANROLL Attachment—one of five sizes of Thread Rolling Attachments for Automatics and Turret Lathes to be displayed.

LANDIS Machine COMPANY • WAYNESBORO PENNSYLVANIA



# CALENDAR OF MEETINGS

**Aug. 15-17, Society of Automotive Engineers Inc.:** West coast meeting, Multnomah hotel, Portland, Oreg. Society's address: 29 W. 9th St., New York 18, N. Y. Secretary: John A. C. Warner.

**Aug. 22-23, Stanford Research Institute and National Industrial Conference Board:** Symposium on electronics in automatic production, Sheraton-Palace hotel, San Francisco. Information: National Industrial Conference board, 247 Park Ave., New York 17, N. Y. Secretary: Herbert Briggs.

**Aug. 24-26, West Coast Electronic Manufacturers Association:** Western electronic show and convention, Civic Auditorium, San Francisco. Information: WESCON, 344 N. LaBrea Ave., Los Angeles 36, Calif.

**Aug. 28-Sept. 1, National Association of Furniture Manufacturers:** Furniture supply fair, Conrad Hilton hotel, Chicago. Association's address: 666 Lake Shore Dr., Chicago 11, Ill. Secretary: John M. Snow.

**Aug. 31-Sept. 26, World's Fair of Power:** Lake Shore Dr. adjacent to Soldiers Field, Chicago. Sponsor: General Motors Corp., General Motors Bldg., Detroit 2, Mich.

**Sept. 5-6, American Machine Tool Distributors Association:** Annual meeting and show, Blackstone hotel, Chicago. Association's address: 1900 Arch St., Philadelphia 6, Pa. Secretary: Thomas A. Fernley Jr.

**Sept. 6-8, Industrial Truck Association:** Fall meeting, the Greenbrier, White Sulphur Springs, W. Va. Association's address: 526 Washington Loan & Trust Bldg., Washington 4, D. C. Managing director: William Van C. Brandt.

**Sept. 6-8, Material Handling Institute Inc.:** Fall meeting, the Greenbrier, White Sulphur Springs, W. Va. Institute's address: One Gateway Center, Pittsburgh 22, Pa. Managing director: R. Kennedy Hanson.

**Sept. 6-17, Metalworking Machinery & Equipment Exposition:** Colliseum, Chicago. Information: Exhibition & Convention Management Inc., 2689 E. Overlook Rd., Cleveland 10, O. General Manager: C. L. Wells.

**Sept. 6-17, National Machine Tool Show:** International Amphitheatre, Chicago. Sponsor: National Machine Tool Builders' Association, 671 E. 102nd St., Cleveland 6, O. General Manager: Tell Berna.

**Sept. 6-17, Production Engineering Show:** Navy Pier, Chicago. Sponsor: National Machine Tool Builders' Association, 2071 E. 102nd St., Cleveland 6, O. General Manager: Tell Berna.

**Sept. 9-11, Metal Powder Association:** Fall meeting, the Homestead, Hot Springs, Pa. Association's address: 420 Lexington Ave., New York 17, N. Y. Secretary: Robert L. Ziegfeld.

**Sept. 11-14, National Metal Trades Association:** Eastern plant management conference, Essex and Sussex hotels, Spring Lake, N. J. Association's address: 122 S. Michigan Ave., Chicago 3, Ill. Secretary: C. L. Blatchford.


**Sept. 11-16, American Chemical Society:** Fall meeting, University of Minnesota, Minneapolis. Society's address: 1155 16th St. N.W., Washington 6, D. C. Executive secretary: J. Den H. Emery.

**Sept. 12-14, American Road Builders Association:** Annual conference of county engineers and officials, New Riverside hotel, Gatlinburg, Tenn. Association's address: World Center Bldg., Washington 6, D. C. Secretary: Eugene Reybold.

**Sept. 12-14, Allied Railway Supply Association:** Annual meeting and exhibit, Sherman hotel, Chicago. Association's address: P.O. Box 5522, Chicago, Ill. Secretary: Charles F. Weil.

**Sept. 12-15, Automotive Electric Association:** Fall meeting, the Homestead, Hot Springs, Pa. Association's address: 16223 Meyers Ave., Detroit 35, Mich. Secretary: S. W. Motter.

**Sept. 12-15, Society of Automotive Engineers Inc.:** Tractor meeting and production forum, Hotel Schroeder, Milwaukee. Society's address: 29 W. 39th St., New York 18, N. Y. Secretary: John A. C. Warner.



## Synchronized Speeds for "Tandem" Load-Handling

EDERER has "job-engineered" cranes to the specific requirements of a plant where the work required two cranes with speeds synchronized for "tandem" operation in handling extra heavy loads. Full dynamic controls with adjustable voltage control allow intermediate speeds from 0 to full load speed to be adjusted at any time to suit any operating requirement.

This is only one of the many ways in which EDERER engineers and builds cranes to do any type of work in any industry. Similarly, EDERER can "job-engineer" a crane to the specific requirements of YOUR plant. Our industrial crane catalog can give you more details . . .

For your copy of EDERER  
industrial crane catalog,  
Bulletin CR-610, just  
write us.

276C55

**EDERER ENGINEERING COMPANY**  
2935 First Avenue South  
Seattle 4, Washington

**EXPORT DIVISION:**  
301 Clay Street, San Francisco 11, California

**EDERER**  
**CRANES**


**OVER 53 YEARS "JOB-ENGINEERING" CRANES FOR INDUSTRY**



If you haven't read this important booklet, your production line may be operating at less than peak efficiency. Your operations may be beating competition with HSS today, but you will likely need carbide tooling to be the leader tomorrow.



Write for your free copy of this important booklet today!



# Conomatic

CONE AUTOMATIC MACHINE COMPANY, INC., WINDSOR, VT., U.S.A.

THE  
MACHINE TOOL  
SHOW  
CHICAGO, ILL.

BOOTH 401







## Gas and Chemical "scrubbers" for Great Lakes Steel

(DIVISION OF NATIONAL STEEL CORPORATION)

At Great Lakes Steel Corporation's Blast Furnace Division, a new by-product coke plant is equipped with a total of 25 large examples of Graver's craftsmanship in steel.

These structures, shop-fabricated at Graver's East Chicago plant and field-erected on the site by Graver crews, were built to the designs of Wilputte Coke Oven Division, Allied Chemical & Dye Corporation. These include bins, stacks, gas coolers, tanks for chemical feed, storage, and settling—and scrubbers such as the three 132' towers shown at the left.

This variety of quality fabrication indicates Graver's versatile craftsmanship—demonstrates Graver's ability to shop-fabricate and field-erect structures for the steel, petroleum and chemical industries. For process and storage equipment in steels, alloys or clads, Graver's offices across the country are staffed with competent engineers ready to serve you.




**...craftsmen in carbon,  
stainless and alloy steels**

**GRAVER TANK & MFG. CO., INC.**

EAST CHICAGO, INDIANA


CHICAGO • NEW YORK • PHILADELPHIA • EDGE MOOR, DEL.  
CATASAUQUA, PA. • PITTSBURGH • CLEVELAND • DETROIT • TULSA  
SAND SPRINGS, OKLA. • HOUSTON • ODESSA, TEXAS • CASPER,  
WYO. • LOS ANGELES • FONTANA, CAL. • SAN FRANCISCO





# **SAVED \$103.46 PER RING!**

## **Switching to Flash Butt-Welding of Mill-Rolled Sections, Slashed Production Cost 76½%**



### **NEW METHOD**

Ring, rolled and welded from mill section of approximate shape of finished part.

### **OLD METHOD**

Ring, rolled and welded from rectangular bar size to maximum overall dimensions of finished part.

Free Catalog of American Welding Facilities. Send for Your Copy TODAY.



Rough rings purchased by a well known manufacturer of jet aircraft engines weighed 135 pounds each. Most of this weight was excess metal which had to be machined away. American Welding's Industrial Products Division, working with this company, studied blueprints and recommended a flash butt-welded ring, formed from a special mill-rolled section. Adopting this new ring saved 88 pounds of metal and eliminated much of the machining time required. American Welding now produces thousands of these rings, in a rough-machined state, at less than one-quarter of the original cost.

Would you like to know more about American Welding and what savings it may help to effect on products which you manufacture? Write today — we will be glad to study your problem.

# **AMERICAN WELDING**

**THE AMERICAN WELDING & MANUFACTURING CO.**  
110 DIETZ ROAD • WARREN, OHIO



# Metalworking Outlook

## Timetable for Autos

Bulk of the 1956 auto models will be introduced during October and November. One luxury car will come out early in September, and one of the independents won't introduce until December. But the introductions, generally, are earlier than last year's. The move should spur sales and should contribute to pushing production to more than 7 million cars in calendar 1955.

## Two Troubles for UAW

The United Auto Workers is in serious trouble. Worry No. 1: The indictment for spending money on politics. Worry No. 2: The defection of some 2000 skilled workers who want to form their own union. The indictment stems from some UAW-sponsored TV shows on which Democratic candidates appeared last year. The splinter movement arises because of the labor contract negotiated with auto companies this year. Skilled workers, less subject to layoff than other employees, aren't much interested in the Supplemental Unemployment Plan.

## Steelworkers To Vote

Steelworker President David J. McDonald faces a test on Oct. 25 which he will probably pass, but just barely. Union members will decide whether to go along with Mr. McDonald's choice for the office of international vice president. The vice presidency became the center of dispute last March when a close friend of McDonald's, Howard R. Hague, was appointed to fill the vacancy caused by the death of James G. Thimmes. Opposition came from Joseph P. Molony, who heads the New York district. He will run for the office, presumably against Mr. Hague.

## Twilight Zones in T-H

Eight years have passed since Taft-Hartley Amendments were passed to the National Labor Relations Act. You'd think most difficulties would be ironed out, but they're not, according to Guy Farmer, chairman of the National Labor Relations Board. Among many, these five twilight zones haven't been clarified: 1. Can an employer insist on a contract provision limiting the union's right to strike by conditioning it upon an employee vote? 2. Are stock purchase plans subject to bargaining? 3. Can a non-striking union refuse to handle products ("hot cargo") of a company being struck? 4. What rights does an employer have to control the use of his property against labor organizers, etc.? 5. What is the correct interpretation of section 8 (d) of the Labor Relations act? (It has to do with notification of wishes to terminate or modify a contract.)

## British Steel Prices Up

British steel prices rose July 25, but they still average 15 per cent under those in the U.S. and on the continent. Increases range from \$2.94 a ton



# Metalworking

---

## Outlook

for basic pig iron, now \$44.10 a ton, to \$12.25 a ton for certain types of alloy bars, which now cost \$215.78 a ton. Reasons: Higher costs of coal, ore, scrap, freight rates and general industry wages.

### Canada Keeps Pace

Canada's system of unemployment compensation keeps pace with boosts in state jobless pay benefits in the U.S., says Commerce Clearing House. Canadian workers who contribute to the fund may receive benefits up to a maximum of \$30 a week for 36 weeks. That compares with the average \$32 weekly payment in the U.S. The maximum period in the U.S. is less, ranging from 16 to 30 weeks. In only a few instances in the U.S. do workers contribute to the fund.

### AF Buys Foreign Tools

Not much will come from protests of machine tool builders over the latest purchase abroad of equipment by the Air Force. It was following a Presidential directive implementing the State department's policy of doing business, where possible, with friendly foreign countries. Involved are 45 radial drills from a British producer and some shapers built by an Italian firm. The British bid was 19.5 per cent less than the lowest American bid. The price on the Italian shapers was about half the lowest American price.

### Challenged on Cost

Trade associations are alarmed at proposed revisions in Section XV on costs of the Armed Services Procurement Regulations (ASPR). Aircraft Industries Association objects because the Pentagon disallowed incentive compensation as cost. It also points the finger at the strange provision that would disallow research expense when more than 25 per cent of the contractor's business is with the government. A company with only 24.99 per cent of its business with the government could charge research as an expense.

### Manpower for Power

"The largest problem in atomic power today is that of technical manpower." So says Louis H. Roddis Jr. of the Atomic Energy Commission's staff. In 1947, not over 50 people in the U.S. were working on atomic power. Today, there are some 5000. That seems like a dramatic increase, but it's still inadequate, says Mr. Roddis. It's only 1 per cent of the number working in all research and development, less than 10 per cent of the researchers in the chemical industry and less than 5 per cent as many as in the electrical industry.

### Straws in the Wind

Some 700 more apprentices were registered at the end of the first quarter than at the beginning . . . Commonwealth Edison Co. has awarded a \$45-million contract to General Electric Co. to build a nuclear power plant . . . The CIO electrical workers have demanded GAW from GE . . . The cost of living rose 0.2 per cent from mid-May to mid-June.



# A word about the Steel Situation

You may be wondering what new supply problems you will have because of the recent set-back in steel production. Strike-loss estimates run to nearly a million tons—and even before the strike, spot shortages had already been created by high demand.

In this emergency period, as always, Ryerson stocks undoubtedly can help you. Thousands of tons of certified quality steels are on hand at your nearby Ryerson plant—carbon steels, alloys, and stainless—and our stocks are being built up daily. In the few cases where the exact kind or size you need is not available locally we will check stocks at our 15 other plants for you.

Remember too that when you order from Ryerson you not only have the

world's largest reservoir of steel stocks to draw on, but also the advantage of our long experience, unequalled facilities, and complete dedication to quality of product and service.

So for help on emergency or regular requirements—call your nearby Ryerson plant today.

---

## PRINCIPAL PRODUCTS IN STOCK

**BARS, CARBON STEEL**—Hot rolled and cold finished—rounds, squares, hexagons, etc.

**STRUCTURALS**—Channels, angles, beams, etc.

**PLATES**—Welding and forming quality, abrasion resisting, E-Z-Cut, flange quality, safety plate, etc.

**SHEETS & STRIP**—Hot and cold rolled, many types and sizes, cut to exact sizes.

**TUBING**—Seamless and welded mechanical and boiler tubes, hydraulic tubing, etc.

**ALLOY STEEL**—All types including leaded alloys.

**STAINLESS**—Allegheeny metal bars, plates, sheets, pipe, tubing, fittings, etc.

**BUILDING PRODUCTS**—Reinforcing bars, spirals, bar joists, wire mesh, etc.

**MACHINERY & TOOLS**—For metal fabrication.



## RYERSON STEEL

PH T. RYERSON & SON, INC. PLANTS AT: NEW YORK • BOSTON • PHILADELPHIA • CHARLOTTE, N. C. • CINCINNATI • CLEVELAND  
ROIT • PITTSBURGH • BUFFALO • CHICAGO • MILWAUKEE • ST. LOUIS • LOS ANGELES • SAN FRANCISCO • SPOKANE • SEATTLE



1955		august		1955	
sun	mon	tue	wed	thu	sat

RELIANCE  
*Job-Fitted*  
ready-to-use  
SHEET and STRIP  
STEEL

T.M. REG. U.S. AND CANADA  
DEPENDABLE DAN

**RELIANCE**  
*Job-Fitted*  
**PRODUCTS**

Cold Rolled • Hot Rolled • H.R. Pickled  
Galvanized • Long Tenne  
Standard or Production Sizes  
Sheared or Slit to Actual Working Dimensions

COPYRIGHT 1955 D.S.C.

99.387%

## Customer Satisfaction Is Our No. 1 Job



GENERAL SALES OFFICE—DETROIT 9, MICHIGAN

### DSC CUSTOMER REPRESENTATIVE OFFICES

Chicago, Cincinnati, Columbus, O., Dayton, O., Detroit, Grand Rapids, Mich.,  
Hamden (New Haven), Conn., Indianapolis, Jackson, Mich., Louisville, Ky.,  
New York, Richmond, Va., St. Louis, Toledo, Worcester, Mass.

DSC MILL PRODUCTS

Hot Rolled and Cold Rolled Sheets  
Cold Rolled Carbon Steel Strip      Flat Cold Rolled Carbon Spring Steel  
Low and Medium Carbon Manufacturers' Wire      High Carbon Specialty Wire  
Aluminum Cable Strand Reinforcement      Rope Wire      Tire Bead Wire  
Welded Wire Fabric

## IN FURTHERANCE OF THE METAL STAMPING INDUSTRY



Learn Tomorrow's Management Methods by attending  
**THE PMI ANNUAL MEETING—GROVE PARK INN, ASHEVILLE, N.C.**

for complete details write to:

**PRESSED METAL INSTITUTE, National Assn. of Metal Stampers, Cleveland 20, Ohio**

OCTOBER  
9-13  
1955



August 1, 1955



## Cheers and Smears

Under Pericles, ancient Athens reached its greatest prosperity. The man was noted for his integrity, honesty and profound patriotism. But some of his reforms offended Athenians. He was investigated, fined and subjected to other indignities. Soon thereafter, when Athens was threatened with war, he was recalled, made ruler and given a free hand.

Crowd psychology hasn't changed much in twenty-four centuries. Through two world wars and several lesser emergencies, Washington has followed the same script:

It sends out urgent calls for businessmen to come to the capital and get the ball rolling on defense production, allocation of scarce materials, price control and similar problems. Industry responds by sending top executives who are able to untangle the mess with speedy solutions. They are men who are sorely needed in their own jobs. They undergo the inconvenience of being away from home, working long hours under often difficult conditions and being frequently frustrated by government red tape.

They do a good job. They are cheered for their self-sacrifice and efficiency.

After emergencies subside, the curtain goes up for the second act:

Businessmen who serve without compensation are investigated by congressional committees or bureaus. They undergo character assassination. They must defend themselves against vague charges that they used their official positions for private gain.

Charges are seldom, if ever, substantiated. Investigators find the men who serve without compensation do an effective and honest job. But the indelible stamp of suspicion remains.

We fear that it is a dual threat to national security: First, it may make the job of recruiting able executives for government service more difficult in the next emergency; second, it imperils the administration's plan to create an executive reserve with industrial know-how and Washington experience.

This plot of cheers and smears is one which the business community resents.

Walter J. Campbell


MANAGING EDITOR



New and improved steels for you from the new

**INLAND**

Research Center.



**THIS PINT-SIZE ROLLING MILL MAY SAVE YOU KING-SIZE HEADACHES (AND MONEY TOO!)**

At Inland, "new ideas" are considered as vital a raw material in steel-making as top grade iron ore and coal. Establishing reserves of this basic ingredient is a continuing job for Inland's research and development people. The new Inland Research Center in Hammond, Indiana, where Inland researchers look for better steels and more efficient ways to make them, is the most recent addition to Inland's "new idea" resources.

**INLAND STEEL COMPANY**

38 South Dearborn Street • Chicago 3, Illinois  
Sales Offices: Chicago • Milwaukee • St. Paul  
Davenport • St. Louis • Kansas City • Indianapolis  
Detroit • New York


Principal Products: Sheets • Strip • Structural  
Shapes • Plates • Bars • Tin Mill Products • Rails  
and Track Accessories • Coal Chemicals



# Steel, Copper, Aluminum

(% of respondents who added to inventories)

## STEEL QUARTERLY SURVEY



Survey includes: Steel products (bars, strip, sheet, plate, structural shapes, wire, tubing), pig iron, copper and brass mill products, copper wire and cable and aluminum products.  
Preliminary

## Inventories Shrinking

WE HAVE been getting steel on about a week's notice for the past month" was a comment made one year ago in STEEL's quarterly survey of steel, copper and aluminum. How times have changed! In the latest roundup, one user reports: "Mill deliveries have been rescheduled and now represent from 90 to 120 days from date of order."

**Troubles**—Over-all, 36 per cent of the steel, copper and aluminum users surveyed report that deliveries are unsatisfactory. Three months ago, 24 per cent commented that way. In most of last year, the figure was only 1 or 2 per cent. This quarter, like the last, about 16 per cent note troubles on one or more items.

"Deliveries seem to be getting worse week by week," one PA notes. Several smaller companies

surveyed feel they are getting the "short end of the stick." It's probably small consolation, but industrial giants are feeling the delivery pinch, too.

A purchasing agent for a division of one large corporation says: "Late deliveries on many individual items and sizes make it extremely difficult to keep efficient production schedules." On the other hand, several smaller companies report "deliveries are adequate on most items."

**Disappointed** — Inventories are shrinking, with more users reporting stocks in the 10-to-30 day supply level, fewer in the higher brackets. It's not a particularly large change, but the trend is downward, and few metalworking executives surveyed are optimistic that the slide will be arrested in the coming three months. The

smallest number this year expect to expand inventories (see chart). Many are disappointed that plans to build in the second quarter didn't pan out. Some 22 per cent expected to wind up the three months with higher stock; only 16 per cent made the grade.

Showing the way things are going: Of the small percentage expecting to add to inventories this quarter, 84 per cent expects it will put them in a better business position; none says it will leave them worse off.

**Mixed Reaction**—On the other hand, almost half of those seeing lower inventories ahead says it will put them in a poorer position. The other half is divided about 50-50 between those who say lower stocks will leave them better off and as well off.

Among the small percentage (of the total survey) that says they'll be happy with lower inventories, is a small core of optimism that the delivery situation will get better. Those PAs are being forced by extended lead times to carry larger than desired stocks and hope to be able to cut them back if lead times shorten.

**Difficulties**—As far as individual products are concerned, plates seem to be the main trouble spots, with over 50 per cent of users reporting trouble on deliveries. That's a small increase from three months ago. Structural are tight with 42 per cent noting difficulty, same as in the previous survey.

Sheet continues in high demand, with about two out five unable to get the kind of delivery they want on hot and cold rolled. The number of users having troubles with galvanized sheets more than doubled. Hot-rolled carbon bars are tighter.

## Manganese in Venezuela

Huge manganese deposits discovered east of Upata, Venezuela, are probably among the richest in the world, claims the Venezuelan Ministry of Mines & Hydrocarbons.

The possible quantity of ore is estimated to be several million tons; the content is between 28 and 55 per cent pure metal.





Electrical League of Cleveland

## Adequate Wiring: A Five-Year Market

	COST IN BILLIONS*
Rewiring present inadequately wired homes (34 million)	\$5.0
Conventional wiring of new homes (1 million a year)	3.0
"Plus" wiring in new homes to bring them to adequate standards	0.5
<b>TOTAL MARKET</b>	<b>\$8.5</b>

\*Includes materials, labor and profit.  
Source: National Adequate Wiring Bureau.

Adequate wiring certifications increase as . . .

## Copper Adds More Circuits

A MARKET WORTH \$8.5 billion over the next five years: That's what awaits manufacturers of copper wire, appliances and allied products in the field of adequate residential wiring.

The campaign for better wiring has been going on to some extent since the 1920s, but it hasn't been until the last two years that metalworking has put much effort into it. Since then, the market has been snowballing.

**Who's Who** — Naturally, the chief industries in the campaign are those which will benefit most. Utilities sold 55 billion kilowatt-hours for "convenience" appliances last year and would like to double that figure by 1964 if home wiring will take it.

Appliance makers, who stand to lose business from inadequate wiring or gain from sufficient home circuiting, are behind the movement. They say they should be able to sell 428 million units in the next five years, but only if the wiring is adequate. They sold only 353 million appliances in the last five years.

Makers of generating equipment, such as Allis-Chalmers Mfg. Co., have boosted the promotion because they see heavier sales of heavy equipment as better wiring increases consumption of pow-

er and forces an expansion of generating capacity.

**Real Payoff**—The net result will be bigger markets for copper wire, which is the reason Kennecott Copper Corp. and Anaconda Co. are promoting better wiring. Neither makes wire itself, but they sell copper to subsidiary or independent wire mills. Copper is in short supply, but these producers are looking to the long range market. It is estimated that there will be 248 million kilowatts of additional generating capacity by 1975. That will require 700 billion feet of wire to handle the power efficiently, not counting the wire that will go into the motors of the 428 million appliances expected to be sold over the next five years.

The present campaign is almost wholly directed at the homeowner and is a two-pronged attack: Existing homes and new construction. The National Adequate Wiring Bureau, New York, estimates that of the 45 million wired homes today, 34 million have less than minimum wiring to handle the requirements of modern living. In 1930, when many of these homes were built, there were only 19 appliances on the market. Today, there are 56.

New construction probably will

continue at the 1-million-a-year pace over the next five years. The goal is to put adequate wiring, which is more than just "conventional" wiring, in each of these homes in the next five years.

**Successful Attack**—Both fronts have struck pay dirt, but it is much easier to measure the results in new construction. The adequate wiring bureau keeps a record of the number of certificates (like the one above) awarded to contractors. The 12 months ending in June, 1955, showed an increase of 86 per cent over the previous 12 months, and the bureau expects that rate to increase.

But statistics cannot begin to account for the improvement in homes not certified. The competitive edge of builders adhering to adequate wiring standards has forced other builders to raise their standards.

**Second Fiddle** — Modernization has been slower to catch on. Since World War II, good contractors have preferred to work on new, clean jobs rather than tackle re-wiring jobs. But because this field has the greatest potential, it is being cultivated heaviest at present. Makers of appliances, such as air conditioners, are becoming alarmed by the number of units returned to the salesroom because they won't run on the wiring in the customers' homes.

This market is paying off. Twenty-three utility companies with modernization campaigns report they have done almost \$3 mil-

ion worth of rewiring, mostly in the last 18 months. The bureau feels that for each job reported, there may be at least three not reported.

**Long Way To Go**—The copper people feel the campaign is barely off the ground. Yet they can trace positive results. Anaconda says the response to its promotion has been far greater than anyone anticipated. In the last two years the company has sent out over 1 million pieces of direct mail for 800 contractors in co-operation with 100 utility companies and 100 distributors of electrical equipment.

Kennecott reports similar success. With such interest stemming from the consumer level, the companies know they aren't wasting their efforts. The result: A continued strong demand for copper from the wire and appliance industries.

### Scrap Exports Too High?

Steel mills say exports of scrap in the first half were too high; export dealers disagree.


The facts: Exports of scrap iron and steel in the period totaled 2,408,789 gross tons (not including shipments to Canada and Mexico). This was about 6 per cent of the scrap used domestically.

All last year only 1,111,417 gross tons were shipped overseas.

Exports to Canada and Mexico are generally considered as a part of the domestic market. The shipments are not large, totaling only 282,227 tons in the first half of 1955. Total shipments last year were 242,317 tons.

The matter is in the hands of the Bureau of Foreign Commerce. Look for it to be influenced by a survey of the country's potential supply of metallics for iron and steel production. It's being made by the Iron & Steel Division, Business & Defense Services Administration.

The division meets with its iron and steel scrap task group this week. Survey results are due this month. Meanwhile, the Bureau of Foreign Commerce continues to require scrap exports to be licensed, although there is no limit on quantity.



*By using school techniques, presenting all data . . .*

## GE Sells with Facts Forum

A DIFFERENT APPROACH to industry selling—one that brings products and customers together in an informal atmosphere minus sales pitches—is getting a warm reception from metalworking and machine tool people in Cleveland.

It's an idea of the local apparatus sales organization of General Electric Co. Groups of customers are invited to a classroom-like display room. Amidst operating samples pertinent to the group, both sides take a fresh look at specialized electrical problems and how to solve them.

**Some Skeptics** — When the "Facts Forum" was at the talking stage, some doubted that it could entice busy men to leave their work for the better part of an afternoon. "That has been no

problem," according to C. J. Miller, manager of component and intermediate distribution sales. "So far it has been harder to get them to leave at the end of the day."

The forum brings together products manufactured by 14 of GE's apparatus departments.

**No Distractions** — One of the hidden beauties of the system is that it gets the customer away from his office. After noncommercial talks by GE sales engineers, the meeting breaks up into small discussion groups around the displayed apparatus.

"In the few weeks we've been at it," confides a sales engineer, "we've learned a lot from our customers and have incorporated many of their ideas into the forum."





INCO builds iron ore processing plant near Copper Cliff, Ont.

## Canada: Trendlines Are Up

Business setbacks of 1954 are disappearing as demand for base metals, lumber and manufactured goods brings industry expansion, new jobs and a revived consumer market

**MINING AND CONSTRUCTION** are playing major roles in Canada's economic upswing.

Mining has parlayed strong export demand with stepped-up domestic requirements to boost its 1955 level some 13 per cent over last year's. New deposits also are in production.

Construction is shooting for a record year. Contracts awarded by the end of April were up nearly 40 per cent over 1954's. Bolstered by over 1000 more residential starts than in the first quarter of last year, an earlier Canadian government survey prediction (outlay

for new construction in 1955: \$4 billion) is coming true. This will give construction a 10 per cent gain over 1954. Housing starts will total 116,000.

**Exports, Too**—Not to be forgotten in the general upsurge is a 12 per cent increase in exports during the first four months of this year. Those to the United Kingdom rose \$80 million, or 46 per cent ahead of the same period a year ago. Exports to the U.S. were up \$55 million—an 8 per cent gain.

Manufacturing industries showed only small gains in the first two months of 1955. March saw the

official government index climb 3 per cent above that month's figure in 1954. Textiles led the parade with a 17 per cent gain. Non-ferrous metals, electrical apparatus, wood and paper products improved. May saw a healthy jump in car output. At 58,279 units, it represented a 52 per cent increase over figures for May, 1954.

**Bright Spot**—There are indications of more production in the machinery, tool and farm implement industries. Demand for steel from them and others is moving up proportionally.

The majority of manufacturers are again building up stocks of raw materials. Production schedules are being expanded. Government statistics show that inventories came up \$40 million the first three months of this year in contrast with a decline of \$58 million during that period in 1954.

**Prices** — Wholesale prices have been stabilized. Led by base metals, lumber and iron and steel products, the wholesale price index (1935-1939 = 100) went from 214.3 in October to 218.5 in April. Point of interest: This trend has not influenced the consumer price index.

As winter turned into spring, more "help wanted" signs began to appear. May statistics show that some 5.3 million people were employed—a 2.5 per cent gain over the previous year. While much of the hiring came from the outdoor fields of agriculture, construction and logging, manufacturing firms also began to expand payrolls.

**Province Report**—In British Columbia, one of the boom areas, manufacturing plants and machine shops have full production schedules. Shipyards are moderately busy. Small boatyards and engine repair shops have finished a good spring season and business activity is still high. Construction shows no signs of weakening.

With an eye to the future, James W. Coyne, governor of the Bank of Canada, predicts: By 1975 Canada's population of 15 million will reach some 23 million. Gross national product, at 1955 prices, will be doubled, meaning a GNP of some \$55 billion. And exports will decline from 24 to 20 per cent of the GNP by 1975.

Backlogs are increasing, but competition is keen as . . .

# Valvemakers Seek 10% Gain

IF SHORT NICKEL and copper supplies hold out, the valve industry will ship 10 per cent more orders than it did in 1954, reports James A. Dwyer, president, Valve Manufacturers Association.

The total will be about \$1.08 billion—a figure which compares with the previous high of \$1.02 billion in 1951 when the Korean War was a dominant economic influence.

**Kinds**—Most common types of valves are globe, gate and check. They are fabricated from gray and malleable iron, steel, stainless steel, brass and bronze. Valves are always "on the job" where the flow of liquids or gases must be regulated.

Standard globe valves often have 10 to 12 components and frequently more than one type metal. Even

with one-metal valves, parts like the stem, seat and body may have different metal specifications.

Valvemakers estimate that 20 to 25 per cent of their products go into new construction, with the balance going to maintenance.

**Sales** — Production is about keeping abreast of orders, but a mild backlog is developing, which is traceable, manufacturers explain, to more orders from distributors that had low inventories at the beginning of the year. When business improved sharply in the first quarter, they had to order heavily. Most valvemakers are able to deliver many sizes and types of standard items from factory warehouses. Special valves may take 60 to 90 days. Government orders are a small portion of today's volume.

Industries calling for new applications and expanded uses of valves include: Chemical, petrochemical, oil and gas, sewage disposal and commercial building. Civilian aspects of atomic power may have great potential.

**More Research** — Higher pressures and temperatures are the chief engineering problems confronting the industry. Research is under way. There is a trend toward cast steel.

Higher profits haven't materialized even though valvemakers see volume 10 per cent above last year's. Reasons: Increased labor and other costs, more competition and customer resistance to higher prices.

## Pipemakers Ask Tariff Hike

American manufacturers of cast iron soil pipe are being victimized by increased imports and unfair competitive practices by producers abroad, charges Cast Iron Soil Pipe Institute, Washington.


Soil pipe imports jumped from 219 tons in 1949 to 5729 last year. In the first four months of this year, the United Kingdom shipped soil pipe to U. S. ports at a rate 47 per cent over last year's.

In 1954, 80 per cent of the imports entered through the Pacific Coast. It costs no more to ship soil pipe by water from Glasgow, Scotland, to Los Angeles than by rail from Los Angeles to Tucson, Ariz.

American soil pipe is being undersold by up to 17.84 per cent, a critical price differential in an industry of tight profit margins.

Homer E. Robertson, executive vice president of the soil pipe institute, says it appears that there has been a violation of the Anti-dumping Act of 1921. He also charges that the government of Great Britain subsidizes scrap iron to its pipe foundries.

The institute has called for invoking the escape clause in tariff agreements to prevent serious injury to American producers; it says that plumbing jobbers in the Midwest and East already are receiving quotations on delivery of foreign soil pipe by ocean-going freighters to Great Lakes ports when the St. Lawrence Seaway is completed.



Assembly lines are full, but nickel and copper supplies dwindle



# Metalworking: First Half Profits Soar

	First Half Net Earnings			First Half Net Earnings	
	1955	1954		1955	1954
Allis-Chalmers Mfg. Co. ....	\$12,562,932	\$13,490,505	Metal & Thermit Corp. ....	\$989,480	\$740,922
American Radiator & Standard Sanitary Corp. ....	8,497,000	7,221,254	Midland Steel Products Co. ....	2,340,502	910,640
American Steel Foundries ....	2,352,338	3,085,022	Minneapolis-Honeywell Regulator Co. ....	7,240,898	7,019,778
Beryllium Corp. ....	475,823	198,193	National Acme Co. ....	1,376,761	1,857,771
Carborundum Co. ....	2,715,950	1,834,516	National Lead Co. ....	23,503,085	17,569,659
Caterpillar Tractor Co. ....	15,446,994	12,627,907	National Malleable & Steel Castings Co. ....	1,030,148	428,380
Central Foundry Co. ....	609,151	325,000	Packard-Bell Co. ....	362,131	334,830
Clark Equipment Co. ....	3,716,765	2,778,850	Pittsburgh Forging Co. ....	102,324	155,543
Cleveland Cliffs Iron Co. ....	3,343,206	1,456,332	Pittsburgh Screw & Bolt Corp. ....	482,416	461,163
Clevite Corp. ....	2,672,957	1,646,758	Republic Aviation Corp. ....	9,612,399	4,597,838
Continental Can Co. Inc. ....	10,289,395	9,131,932	Rheem Mfg. Co. ....	3,162,982	3,295,819
DeVilbiss Co. ....	507,807	309,602	Rockwell Spring & Axle Co. ....	8,681,889	5,692,815
Douglas Aircraft Co. ....	13,680,622	19,178,939	Signode Steel Strapping Co. ....	1,562,000	1,011,000
Eaton Mfg. Co. ....	7,397,402	5,206,031	Standard Forgings Corp. ....	372,580	172,860
Ekco Products Co. ....	2,321,071	2,195,678	Stanley Works ....	2,503,218	2,172,624
Ferro Corp. ....	1,273,049	866,065	Sylvania Electric Products Inc. ....	2,840,364	1,401,298
Gardner-Denver Co. ....	2,087,808	1,297,092	Thompson Products Inc. ....	6,768,149	6,490,502
General Electric Co. ....	101,892,000	93,856,000	Towmotor Corp. ....	701,066	387,398
General Refractories Co. ....	2,550,389	1,090,926	Underwood Corp. ....	543,375	280,525
General Steel Castings Corp. ....	902,586	1,074,190	United-Carr Fastener Corp. ....	1,903,686	1,068,754
Greenfield Tap & Die Corp. ....	476,369	260,349	U. S. Hoffman Machinery Corp. ....	1,206,102	370,163
Harbison-Walker Refractories Co. ....	3,395,157	1,535,285	U. S. Pipe & Foundry Co. ....	4,975,839	4,352,739
Houdaille-Hershey Corp. ....	1,404,891	1,235,661	Westinghouse Air Brake Co. ....	3,227,911	2,317,916
IBM Corp. ....	23,870,992	21,600,314	Youngstown Steel Door Co. ....	610,465	500,104
Jack & Heintz Inc. ....	962,000	797,300			

METALWORKING companies, across the board, are reporting increased earnings for the first six months of this year.

While a sprinkling of firms did not reach 1954 profit levels, most are record bound. Union Carbide & Carbon Corp.'s net income jumped to \$63.6 million from last year's first-half total of \$41.8 million. Sales improved 27 per cent and earnings soared to a 52 per cent gain.

**Cool Sales**—York Corp. had its best single quarter in the June period, racking up a net profit of \$1.5 million. Stewart E. Lauer, president, says: "The improvement stemmed from higher sales of packaged products through York's commercial division and contracts for heavier equipment sales."

**Other Side**—While Allis-Chalmers Mfg. Co. increased its sales during the first half (\$258.9 to \$267.0 million), its net profit dropped from \$13.5 to \$12.6 million.

General Electric Co. ran profits

up into nine figures. Net earnings were \$101.9 million, a 9 per cent increase over 1954's. Sales climbed 5 per cent to \$1.5 billion.

George Romney, president, American Motors Corp., reports that the corporation operated profitably during March, April, May and June. He declared a second quarter profit of \$1.6 million. Production of 56,036 Nash and Hudson cars in the June quarter compares with 23,476 produced during the same months last year. This has helped to offset losses for the first five months of American Motor's fiscal year (Sept. 30) when Nash and Hudson manufacturing programs still were being consolidated at heavy cost. Net loss for the company for the nine-month period, ending June 30, is \$4.5 million.

**Other Barometers**—The Council of Economic Advisers July report predicts the gross national product will reach \$400 billion by the end of the year. The second quarter

saw GNP soar to an annual rate of \$383.0 billion. Point to remember: Government purchases of goods and services for national security will only be about 10 per cent of this total.

General Motors Corp. had a record number of employees and an all-time high payroll during the first half of 1955, despite a 25 per cent drop in defense sales. Average employment was 635,786.

**Coming Back** — Monarch Machine Tool Co., coming out from under a 10.5-week strike during the second quarter, suffered losses of \$284,850, which compares with profits of \$994,300 during the first half of 1954. Jerome A. Raterman, president, says that the future is still bright. "Over 98 per cent of our employees have returned to their jobs, additional people have been added . . . and incoming business continues at a lively pace. Our backlog is at its highest peacetime level."

Metalworking outlook: Previ-

us sales and profit records will be erased by 1955 totals in hundreds of firms—large and small.

## Profits: Four-Year High

U. S. manufacturing profits are at the highest quarterly level in four years, states the *Quarterly Financial Report* of the FTC and SEC. Earnings after taxes for the first quarter of this year are estimated at \$3.3 billion, up 29 per cent over the first three months of 1954.

## Researchers Needed

Supply of qualified research scientists and engineers falls short of industry's needs

COMPANIES are having trouble carrying out research programs because of a lack of scientific and engineering personnel. A survey by the Bureau of Labor Statistics states that shortages are most severe in the aircraft, electrical equipment, petroleum, paper, food and primary metals industries.

Interviews with about 200 large companies, which employ well over half of the nation's industrial research scientists and engineers, show at least half are unable to hire enough researchers to meet their needs. One out of three companies report major or substantial shortages. Many companies not reporting numerical shortages emphasized their need for better qualified scientists and engineers.

**Needs**—The situation extends to all levels of experience and training. The greatest need is for personnel with experience or advanced degrees.

Demand exceeds the supply of qualified personnel in a wide range of fields—chemical, electrical, mechanical and aeronautical engineering, chemistry, physics metalurgy and mathematics.

A sizable number of firms have been forced to curtail projected increases in their research and development activities. The research director of a major petroleum company points out that it is a better policy to let positions go unfilled than to drop hiring standards below the high level necessary to obtain effective research workers.

# Steel Output, Sales High

	First Half Net Earnings		First Half Sales	
	1955	1954	1955	1954
Acme Steel Co. ....	\$ 3,395,301	\$ 1,970,149	\$ 53,338,031	\$ 41,245,457
Alan Wood Steel Co. ....	891,897	445,976	26,362,921	20,089,007
Allegheny Ludlum Steel Corp. ....	6,415,653	1,891,671	116,842,495	85,285,193
Armco Steel Corp. ....	28,020,053	19,001,116	329,521,667	267,071,172
Continental Steel Corp. ....	1,585,098	897,881	23,757,471	19,250,033
Crucible Steel Co. of America ....	6,285,475	1,312,395	114,829,465	84,555,951
Granite City Steel Co. ....	5,483,603	1,358,232	55,016,335	33,410,552
Inland Steel Co. ....	23,419,852	19,417,669	315,030,610	280,065,819
Pittsburgh Steel Co. ....	2,574,000	318,000	84,623,025	60,690,829
Republic Steel Corp. ....	41,137,071	24,791,945	570,684,791	432,609,292
Rotary Electric Steel Co. ....	1,889,895	964,866	26,510,638	15,594,931
Sharon Steel Corp. ....	4,488,002	644,262	83,636,451	47,972,633
U. S. Steel Corp. ....	177,877,960	93,851,114	1,968,160,985	1,670,842,389
Youngstown Sheet & Tube Co. ....	18,006,502	9,070,694	297,032,213	223,463,883

MIDYEAR FINANCIAL reports from the steel industry reveal: Sales and profits are approaching peak levels. Near capacity production will continue through the third quarter.

Reflecting the general optimism of the industry, John N. Marshall, president, Granite City Steel Co., reports: "Our first half results (see chart) represent our initial opportunity to operate recently expanded facilities at high levels; current earnings reflect the benefits of expansion on a co-ordinated basis. We are optimistic about continuing high operations and expect 1955 to set many records.

**Another Record**—F. M. Gillies, president, Acme Steel Co., says that June shipments amounted to over \$10 million, an alltime high for the company.

Republic Steel Corp. operated at 97.7 per cent of capacity in the second quarter. During the second quarter in 1954, its production was 69.9 per cent of capacity.

Inland Steel Co., while reporting new records for production, shipments, sales and earnings for the first half of 1955, is predicting that capacity operations will continue through the third quarter and considers the fourth quarter outlook "bright."

**Survey**—Meanwhile, the Ameri-


can Iron & Steel Institute is declaring that a 30-year comparison of net profits, based on data published by the First City Bank, New York, shows that the iron and steel industry's net profits usually have been 35th on a list of from 42 to 46 manufacturing industries. Reports compare net profit with net worth.

Completing its fiscal year on June 30, Colorado Fuel & Iron Corp., discloses a consolidated net income of \$10.9 million. This compares with a net income for the previous fiscal year of \$7.1 million. The steel producing plants operated at 78.3 per cent of capacity. The June quarter rate was 93.7 per cent.

Finishing with a strong second quarter, U. S. Steel Corp. registered the best net income (\$177.9 million) since the first six months of 1917 when net profits were \$128.0 million. Total for the first half of 1954 was \$93.8 million. Shipments of steel products in the second quarter of this year amounted to 7.1 million tons. This is the greatest tonnage shipped during any one quarter.

Outlook for domestic producers: A near capacity third quarter and a better than usual fourth will bring a record year to the steel industry.





Newport News Shipbuilding &amp; Dry Dock Co.

## Shipbuilding: Full Steam?

THE MARITIME Administration may trigger some \$756 million in ship construction and repair work during fiscal '56.

Clarence J. Morse, chairman of the Federal Maritime Board and head of the Maritime Administration, reports that government appropriations on hand or assured call for 85 new ships to be added to America's active merchant fleet and the repair of 189 military auxiliary vessels in the reserve fleet.

**Breakdown** — Private industry will shoulder about 58 per cent of the total cost—Uncle Sam will pay the rest of the bill. Some \$84 million already has been obligated for construction of 15 new ships or conversions.

Estimates for contracts, says the Maritime Administration, call for 53 ships or conversions involving expenditures of as much as \$500

million. "The 53 ships represent solid contractual prospects under the present subsidy legislation," says Mr. Morse, "and the Maritime Administration will make every effort to bring the entire 53 to the contract stage."

**Suppliers**—As about 50 per cent of the money spent on shipbuilding goes for materials, machinery and supplies used in the industry, suppliers can expect better times.


Interest in the roll-on roll-off ships has been spurred sharply by the Army's offer to take the first six of these vessels under a seven-year charter. Six shipping companies also are discussing the possibility of operating 30 of them. If these talks should end in orders, it would bring in an additional \$240 million. This amount was not included in Mr. Morse's "solid contractual prospects."

## Best Seller Revised

Copies of the 1955-56 edition of the government's best seller, The United States Government Organization Manual, are available for \$1 from the Superintendent of Documents, Government Printing Office, Washington 25, D. C. This 768-page book names all agencies and divisions of the government in the legislative, judicial and executive branches and describes their functions. It lists names and titles of some 4000 officials.


## Pay Hike for 2.1 Million

Washington authorities figure that the new \$1 wage rate will mean wage increases to an estimated 2.1 million workers. They are employed in many fields, but particularly in the lumber and textile industries. About 24 million workers will be covered by the law.




**Meet Robert W. Clark:** He is the new deputy director of the Scientific, Motion Picture and Photographic Products division of the Business & Defense Services Administration.

Mr. Clark is on leave from his duties as an official of Powers Regulator Co. From 1951 to 1953 he served with the Navy, helping to develop an industrial mobilization planning program. Mr. Clark may be contacted in Washington by calling Sterling 3-9200, Ext. 2911.



a hole here is a letdown...



a hole here is a lift

**Crucible Hollow Tool Steel Bars** can step up output on most any production line where ring shaped or hollow parts are made. Why? Simply because the hole is already there. There's no need for drilling, boring, or hole-sawing. And that's where you save production time, increase machine capacity, and avoid scrap losses!

Crucible's famous tool steel grades are available to you in hollow form, in almost any combination of OD, ID and length. In fact, your local Crucible warehouse can give you immediate delivery of these popular grades — KETOS oil-hardening, SANDERSON water-hardening, AIRDI 150 air-hardening, and NU DIE V hot-work tool steels.

Ask your local Crucible representative how you can save time and money by using Crucible Hollow Tool Steel Bars. Call him today, at our nearby Branch Office. *Crucible Steel Company of America, Henry W. Oliver Building, Pittsburgh 22, Pa.*

Visit us at Booths 830-832 Production Engineering Show, September 6-16, Navy Pier, Chicago.

**CRUCIBLE**

first name in special purpose steels

**Crucible Steel Company of America**




# 90 minute exasperating job

now accomplished easily in seconds

In the illustration below, the operator shows how easy it is to balance the grinding wheel on a CINCINNATI FILMATIC 10" x 72" Plain Hydraulic Grinder.



Automatic balancing control lever and indicator.



Here's how it works. Three steel balls are carried in a raceway in the wheel end of the spindle. As the spindle rotates while the elastically supported bearing assembly is unclamped, the balls are free to move and correct any unbalanced condition that may exist. Then the complete spindle and bearing assembly is locked in position to form a rigid mounting and retain all the advantages of FILMATIC bearings for precision cylindrical grinding.

Have you ever seen an operator balance a grinding wheel mount on conventional static balancing ways? It's a tedious operation, and may require 90 minutes or more to remove wheel mount, balance and replace mount. Cincinnati did something about this. They developed automatic grinding wheel balancing that does the job ten times more accurately and infinitely quicker and easier.

*This exclusive Cincinnati feature automatically balances the grinding wheel mount on the machine . . . within a few seconds . . . while the spindle rotates at its operating speed. This exclusive Cincinnati feature eliminates vibration and resultant chatter on the work . . . permits more effective stock removal . . . reduces wheel cost per work-piece.*

FILMATIC spindle bearings and automatic grinding wheel balancing constitute a team that just can't be beat for lower cost precision cylindrical grinding. Best of all, these features are standard equipment on CINCINNATI FILMATIC 6", 10"-L, 10", 14"-L, 14" and

16" Plain Grinders, and on 6", 10"-L, 10" and 14"-L Angular Feed Plunge Grinding Machines. Extra equipment other sizes. Write today for the complete balancing story. Ask for publication No. G-637-1.

**CINCINNATI GRINDERS INCORPORATED**


**CINCINNATI 9, OHIO**



# CINCINNATI

**CENTERTYPE GRINDING MACHINES • CENTERLESS GRINDING MACHINES  
CENTERLESS LAPPING MACHINES • MICRO-CENTRIC GRINDING MACHINES**



Publication G-637-1 explains the Cincinnati Automatic Balancing principle. Write for a copy.





## What a Suggestion Did for F. A. Lackner

ALTHOUGH he doesn't recommend or guarantee it as a good technique, Francis A. Lackner Jr. got his job by suggesting it.

Working part time handling return goods in the credit department of Cherry-Burrell Corp., Chicago, a thought came to him on how to reduce the number of returned items. He dropped a note in the suggestion box: "We should know more about our customers."

**The Job**—Management's response was immediate: "What are you going to do about it?"

The short note won for Mr. Lackner the post of manager of commercial research.

"Too few firms, particularly the smaller ones," he believes, "are doing market research or getting all they should out of their programs." He feels any company with sales of \$1 million or more can use market research to advantage. The department need not be large—Mr. Lackner has no full-time assistants, but he can call upon the field services for help.

Market research is a tool for management, Cherry-Burrell's research manager emphasizes. Effectiveness of any survey is dependent upon how well the information secured is understood by the person using it. Presentation is important—here's a tip: Keep your primary report short, one page if possible. Answer the ques-


tion which initiated the survey. Use one or two charts, each having no more than three lines.

**Transplanting**—Cherry-Burrell's chief customers are in the dairy industry. Sales are handled through 16 branch offices and a number of distributors. One activity which Mr. Lackner rates high in importance to his firm's sales program is that of discovering major weak and strong points of each sales branch. This is done by interviewing field salesmen and their customers. "It's an excellent way," he points out, "to transplant effective techniques from one branch to another. It's particularly effective when you're introducing new products or have products which may be selling well in one area and dragging in another."

The functions of market research generally are considered to be tied to product studies and sales forecasting, says Mr. Lackner. "But here at Cherry-Burrell we've noticed an important by-product—customer relations. Our program has developed to the point where our top management periodically gets out into the field to talk with our customers.

"Customers appreciate the fact that you're trying to supply their needs at the right time at the right price—that you're trying to get to know them better."





## 'BIG HOIST' QUALITY WITH 'SMALL HOIST' ECONOMY

A quick look at the Robbins & Myers "J" Hoist shows you the high degree of engineering and manufacturing precision that makes them so durable. The "J" Hoist, at prices competitive with the lowest, can give your handling problems a lift. Features like the following pay off in long service:

- 1—**BEARINGS** Nine oversize ball bearings; sealed bearing in hook block.
  - 2—**GEARS** Wide faced, precision cut, heat treated for tough service.
  - 3—**SHAFTS** Precision ground high carbon or alloy steel.
  - 4—**MOTOR** Specially built by R & M for hoist duty; 30 min., 55° C.
  - 5—**MOTOR BRAKE** Oversize shoes for long life, quick stops, no drift.
  - 6—**LOAD BRAKE** Weston-type, runs in oil bath.
  - 7—**FRAME** Single unit, aluminum alloy, ribbed for extra strength.
- "J" Hoist capacities range from 500 to 4000 lbs. Prices start at \$268.



☐ Send Bulletin 851-B

☐ Have representative call



VENTILATORS



MOYNO PUMPS



HOISTS CRANES



MOTORS



FANS

**ROBBINS & MYERS** INC.

SPRINGFIELD, OHIO

BRANTFORD, ONTARIO



n industry uses, synthetics pose no threat to mined gems as . . .

# Diamond Market Sparkles

IMPACT of General Electric Co.'s man-made diamond on the industrial market for mined "sparklers" won't be felt for a long time, predict trade spokesmen.

GE isn't saying a word. Going ahead with research, spokesmen will be greatly affected for years, if ever."

**Industry Analysis**—Athos D. Leveridge, executive manager, Industrial Diamond Association of America Inc., doubts "if the importance of the natural product will be greatly affected for years, if ever." He reports: "The work at GE is still at the research level. It hasn't produced a specimen larger than one-hundredth of a carat."

Mr. Leveridge feels that the cost of industrial diamonds is slight when compared with the work they do (making dies for drawing miles of wire, dressing and shaping grinding wheels, processing tools, etc.). Because of the cost factor, he declares: "If a synthetic diamond is produced at lower cost, the difference in price would be infinitesimal."

Others say that the artificial

diamond never will replace the natural stone in making single point tools used for dressing diamond wheels; nor will it be found suitable for making shaped tools in the near future.

**On the Other Hand**—Some regard artificial stones as a potential source for bort (rough, low-cost diamonds) which can be crushed into powder. It goes into diamond wheels and saws and lapping compounds. It's possible that synthetic diamonds can be made large enough to be used for cluster tools which require small diamonds—set and bonded together.

**In the Meantime**—Industrial diamond demand is running well ahead of last year's. Reasons: Expanded industrial activity, use of harder materials and the demand for better finishes.

Imports of industrial diamonds hover near 12 million carats annually. Some 70 U.S. companies use about two-thirds of the world's output.

**Added Impetus** — New machinery, developed for the production of intricate forms, is bringing ad-

ditional business. Maurice S. Dessau Co.'s Frank Blaine points out that a new field is the manufacture of germanium crystals (for transistors). Germanium must be sliced and diced. Diamond wheels for this work must be thin—0.006-in. and thinner.

Prices are stronger than they were a year ago. C. R. Myer, manager, abrasive division, Elgin National Watch Co., says: "Increased demand has naturally resulted in higher prices on raw material, but these prices are at a reasonable level. A year ago, considerable distress material was on the market. Today, the diamond market is balanced and healthy."

## Navy To Test Gas Turbine

A packaged 300-kw, 60-cycle generating set with a constant-speed gas turbine engine as a prime mover will be built by Solar Aircraft Co., San Diego, Calif.

A contract with the U. S. Navy Bureau of Ships calls for delivery by December, 1956. The unit must function automatically and be operative in 10 seconds or less.

The Navy wants to find out if gas-turbine-driven generator sets are practical for emergency and regular shipboard service.

## SBA Lends to 96 Firms

Loans to small businesses approved by the Small Business Administration in June totaled \$4,534,377. Categories covered manufacturing, wholesaling, retailing and service. The money is for the purchase of new equipment and expansion. In some cases, it will finance the processing of defense contracts.

About two-thirds of SBA loans have been made in participation with private banks.

## It's the AFL & CIO

A compromise: The name of the combined union formed by the AFL and the CIO will be: "The American Federation of Labor & Congress of Industrial Organizations."

The new name was announced jointly by George Meany, president of both the AFL and the new 15-million member amalgamated union, and Walter Reuther, head of the CIO.



Maurice S. Dessau Co. Inc.

Grinding accounts for much of the demand for industrial diamonds. Being decided here is tool needed to dress wheels that grind aircraft engine parts





## PRODUCTION PROBLEM?

**if you use flat-rolled steel  
talk to a specialist**

**PROBLEM** With present designs and manufacturing facilities, the auto industry needs wide coils of sheet steel with a minimum number of welds. These welds must be cut out before steel goes into the big presses—a costly, time-consuming process.

**SOLUTION** As a prime supplier to the automotive and other industries, Great Lakes Steel has developed facilities which now produce wide coils of steel in greater lengths ./. drastically reducing the number of expensive welds in each coil. Result: important fabrication savings for our customers.


**MORAL** Whether you make autos, appliances, or farm machinery . . . if it's flat-rolled steel, you can't lose by talking to Great Lakes Steel—specialists in flat-rolled production and application for 25 years.

**GREAT LAKES STEEL CORPORATION**  
Ecorse, Detroit 29, Mich. • A Unit of

**NATIONAL STEEL CORPORATION**



SALES OFFICES IN BOSTON, CHICAGO, CINCINNATI, CLEVELAND, HOUSTON, INDIANAPOLIS, LANSING, LOS ANGELES, NEW YORK, PHILADELPHIA, PITTSBURGH, ROCHESTER, ST. LOUIS, SAN FRANCISCO AND TORONTO



*Maker of Mercedes has cheap labor at home, but . . .*

## D-B's Debut Makes Sense

IN THE WORLD automotive scene, perhaps no name has the magic of Mercedes, the car named after the daughter of an early Daimler-Benz financial backer.

D-B was most recently in the news when two Mercedes 300 SLR cars, which were leading, were withdrawn following the one-in-a-million crash at Le Mans, France. The firm's success in racing includes victories in the 1955 Mille Miglia in Italy, the 1953 Mexican Road Race and many more. Yet behind its string of victories and its sports cars with speeds in excess of 175 mph lie engineering and production victories perhaps even more astounding.

**New Start**—During World War II, the German auto industry was largely bombed out. Daimler-Benz found 70 per cent damage at its Unterturkheim plant, 85 per cent at Sindelfingen, 80 per cent at Gaggenau and 20 per cent at Mannheim. The Berlin-Marienfelde plant in the American sector of Berlin also was badly damaged, and the remaining equipment was appropriated by the Russians.

As early as 1946, the Mannheim plant was back in operation, and last year D-B was third in German production, with 67,900 cars and trucks. Volkswagen's "People's Car," of course, was first with 242,000 units and GM's Opel was sec-

ond with 167,650 vehicles. Other German auto manufacturers include Ford, Auto-Union, Borgward, Goliath, Lloyd, BMW and Porsche. Together, their production this year is expected to be up about 10 per cent from the 680,000 units in 1954.

**Almost Half Exported**—The leading European automaker is still Britain, with France dropped into third place for the second successive year by the German effort. Forty-five per cent of German auto production is exported. Daimler-Benz has established assembly plants in Belgium, Argentina and India. Volkswagen is planning assembly plants in Australia and New Zealand, according to reports, but of particular interest is the planned Daimler-Benz assembly plant in the United States.

Formation of Daimler-Benz of North America Inc., with headquarters in Washington, is announced with the report that a factory will be built in this country at an undisclosed location. Neither the Mercedes-Benz sports cars nor passenger cars will be made here at this time, however. The principal functions of the new assembly and manufacturing plant will be concentrated in the diesel truck, marine and heavy duty industrial fields.

The decision of D-B to build an assembly plant in this country is interesting, since one of the biggest assets of the European automakers is low labor costs. Western Germany employs about 250,000 auto workers, and last year's average hourly rate was only 23.8 cents.

**Automation Minded**—In view of low labor costs, use of automation in the D-B plants is somewhat surprising. This is particularly notable in view of limited production. At the Unterturkheim plant near Stuttgart there is a new transfer line being installed by Ludwigsburger Maschinenbau which performs 18 milling, drilling, boring and facing operations in completely machining rear axle housings.

A few miles away at Sindelfingen, D-B produces sheet metal parts and assemblies with plenty

*(Material in this department is protected by copyright, and its use in any form without permission is prohibited.)*





D-B makes units such as the jeep-like UNIMOG and this UNIMOG S

of cost cutting techniques. A modern press department includes a couple of new Clearing presses from the United States.

An excellent flow of parts has been worked out for subassembly and final assembly. At Unterturkheim there is an up-to-date production line layout for machining parts and assembling engines, front end units and differentials. At Sindelfingen (photo, page 49) front and rear end assemblies are brought in from the sides to the main conveyor line fitted with locating fixtures. The single unit body and frame assemblies are dropped by an overhead monorail, with cars coming off the line completely tested and ready for final road testing before shipment.

**Plenty of Savvy**—The formation of Daimler-Benz North America Inc. is of particular interest because of the many types of vehicle and engineering features which could be introduced, as well as the competitive production know-how manifested by the firm. A good example is the fuel injection system used on the Mercedes 300 SL sports car.

The common complaint with fuel injection in this country, aside from the present cost penalty, is the difficulty in getting a uniformly correct fuel mixture for all engine speeds. So flexible is the 300 SL that the car may be accelerated in fourth gear from 15 mph

to 165 mph without flat spots.

Production of these 300 SL sports cars is only five units per day—four of its lighter and smaller counterpart, the 190 SL, are turned out daily. With most of these cars coming to the United States, it is conceivable that assembly in this country might be possible later on.

**Diesel**—Another interesting car produced by Mercedes is the 180 D, a diesel-engined version of its 180 sedan. Producing only 40 hp,

this engine delivers about 33 miles per gallon of inexpensive diesel fuel and cruises at about 70 mph. With judicious use of the gearbox, it will move along with traffic. Using an independent rear suspension, like all Mercedes cars, the little bearcat will stick in the corners like a Band-Aid on a hair man's arm. Over erratic road surfaces, wheel adhesion is incredibly superior to that of the straight axle.

As American automakers contemplate going to independent rear suspension, Mercedes is contemplating use of an automatic transmission. The coming together of design ideas could make some of these cars possible candidates for U. S. production in the future.

**Do-All**—Perhaps the best candidate of all, however, is a utility vehicle known as the UNIMOG. Designed as an all-round workhorse for farm and industry, this vehicle is a combination of truck and tractor, with a cargo body, four-wheel drive, locking differential (to prevent loss of traction if one wheel spins) and power takeoff front and rear. Power is supplied by the same engine as that of the 180 D. This vehicle does such jobs as plowing, digging potatoes, hauling logs, spraying grapes. It has about 90 basic uses.

Of the 12,000 units produced since D-B took over the vehicle in 1951, most have gone to about 60 foreign countries. A larger vehicle, the UNIMOG S, is built to the same general specifications. As a military vehicle, it will handle ten men and their equipment, cruising at speeds of 60 mph on the highway, or carry 1½-tons.

**Problems** — Material shortages continue to plague German automakers. Some cold-rolled sheet are imported from the United States. Developing a local market for autos, too, is a long and slow process for the auto is still a luxury. The high costs of fuel and auto taxes do much to continue this picture on the continent, which lacks a second-hand market to create turnover.

In this light, the move of Daimler-Benz to open a plant in the United States makes sense.

Cars named for Mercedes have considerable mechanical attractions which could get around.

## Auto, Truck Output

U. S. and Canada


	1955	1954
January . . .	780,780	594,467
February . . .	770,530	574,215
March . . . .	955,027	672,858
April . . . . .	936,994	676,269
May . . . . .	913,257	621,318
June . . . . .	825,031†	635,540
July . . . . .	805,000*	543,540
August . . . . .	523,799	
September . . . . .	364,441	
October . . . . .	312,078	
November . . . . .	616,395	
December . . . . .	761,954	
Total . . . . .	6,896,874	

Week Ended	1955	1954
June 25 . . .	191,890	140,695
July 2 . . . .	195,071	133,141
July 9 . . . .	167,288	106,169
July 16 . . . .	207,627	130,757
July 23 . . . .	210,740†	130,744
July 30 . . . .	197,000*	130,523



Source: Ward's Automotive Reports.  
†Preliminary. \*Estimated by STEEL.

*These are the features*  
that make **Verson**  
presses your best buy

After 30 years



**ALL-STEEL FRAMES**  
still set the standards  
for strength, rigidity  
and long life



For every action there is an equal and opposite reaction. The result in press design, is tool-damaging deflection.

Verson welded steel frame construction minimizes this problem because it utilizes high quality rolled steel plates . . . cut to shape, interlocked and welded into strong, rigid box sections. This construction capitalizes to the fullest rolled steel plate's advantages of greater uniformity and inherently greater strength. The extra strength and uniform quality of this steel plate assures the ability of the press to withstand high speed and repeated impact loads. Rigidity and resistance to

deflection is also rated higher than with other construction materials.

Originated by Verson over 30 years ago, all steel welded frame construction gives you top performance—cleaner stampings—better drawn sections—and substantial savings in tool dollars when you use Verson Presses.

The Verson all steel frame is just one of many reasons for selecting Verson Presses. We'd like to tell you more . . . just call or write. For specific recommendations, send an outline of your requirements.

Ask us about our new customized  
installment and leasing programs.

*Verson Press for every job from 60 tons up.*

**Verson**  
TRADE MARK

ORIGINATORS AND PIONEERS OF ALL-STEEL STAMPING PRESS CONSTRUCTION

**Verson ALL-STEEL PRESS CO.**


9318 S. KENWOOD AVENUE, CHICAGO 19, ILLINOIS • SO. LAMAR AT LEDBETTER DRIVE, DALLAS, TEXAS

MECHANICAL AND HYDRAULIC PRESSES AND PRESS BRAKES • TRANSMAT PRESSES • TOOLING • DIE CUSHIONS • Verson-WHEELON HYDRAULIC PRESSES

August 1, 1955



# USE YOUR IMAGINATION WITH Cross-Bay® Transfer Cars



**Infinitely variable** application of EASTON motor-driven Cross-Bay Cars, together with the possibility of special super-structure design, provides full scope for imaginative planning in this growing era of automatic handling.

**EASTON** Cross-Bay Transfer Cars were originally introduced to supplement overhead crane service in modern parallel bay plants and for movement of materials between plant buildings, storage yards and shipping platforms. Operating men everywhere were quick to see the adaptability of the Cross-Bay idea to

many other heavy handling and production problems.

**EASTON** Cross-Bay Cars, controls and special super-structures are custom-designed to meet individual requirements. Customers may specify electric motor, storage battery, gasoline-electric or gasoline-hydraulic power. Controls may be manual, electric (by push-button on the car or remote station) or electronic. EASTON Cross-Bay Cars can be built to capacities from 5 to 500 tons to fit any track gauge.

**Investigate** the EASTON Cross-Bay idea now for plant expansion and new plant programs.



**IN A TUBE MILL.** An interesting application of mechanized superstructure. Here several lengths of brass tubing are carried in a special superstructure on an EASTON Cross-Bay Car. The 2 horsepower electro-fluid drive, controlled from a walk-along push-button station on the side of the car, moves the 20-ton loads from station to station. A motor-driven down-folding gate provides automatic unloading.



**IN A STEEL MILL.** Here a push-button control panel is attached by a 10 ft. cable to a 100-ton capacity 3 horsepower electro-fluid EASTON Cross-Bay Car. As the operator walks along the car follows carrying two 50 ton slabs of steel.



**IN A STEEL WAREHOUSE.** Here a 12 horsepower gasoline-hydraulic EASTON Cross-Bay Car handles 25 ton loads of structural shapes in a steel warehouse. A comfortably seated driver operates the car at speeds up to 50 ft. per minute forward or reverse between plant buildings.



## OTHER EASTON CUSTOM-BUILT CARS FOR INDUSTRY

Annealing Furnace Cars  
Coal Charging Cars  
Core Oven Cars  
Gable Bottom Cars  
Hopper Cars  
Mine Cars


Motor Driven Cars  
Newsprint Cars  
Platform Cars  
Quarry Cars  
Rack Cars  
Rocker Dump Cars

Scoop Cars  
Skip Cars  
Steel Mill Cars  
Transfer Cars  
Transformer Cars  
Turntables

FORTY-ONE YEARS OF DEPENDABLE SERVICE IN THE DESIGN AND MANUFACTURE OF INDUSTRIAL TRANSPORTATION EQUIPMENT

# EASTON®

EASTON CAR & CONSTRUCTION COMPANY • EASTON, PA.

**STEEL's INDUSTRIAL PRODUCTION INDEX** (1947-1949=100)

\*Week ended July 23. Based upon and weighted as follows: Steel Output 35%; Electric Power Output 32%; Freight Car Loadings 22%; and Auto Assemblies 11%.

## Record-Smashing Becomes a Habit in 1955

INDUSTRIAL PRODUCTION in STEEL's index is clipping along at all-time highs. For two weeks in a row new records were set, the latest, 156 per cent of the 1947-1949 average.

Sparkling the jumps are soaring electrical output, almost double what it was in the base years; auto output, again, is almost double the 1947-1949 average.

**Boosters** — Steel production at its current rate of 90-per-cent-plus is another reason why the index is so far above last year's July average of about 120. Freight car loadings are climbing. They're running a little ahead of 1953's, about 18 per cent up from last year's, in recent weeks.

Late reports from metalworking trade associations show: Business in the industrial heating equipment industry seems headed for a record peacetime year, says Carl L. Ipsen, executive vice president, Industrial Heating Equipment Association.

**Hot Pace**—New orders received by the industry in the first six months are running 64 per cent ahead of those in that period last year. Industrial furnace makers received orders totaling \$42.4 million in the first half, compared with \$25.8 million in 1954's.

Induction and dielectric heating equipment is enjoying an even

bigger surge. In 1954, first-half orders were \$3.8 million; in 1955, they soared up 89 per cent, to \$7.1 million.

**Handling** — Materials handling equipment bookings in March hit one of the highest points ever recorded by Material Handling Institute Inc. There was a sharp slide in April, but still the month's

business was 10 per cent higher than the 1954 average. Now the trend is up again. May bookings were about 16 per cent above 1954's. The association calls the trend, "significantly optimistic."

**Building**—Construction, a year ago, was one of the sturdiest props under a sagging economy. This year it's in the forefront of a busi-

### BAROMETERS OF BUSINESS

#### INDUSTRY

	LATEST PERIOD*	PRIOR WEEK	YEAR AGO
Steel Ingot Production (1000 net tons) <sup>2</sup>	2,284 <sup>1</sup>	2,195	1,532
Electric Power Distributed (million kw-hr)	10,380 <sup>1</sup>	10,440	9,103
Bitum. Coal Output (1000 tons)	9,730	7,340	7,206
Petroleum Production (daily avg.—1000 bbl)	6,613 <sup>1</sup>	6,626	6,268
Construction Volume (ENR—millions)	\$360.7	\$578.4	\$259.3
Automobile, Truck Output (Ward's—units)	210,740 <sup>1</sup>	207,627	130,744

#### TRADE

Freight Car Loadings (1000 cars)	786 <sup>1</sup>	799	684
Business Failures (Dun & Bradstreet, no.)	218 <sup>1</sup>	224	188
Currency in Circulation (millions) <sup>3</sup>	\$30,287	\$30,416	\$29,854
Dept. Store Sales (changes from year ago) <sup>3</sup>	+10%	+13%	+5%

#### FINANCE

Bank Clearings (Dun & Bradstreet, millions)	\$21,388	\$19,658	\$20,730
Federal Gross Debt (billions)	\$276.3	\$274.3	\$270.9
Bond Volume, NYSE (millions)	\$19.3	\$20.4	\$19.6
Stocks Sales, NYSE (thousands of shares)	11,582	11,607	12,881
Loans and Investments (billions) <sup>4</sup>	\$84.0	\$84.1	\$81.1
U. S. Govt. Obligations Held (billions) <sup>4</sup>	\$31.7	\$31.8	\$33.5

#### PRICES

STEEL's Finished Steel Price Index <sup>5</sup>	207.76 <sup>1</sup>	207.76 <sup>1</sup>	195.87
STEEL's Nonferrous Metal Price Index <sup>6</sup>	240.2	239.4	215.8
All Commodities <sup>7</sup>	110.0	110.3	110.2
Commodities Other than Farm & Foods <sup>7</sup>	116.3	116.2	114.2

\*Dates on request. <sup>1</sup>Preliminary. <sup>2</sup>Weekly capacities, net tons: 1955, 2,413,278. 1954, 2,384,649. <sup>3</sup>Federal Reserve Board. <sup>4</sup>Member banks, Federal Reserve System. <sup>5</sup>1935-1939=100. <sup>6</sup>1936-1939=100. <sup>7</sup>Bureau of Labor Statistics Index, 1947-1949=100.





## Cincinnati Owners Report

- "processes 8 tons of parts daily"
- "120% more production"
- "tremendous time and labor saver . . . time saved, 75%; labor saved, 81%"
- "cleans and finishes 1000 parts per hour in 16' x 40' floor space"

**What do your  
part cleaning  
and painting  
operations cost?**

*too much? normal?  
don't know?*

Let a Cincinnati Cleaning engineer survey your requirements, give you a no-obligation report which may point to important savings. For cleaning, or for completely integrated painting systems, you can depend on CINCINNATI.


Write for **FREE** Information!

## Cincinnati

CLEANING AND FINISHING  
MACHINERY COMPANY, INC.  
2019 Hageman Street, Sharonville, Ohio




## THE BUSINESS TREND



	Prim. Mtls.	Fab. Prod.	Mach-inery	Elec. Mch'y.	Trans. Equip.
1954					
June	982	831	1,154	761	1,328
July	969	809	1,111	751	1,279
Aug.	967	820	1,095	766	1,238
Sept.	965	821	1,097	785	1,183
Oct.	989	829	1,093	800	1,249
Nov.	988	844	1,092	811	1,334
Dec.	1,002	843	1,106	809	1,375
1955					
Jan.	1,013	834	1,109	800	1,400
Feb.	1,032	844	1,125	803	1,426
Mar.	1,057	860	1,144	803	1,447
Apr.	1,076	868	1,164	804	1,462
May*	1,097	877	1,173	809	1,462
June*	1,117	877	1,175	809	1,458

\*Preliminary.  
U. S. Bureau of Labor Statistics.  
Charts copyrighted, 1955, STEEL.



	Prim. Mtls.	Fab. Prod.	Mach-inery	Elec. Mch'y.	Trans. Equip.
1954					
June	208	189	200	182	212
July	211	189	201	182	212
Aug.	210	190	201	181	213
Sept.	214	191	203	182	216
Oct.	213	192	203	184	216
Nov.	214	193	203	184	218
Dec.	214	194	204	184	219
1955					
Jan.	216	195	203	185	220
Feb.	215	195	204	185	220
Mar.	216	195	205	185	221
Apr.	217	195	206	186	220
May*	218	196	207	187	222
June*	219	195	208	186	219

\*Preliminary.  
U. S. Bureau of Labor Statistics.

ness upswing that is well on the way to making 1955 the most prosperous year on record.

Amid predictions of a building slump for this year, the industry has set record after record. The pace set in the first half is almost guaranteed through the second.

### Record Year for Building . . .

Here's why: Building contract awards in the first six months are over \$12 billion, 30 per cent above last year's record for the period (in 37 eastern states). Since contract letting precedes building: "The year will almost certainly establish a new record for construction put in place." So predicts Dr. George Cline Smith, economist for F. W. Dodge Corp., long established specialist in construction news and marketing.

"One of the most striking features of the situation is the broad base of the increased activity," observes Dr. Smith. "In addition, there has been no indication of a downturn in recent months."

### Fast Pace Continues . . .

Such large percentage increases over last year can't be expected to go on forever. But there hasn't

been any slowdown so far. Dr. Smith sees these plus signs in the construction picture: 1. A broad-based reversal of the post-Korea slide in industrial building. 2. Residential construction making big increases over a year ago, with much of the upward push coming from single family homes. 3. Every major category of construction showing increases over last year, most of them substantial. 4. The smallest increase was in educational buildings, up only 4 per cent; still, that category marked up a new first-half record of over \$1 billion.


The life in industrial construction surprised many experts who predicted a continued decline for this year. Awards have risen sharply since early in the year and now stand about 45 per cent ahead of 1954's first half. The \$850-million total is the highest for any first half since World War II, except 1951 when huge atomic energy contracts swelled the total.

### Metalworking Expands . . .

The upturn is spread over 18 of the 23 major manufacturing categories. The chemical industry is a big spender, but swelling the total are primary ferrous metals, fabri-


## ELECTRIC REFRIGERATORS

IN THOUSANDS OF UNITS



## HOUSEHOLD ELECTRIC RANGES

IN THOUSANDS OF UNITS



Total Factory Sales—Units

	1955	1954	1953
Jan. ....	381,197	344,401	325,186
Feb. ....	335,575	334,122	377,606
Mar. ....	392,774	330,641	365,498
Apr. ....	384,298	230,900	366,951
May ....	390,385	282,164	317,667
June ....	.....	303,127	343,114
July ....	.....	325,061	298,838
Aug. ....	.....	256,665	232,981
Sept. ....	.....	271,859	231,224
Oct. ....	.....	190,753	179,749
Nov. ....	.....	175,557	139,563
Dec. ....	.....	228,612	197,102
Total ....	.....	3,323,562	3,878,478

National Electrical Mfrs. Assn.

Total Factory Sales—Units

	1955	1954	1953
Jan. ....	136,663	101,870	88,145
Feb. ....	127,188	109,647	114,465
Mar. ....	130,180	115,393	130,788
Apr. ....	108,619	92,751	118,999
May ....	109,263	82,649	114,404
June ....	.....	85,854	113,086
July ....	.....	80,017	77,836
Aug. ....	.....	75,907	74,326
Sept. ....	.....	99,611	84,481
Oct. ....	.....	84,321	73,422
Nov. ....	.....	79,340	55,748
Dec. ....	.....	85,033	73,870
Total ....	.....	1,092,393	1,119,570

National Electrical Mfrs. Assn.

cated metal products, machinery and ordnance. But, as metalworking stands out among the increases, so it also does in categories that are spending less than last year: Primary nonferrous metals, aircraft, electrical machinery and equipment and miscellaneous transportation equipment.

Commercial building awards have gained spectacularly since last year, bulging over the \$1-billion mark in the first half for the first time in history. Awards for public works at \$1.7 billion set a new first-half record, 25 per cent ahead of those a year earlier. Highways are up 42 per cent; utilities, 38 per cent—far out in front of 1952's record first half.

## Recovery Is Genuine . . .

Business is good in two important metalworking centers, Pittsburgh and Cleveland. In the city of the Golden Triangle, activity is back near the year's peak after being badly dented by the short-lived steel strike, reports the Bureau of Business Research, University of Pittsburgh. That means it's near the best in two years.

In Cleveland, the Federal Reserve Bank says: "The continued expansion in business activity

throughout the first half of the year leaves no doubt that recovery from last year's recession is genuine. Construction, new car sales and electric power output set records. Unemployment declined steadily during the period."

## Trends Fore and Aft . . .

Railroad equipment buying keeps improving. Class I roads had 470 locomotive units on order as of July 1, compared with 385 a month earlier and only 124 a year ago, reports Association of American Railroads . . . Distributor-to-dealer movement of Admiral room air conditioners set an all-time record in the two weeks ending July 15; distributor sales were 51 per cent higher than any other two-week period . . . In bigger air conditioning units: Chrysler Airtemp records a 101 per cent increase in its air-cooled (waterless) models; the high construction rate and stepped-up sales efforts account for the gains . . . Factory sales of household vacuum cleaners in June were the highest for that month since 1950, and the half-year total was greatest since the second half of that year, reports the Vacuum Cleaner Manufacturers' Association. June sales were 241,665.

COOPER ALLOY

# CORPORATION BRIEFS

• Edited by GEORGE BLACK

## ENGINEERING DATA BOOK

Another section of the new Cooper Alloy catalog being readied by the Valve and Fitting Division is now available. Referred to as "Stainless Steel Engineering Data," this 16 page manual includes a variety of tables and charts of reference value for those who work with stainless steel valves, fittings, pipe, tubing or castings. Your copy is waiting.



## ADVANCED KNOW-HOW #1

The full story behind the Shellcast® stainless steel jet engine support rings being turned out by the Foundry Products Division of Cooper Alloy is told in Advanced Know-How Report #1. The problem, the specifications and the solution are covered in detail with text and photos. Write for your copy.



## PUMPING ETCH ROOM SOLUTIONS

Transferring acids and salt solutions used in the Etch Room of Litho Chemical & Supply Co. caused repeated pump failure and constant shaft seal maintenance. Five years ago a Vanton plastic pump (no stuffing box, no shaft seals) was put into daily service. Customer reports "no maintenance except lubrication." Full story appeared in Chemical Processing (July). Reprint available on request.




## QUIKUPL DATA POPULAR

Since the publication of the May issue of Newscast which featured this patented fitting, the requests for additional data have been pouring in. In case you missed the issue, may we remind you that copies are still available. Full engineering data, case histories and photographs are included, making it possible for you to see for yourself just how this unique stainless steel fitting can cut your installation and operating costs.




COOPER ALLOY  
CORPORATION • HILLSIDE, N.J.





# Don't Forget Materials Handling When Designing the Building



The foremost demand of a new factory building, whether for production or storage, is that its design and construction aid overall operating efficiency to the utmost. Thus, the building becomes more than just an enclosure, but is actually a vital part of the manufacturing process.

It is, therefore, imperative that the various steps entering into the making of an item be thoroughly considered when the building is designed. One of the most important of these concerns materials handling because this item often amounts from 25% to 50% of the total production cost, and, also, because it is plant-wise in nature.

Regardless of what handling methods are deemed best, overhead cranes or Tramrail, roller or chain conveyors, floor trucks, etc., the building design, size and construction usually has a tremendous bearing on the ultimate handling efficiency secured. Building clearances, floor construction, column locations, aisleway allowances and other factors must be considered for the different handling methods for most satisfactory results.

For initial economy in installation, for most satisfactory operation and highest efficiency, plan for materials handling when you design the building. **Do not make materials handling an afterthought.**

**CLEVELAND TRAMRAIL DIVISION**  
THE CLEVELAND CRANE & ENGINEERING CO.  
7873 EAST 284TH ST. WICKLIFFE, OHIO

## GET THIS BOOK!

BOOKLET No. 2008. Packed with valuable information. Profusely illustrated. Write for free copy



# CLEVELAND TRAMRAIL

## OVERHEAD MATERIALS HANDLING EQUIPMENT



**DANIEL J. YOUNGERMAN**

... Clark Equipment div. purchasing agent

**GEORGE CAMERON**

... Colonial Broach engineering dir.

**CURTIS B. HOFFMAN**

... Brush Electronics v. p.-sales

Clark Equipment Co. appointed Daniel J. Youngerman purchasing agent for its construction machinery division, Benton Harbor, Mich. He was assistant purchasing agent of Studebaker-Packard Corp., where for 12 years he was in charge of truck division purchasing.

James E. Thompson was made sales assistant, Horton Chuck Division, E. Horton & Son Co., Windsor Locks, Conn. He was sales supervisor with Union Mfg. Co. Robert E. Giauque was made works manager and chief engineer, responsible for two manufacturing divisions, Horton Chuck and Gabb Special Products Division.

Howard E. Chilcoat will retire Sept. 1 as vice president-general sales manager, Townsend Co., New Brighton, Pa., and will transfer to Santa Ana, Calif., to fill the new post of West Coast sales manager. He will retain his vice presidency. George A. Bentley will become general sales manager. Robert E. Casner becomes central division manager in Detroit, and is replaced as general superintendent at the New Brighton plant by John W. Hernlund, whose title will be works manager.

Johnston Mfg. Co., Minneapolis, elected R. J. Shannon president and W. E. Johnston chairman of the board.

George Cameron was made director of engineering and Gordon Cook supervisor of broach engineering at Colonial Broach & Machine Co., Detroit. Mr. Cameron was co-owner of Cameron & White Co., engineering firm.

Kenneth Bryan, formerly with Babcock & Wilcox Co., was named superintendent, electric furnace melt shop, Northeastern Steel Corp., Bridgeport, Conn. Charles P. Hammond will be general superintendent, rolling mills, Bridgeport works.

Charles H. Schiller was made administrative assistant of sales, American Steel & Wire Division, Cleveland, U. S. Steel Corp. He is succeeded as manager of commercial research by Elliott D. Jones. William P. Keefe was made assistant manager-commercial research.

Charles Kuhn was made sales manager, products division, Hills-McCanna Co., Chicago. He was vice president-sales of Fansteel Metallurgical Corp.

Francis G. Kredel, superintendent of the 10 and 12-in. bar mills at the Cleveland steel plant of Republic Steel Corp., was named chairman of the bar mill committee. He is succeeded by E. W. Carlson, former assistant bar mill superintendent at Chicago. Mr. Kredel succeeds B. F. Handloser, retired.

Curtis B. Hoffman was elected vice president-sales, Brush Electronics Co., Cleveland, a division of Clevite Corp. In addition to administrative duties, he will direct the marketing of industrial and research instruments, electronic components and electronic memory devices.

T. J. Winter was made assistant sales manager, Wright Hoist and Ford Chain Block Divisions, American Chain & Cable Co. Inc., York, Pa. He joined the Wright Hoist Division in 1947 and most recently was district sales manager in the Detroit-Cleveland area.

Carl E. Rowe was elected vice president-manufacturing and William J. Brinkman vice president-engineering, Pressco Casting & Mfg. Corp., Chesterton, Ind.

Robert Duffy was made Milwaukee district sales manager, Lindberg Engineering Co. He succeeds Robert Onan, now president of Waukeet Engineering Co., Milwaukee.

Sterling C. Nichols was appointed general sales manager, Steel Fabricators Co., Cleveland. He has been sales representative since 1949.

Tom Davidson was made sales manager of O & M Machine Co. Inc., Los Angeles.

Ken R. Gerlach, formerly with Sperry Gyroscope Co., joined Bogue





**SIDNEY G. YOUNG**  
... Lewis Rolls sales manager



**WILLIAM J. BLASHILL**  
... Udylite Div. manufacturing mgr.



**LORING S. BROCK**  
... U. S. Steel product dev. director

Electric Mfg. Co., Paterson, N. J., as executive vice president.

**Sidney G. Young** was appointed sales manager for **Blaw-Knox Co.'s** Lewis Rolls Department, Pittsburgh. He succeeds **Glen McDowell**. Mr. Young joined Blaw-Knox in 1948 after ten years with U. S. Steel Corp. at Gary, Ind., and the Irvin Works.

**Delta Power Tool Division**, Rockwell Mfg. Co., Pittsburgh, appointed **Byron E. Coon** sales promotion and merchandising manager and **John P. MacCrossen** regional manager, western region. Mr. MacCrossen, who succeeds Mr. Coon, was San Francisco district sales manager. He continues headquarters in Oakland, Calif. Mr. Coon moves to Pittsburgh.

**Aluminum Co. of America**, Pittsburgh, named **Lewis P. Favorite** manager of product sales; **Frederick J. Close**, manager of market development; and **W. S. McChesney**, manager of industry sales.

**George Kelley** was made manager of heating and air conditioning, **Day & Night Division**, Carrier Corp., at Monrovia, Calif.

**John H. Island** and **Kenneth E. Whitekettle** were made sales managers for Baltimore Brush Division, **Pittsburgh Plate Glass Co.**, Pittsburgh. Mr. Island will supervise the paint and varnish brush department. Mr. Whitekettle heads power driven brushes.

**William J. Blashill** was named manager of manufacturing and **Louis J. Minbiole Jr.** sales manager, **Udylite Division**, Udylite Corp., Detroit. **L. Eugene Drury** was made facilities manager.

**V. C. Warfield** was made western division merchandise manager for **American Blower Corp.**, with headquarters in Chicago. He will service jobbers in the Chicago, Minneapolis, Milwaukee, Rock Island, (Ill.) South Bend, Ft. Wayne and Indianapolis (Ind.) areas.

**Brainard Steel Division**, Sharon Steel Corp., appointed **John M. Magde** manager of its Larchmont avenue plant at Warren, O. He was plant manager of the Griswold street plant.

**Clayton A. Kolstad**, former production planning manager, was appointed controller of **Sargent & Co.**, New Haven, Conn. He is succeeded by **William Larkin** who was purchasing agent. Mr. Larkin is responsible for all production planning and purchasing. **Walter C. McCaughey** was made purchasing agent, **George Ulrich** a buyer in the purchasing department.

**Jerome A. Winston** was made rolling mill superintendent at Bessemer, Ala., for **Tennessee Coal & Iron Division**, U. S. Steel Corp.

**George H. Buchner** was made director of contracts and spare parts for **Northrop Aircraft Inc.**, Hawthorne, Calif.

**Loring S. Brock** was made director product development division, commercial department of **United States Steel Corp.**, New York, responsible for commercial phases of product planning and development of new products. These activities were temporarily under the direction of **Robert C. Myers**, director of market development.

Appointed divisional superintendents at **Granite City Steel Co.** Granite City, Ill., are: **Harold A. Muttach**, coke ovens, blast furnaces and open hearths; **Clarence R. Mitchell**, rolling mills; and **Russell G. Solomon**, finishing.

**J. A. Rishel Jr.** was made general sales manager, **Amana Refrigeration Inc.**, Amana, Iowa. He succeeds **E. L. Hinchliff** who relinquished the post to become special merchandising consultant for the company. Mr. Rishel joined Amana in May as a special representative. He was formerly general sales manager of **Deepfreeze Appliance Division**, Motor Products Corp.

**P. C. Will**, who resigned as vice president-engineering of **Hydro-Blast Corp.**, is associated with **Edwin Hancock Engineering Co.**, Chicago.

**James H. Joyner** was made Pacific Coast sales manager, **Quaker Pioneer Rubber Mills**, division of **H. K. Porter Company Inc.**, San Francisco.

**Frank V. Stauffer** was made De-

Users of tubing for cylinder applications—  
now you can have this new...

## J&L Cold Drawn ELECTRICWELD

Tubing with a **Special Smooth ID Finish**

Reduces your overall production costs in applications like these...

- cylinder tubing
- hydraulic and pressure tubing
- shock absorbers
- ordnance components

This new drawn-over-mandrel grade tubing with its mirror-like inside surface finish is today busy helping manufacturers reduce or entirely eliminate costly machining on many applications and is being substituted for more costly types of steel tubing. For example, it may be used, without inside honing, for many cylinders through which plungers are passed.

J&L Cold Drawn ELECTRICWELD Tubing with a *Special Smooth* ID finish combines the physical advantages imparted by today's modern electric welding techniques with those of cold working. It withstands high internal hydrostatic pressures, carries heavy torsion loads, resists high-frequency vibration, and offers a favorable weight-to-strength ratio for applications in which loading occurs in all directions.

J&L Cold Drawn ELECTRICWELD Tubing can be furnished in its three specifications in OD sizes from  $\frac{3}{8}$ -inch to 2 $\frac{1}{4}$  inches and in wall thickness from 20 to 10 gage, 0.035 and 0.134-inch respectively.

This new booklet provides the information you need... specifications... tolerances... chemistry... mechanical properties... annealing... finishes.

Send for your free copy today!

# J&L STEEL

Jones & Laughlin Steel Corporation  
Dept. 404, 3 Gateway Center, Pittsburgh 30, Pa.

Send me a copy of your new Cold Drawn ELECTRICWELD Booklet.

Name

Title


Company

City  Zone  State





J. ROBERT JONES



JOHN R. JOERGER

... Kearney & Trecker executive sales positions

troit district manager for Bellows Co.

At Kearney & Trecker Corp., Milwaukee, J. Robert Jones was made general sales manager and John R. Joerger sales manager of a new aircraft machine division. Mr. Jones continues as sales manager, standard machine division.

Arthur H. Luchs was elected vice president in charge of western sales for Dickey Industries, Cleveland. He has headquarters in San Francisco.

J. O. Slaybaugh was made Cleveland division manager, Diversey Corp.

Hugh J. McKane, Atlanta, was made southern district manager, Bay State Abrasive Products Co.

H. Gordon Smith, executive vice president, United States Rubber Co., New York, has also been elected vice chairman of the board and chairman of the executive committee. Chester J. Noonan, vice president, was elected a member of the executive committee.

Robert W. Dibble succeeds Allan J. Peterson, retired, as manager of general sales, International Harvester Co., Chicago. He is succeeded as assistant manager-general sales by B. H. Bagby.

Carl E. Haugh, formerly with Hydropress Inc., joined Continental Foundry & Machine Co., Pitts-

burgh, in sales for rolling mills and heavy machinery.

John F. Dockum and Brooks M. Dyer head new sales groups for Columbia-Southern Chemical Corp., Pittsburgh. Mr. Dockum is manager of chrome chemical sales. Mr. Dyer will supervise the calcium chloride sales group.

Leland Electric Co., Dayton, O., division of American Machine & Foundry Co., elected Rex D. Marsh vice president-sales and Walter T. Buhl vice president in charge of engineering and manufacturing. Mr. Marsh joined Leland in 1953 as sales manager and was formerly



REX D. MARSH

president and a director of the Canadian subsidiary, Bowser Inc. Mr. Buhl, a consulting engineer for the last four years, was formerly research director at Whirlpool Corp.

Paul E. Forsythe was appointed vice president-general manager, Hallidie Machinery Co., Seattle. For the last ten years he was manager of the commercial and engineering department, Western Gear Works.

Kenneth V. Dawson was named sales engineer for Kaiser Steel Corp.'s Napa, Calif., fabricating plant. For the last two years he was commanding officer of the San Francisco branch office, Office of Naval Research.

Herbert Tramer was made a vice president at Chicago for Federal Enameling & Stamping Co. He was director of sales at Belmont Stamping & Enameling Co.

Purchasing appointments for Mercury Division, Ford Motor Co., Detroit, include: S. A. Cornell, assistant general purchasing agent; S. T. Myres, purchasing agent, machined and service parts department, E. W. Reynolds assistant purchasing agent and James Veras senior buyer in the department; C. M. Bowen, assistant manager, purchase analysis department and D. B. Bachman supervisor in purchase analysis.

Wallace T. Gray was made gen-



WALTER T. BUHL

... Leland Electric Co. vice presidents

# the **NEWEST** member of a Famous Family



## **3" HORIZONTAL BORING MILLING and DRILLING MACHINE**

### **PENDANT CONTROL**

*Complete machine control*  
from a movable station for feed  
and speed selections,  
directional feed and traverse for  
Spindle, Head, Table and Saddle

### **ADDITIONAL FEATURES**

Both Screw and Rack  
Feed to the spindle


Massive 4-Way Bed, Head,  
Headpost and Rear Post  
for rigidity

Spindle Speed up to 2000 R.P.M.

Replaceable Ways, chrome  
hardened, on Bed and Saddle

Optical measuring equipment  
for head and table (optional)

FOR FULL INFORMATION  
CALL YOUR NEAREST  
BULLARD SALES OFFICE, OR  
DISTRIBUTOR OR WRITE . . .



**THE BULLARD COMPANY** | BRIDGEPORT 3, CONNECTICUT



# FISHING FOR WAYS TO CUT ELECTROPLATING COSTS?

KNICKERBOCKER FOUND IN TEST THAT IT CAN

- Cut cost of solution correction
- Cut Power Costs by 1/3 or Boost Production!

WITH

## "PLUS-4" ANODES

(PHOSPHORIZED COPPER)

The Knickerbocker Electrotype Co. of New York filled its Tank No. 1 with Anaconda "Plus-4" PhosphORIZED Copper Anodes, set up Tank No. 2 as a control, using only electric tough pitch copper anodes. Solution concentrations are tested and corrections made weekly—and consistently Tank No. 1 with the "Plus-4" Anodes has shown the better record.

After five months of testing, Mr. William Welsh, foreman of the plating department, expressed his satisfaction with "Plus-4" Anodes and made this statement: "Using regular anodes, we must hold our cathodes at least 4½ inches from the anodes. This is necessary because the sludge from the old anodes will fall on our work and cause roughness. With the new 'Plus-4' Anode, there being no loose sludge, we could work much closer—only 3 inches away—which would reduce the resistance by ⅓—which would in turn reduce our power costs by about the same proportion. This would also reduce the heat generated by a like proportion."

Mr. Welsh explained that because Knickerbocker uses thermoplastic molds, heat is important—the tanks must run no higher than 95F to prevent warping. As an alternate to reducing power, he explained that he could use the same power and run plates through faster, increasing production.

65142

### WHY PLATING WITH "PLUS-4" ANODES COSTS LESS!

- + 1 no anode sludge (no "bagging" or diaphragms required)
- + 2 no copper "build-up" in solution
- + 3 smooth, heavy cathode deposits
- + 4 up to 15% more cathode deposit per anode

**SEE FOR YOURSELF**—For details on how you can get a test supply of "Plus-4" Anodes sufficient to fill one tank, write to The American Brass Company, Waterbury 20, Conn. In Canada: Anaconda American Brass Ltd., New Toronto, Ont.

### "PLUS-4" ANODES

A PRODUCT OF

# ANACONDA®

made by The American Brass Company

For use under Patent No. 2,689,216

Here is a "Plus-4" "fish" pulled out of a Knickerbocker tank. It measures .170" at the thickest part at the bottom and .058" at the thinnest point. This remnant of a 40-lb. anode weighs only 2 lb., 3 oz. "Plus-4" Anodes corrode this way regularly—another indication of the superior job they can do for you.



**JACK F. ANSCHUETZ**

... Hamilton press sales mgr. at B-L-H

ral works manager, Leece-Neville Co., Cleveland.

Jack F. Anschuetz was made sales manager for Baldwin-Lima-Hamilton Corp.'s Hamilton presses. He was headquarters at Hamilton, O. He was sales manager for Clearing Machine Corp.'s Hamilton division.

Samuel C. Wagner joined Kaiser Aluminum & Chemical Sales Inc., as assistant to the general sales manager in its Chicago sales headquarters office. He formerly was assistant manager of sales in the sheet and strip division, Inland Steel Co.

Robert P. Gibson was made assistant to the superintendent of the masonry department at the Buffalo plant of Republic Steel Corp.

V. M. Koenig was appointed manager of stainless steel sales, Rotary Electric Steel Co., Detroit; David Cooke succeeds him as head of Rotary's eastern sales office, Newark, N. J.



**EDGAR D. FLINTERMANN**

... Detroit Gray Iron Foundry v. p.

Edgar D. Flintermann was elected executive vice president, Detroit Gray Iron Foundry Co., Detroit. He recently resigned as president of Misco Corp.

Joseph E. Seibold was named manager of the merchandising division, Worthington Corp., Harrison, N. J. He succeeds J. O. Glenn who resigned.

R. C. Roderick was appointed assistant to the manager of manufacturing, Fruehauf Trailer Co., Detroit. For last six years, he was with A. O. Smith Corp., as manager, railroad products division.

Willis R. Slaughter was elected a vice president of W. L. Maxson Corp., New York. A brigadier general, USA, ret., he joined Maxson in July, 1954 as plans and programs adviser.

Forrest Stretmater was promoted to chief metallurgist from assistant chief metallurgist at Servel Inc., Evansville, Ind.



**GEORGE H. GARRAWAY**

... mfg. dir. at New York Air Brake

George H. Garraway was appointed director of manufacturing, New York Air Brake Co., New York. Before joining the company in June, 1954, he was vice president of Orr & Sembower and prior to that was chief engineer, Quimby Pump Division, H. K. Porter Company Inc.

Goddard & Goddard Co., Detroit, made H. C. Henderson executive vice president and treasurer; L. H. Goddard, vice president-marketing; S. H. Grattan, vice president-engineering; and W. H. Fritz, vice president-manufacturing.

J. A. Zurn Mfg. Co., Erie, Pa., announces four promotions: Thomas A. Kennedy, assistant to the president; John Henry Zurn, vice president-general manager; Albert A. Baker, vice president-sales; and John L. Derby, director of manufacturing.

Wilbur Deutsch was appointed sales manager, Lectroetch Co., East Cleveland, O.

## OBITUARIES...

George J. Belknap, 64, former vice president and general manager, Belknap Mfg. Co., Bridgeport, Conn., died July 16.

Meldon S. Spire, retired chief experimental engineer, Syracuse Shilled Plow Works, Syracuse, N. Y., died July 12.

William F. Zimmerman, 71, executive vice president, Gould & Eberhardt Inc., Irvington, N. J., died July 9.

Alton W. Healy, 65, senior member of the sales staff, Continental Screw Co., New Bedford, Mass., died July 12.

Michael J. Wynn, 56, manager of

Jersey City, N. J., plant, American Can Co., died July 13.

Raymond D. Brown, 55, president, Eastern Steel Tank Corp., Flushing, N. Y., died July 20.

Frank C. Mahnke, 85, purchasing agent and office manager, Gilbert & Bennett Mfg. Co., Blue Island, Ill., died July 13.



# Pressmaker Expands

## Clearing Machine Corp. to spend \$3 million for construction and equipment

CLEARING Machine Corp., a division of U. S. Industries Inc., Chicago, has launched a \$3-million expansion program. It calls for new facilities scheduled to be in operation within three months.

A building is being built next to the firm's Chicago plant. Over 61,000 sq ft, it is designed for expansion. Considerable new equipment will go into it, including five overhead cranes up to 75 tons of capacity to handle huge weldments fabricated there.

Plans also call for the purchase of milling machines and other major machine tool equipment.

**Demand Soars** — Clearing Machine is a major manufacturer of industrial presses. John I. Snyder Jr., chairman of the board and president of U. S. Industries Inc., stresses the need for speedy expansion, pointing out that demand for Clearing's products is at a record high. Plans of many of its customers call for greater use of modern cost-reducing machines and increased production.

Clearing presses range from 45-ton units used to draw small stampings to giants capable of drawing automobile tops or bending keels for ships.

## Improves Tool Bit Department

Vanadium-Alloys Steel Co., Latrobe, Pa., has begun production in a new integrated department designed to meet the growing demand for fine-finish tool bits. Each stage of tool bit manufacture from the hot-rolled bars to the ready-for-shipment bits is located in the new building adjacent to the firm's main plant.

## Westinghouse Unveils Plant

Westinghouse Electric Corp., Pittsburgh, has unveiled its factory at Cheswick, Pa., designed to produce parts for atomic power plants. Skilled machinists are manufacturing "canned" motor-pumps that send radioactive fluids through the hermetically-sealed

systems of nuclear power plants. "Canned" motor-pumps currently in production range in size from ½-hp or 5 gal per minute up to 300 hp or 4000 gal per minute. Weight ranges from 60 lb to nearly 3½ tons. Some parts are worked to tolerances of 3 to 5 millionths of an inch.

## Koppers To Build Coke Ovens

Inland Steel Co., Chicago, awarded a contract for construction of a battery of 87 coke ovens to Koppers Co. Inc., Pittsburgh. The project is part of a multi-million dollar construction program (STEEL, May 23, p. 166) for the company's Indiana Harbor, Ind., Works. It will increase the plant's coke-making capacity 21 per cent to 2,598,000 tons.

Koppers will design and build additional coal chemical facilities as well as equipment for handling coal and coke.

The new coke battery will be the seventh at the plant. Its output will supplant coke purchased.

It also will increase the company's production of coal chemicals, such as tar, toluol, benzol, naphtha, pyridine and ammonium sulphate.

Engineering work has been started. The construction schedule calls for completion in a year.

## Indiana Gets Stamping Plant

Fisher Body Division of General Motors Corp., Detroit, will build a stamping plant near Marion, Ind. This is the second new body plant to be included in GM's \$500-million capital expenditure program. James E. Goodman, general manager of Fisher Body, announced (STEEL, July 11, p. 73) that a stamping plant would be built at Mansfield, O. The Marion plant will contain about 1,776,000 sq ft of floor space.

## Snyder Tool Enlarging Plant

Snyder Tool & Engineering Co., Detroit, has started work on a \$500,000 expansion program. To make automation machines and special machine tools, it will increase floor space 50 per cent. Many transfer-type machine tools that the company has delivered recently to the automotive industry have

been up to 180 ft long and cost more than \$1 million. H. N. Maynard, president, predicts that similar machines in the next few years will be up to 250 ft long.

## Steel Castings Firm To Move

Alloy Steel Casting Co. is preparing to move from Willow Grove Pa., to its new plant at Southampton, Pa. New equipment and facilities will double its capacity for the production of sand castings made of corrosion and heat-resistant stainless steel.

## Bearings Firm Doubles Space

New Hampshire Ball Bearings Inc., Peterboro, N. H., is doubling manufacturing space with a \$350,000 plant. The firm assembles small precision bearings used in fine instruments.

## Rheem Enters New Field


Rheem Mfg. Co., New York, producer of a wide range of products, including steel shipping containers, is entering the reconditioned drum field. The company will begin operations in the San Francisco Bay area and in Southern California.

## Timken To Buy Equipment



Timken Roller Bearing Co., Canton, O., will expand its Bucyrus, O., plant facilities at a cost of about \$850,000. This appropriation brings the firm's expenditures for expansion of that plant to more than \$10 million. Equipment scheduled for purchase under the new appropriation will be ordered in the near future.

## Borg-Warner Diversifies

Borg-Warner Corp., Chicago, has entered the materials handling field by acquiring Brooks Equipment & Mfg. Co., Knoxville, Tenn., maker of hoist-bodies for standard truck chassis and containers for all kinds of bulk loads. The Brooks firm is operated as a subsidiary under the direction of J. H. Ingersoll, president of the new firm as well as Ingersoll Products Division, Ingersoll Kalamazoo Division and Ingersoll Conditioned Air Division. R. F. Schutz, manager of the In-



**Dependability  
is a must... so**



**RADIOGRAPHY  
keeps its eye on  
production**

**Radiography...**  
*another important example  
of Photography at Work.*

SALES of outboard motors have gone up dramatically. New high power, smoothness, and quiet have all helped. But chief of their outstanding virtues is dependability.

This quality is guarded by radiography. It insures soundness of castings—sees that weakness is not lurking in a hidden flaw.

Radiography cuts cost, too, when x-rays reveal unsatisfactory castings before machining is begun.

Today radiography is playing a greater and greater role in good foundry operations. It frequently points the way to better casting methods... makes sure only sound castings are delivered.

If you'd like to know how radiography can help you, get in touch with your x-ray dealer. Or, if you like, write us for a free copy of "Radiography as a Foundry Tool."

**Kodak**  
TRADE-MARK

**ASTMAN KODAK COMPANY, X-ray Division, Rochester 4, N.Y.**



# THE CYCLEMASTER

## UDYLITE'S NEW AUTOMATIC PLATING MACHINE

OFFERS • HIGHER PRODUCTION  
PERMITS • GREATER VARIETY OF PROCESSES  
USES • MINIMUM FLOOR SPACE

*WATCH FOR IT!*



THE  
**Udylite**  
CORPORATION  
DETROIT 11, MICHIGAN

gersoll Kalamazoo Division and vice president and manager of Wausau Mfg. Co., subsidiary of Borg-Warner Corp., is vice president and general manager of Brooks Equipment.

### Union Twist Drill Makes Change

Union Twist Drill Co., Athol, Mass., has taken over the operation and management of its West Coast operations, formerly under the direction of E. B. Sutton Co. Direct factory branch offices and warehouses, as well as the operation of Butterfield and S. W. Card divisions, continue at 3675 E. Olympic Blvd., Los Angeles; 121 Second St., San Francisco; and 558 First Ave. S., Seattle.

### Opens New York Branch Office

Precision Drawn Steel Co., Camden, N. J., established New York metropolitan district offices at 56 Main St., Millburn, N. J. In charge is James J. Holloran, former manager of the Cold-Finished Bar & Tube Division, Mapes & Sprowl Steel Co., Union, N. J.

### Thompson Products Buys Firm

Thompson Products Inc., Cleveland, manufacturer of aircraft, electronic and automotive parts, acquired Karl-Douglas Associates Inc., Hawthorne, Calif., maker of hydraulic and pneumatic cylinders and valves.

### GE To Build Service Shop

General Electric Co., Schenectady, N. Y., will construct a multi-million dollar apparatus service shop on Tonnelle avenue, North Bergen, N. J. It will provide electrical maintenance facilities for New Jersey and New York. Operations now in the greater New York city area will be moved in.

### National Valve To Expand

Henry E. Haller Jr., newly elected executive vice president and general manager of National Valve & Mfg. Co., Pittsburgh, will spearhead an expansion program for the firm. Following transfer of Navco assets to new owners, headed by Frederick W. Richmond,



These officers were re-elected: Henry E. Haller Sr., president; J. R. Vicklin, vice president; C. G. Grabe, vice president-engineering; J. S. Land, vice president-sales. R. C. Williams was named secretary-treasurer.

### Kaiser Opens Branch Office

Kaiser Aluminum & Chemical Sales Inc., Oakland, Calif., opened a branch sales office at 108 N. Main St., South Bend, Ind., under the management of R. D. Murphy. The firm moved its Baltimore branch office to 5017 York Rd.

### buys F. Jos. Lamb Co.

F. Jos. Lamb Co., Detroit, manufacturer of automation equipment, special machinery and multiple drill heads, has been purchased by a local financial group. Officers are Alfred C. Ryan, president; J. K. Rye, vice president and general manager; Arthur Wrock, secretary; and A. C. McLee, treasurer.

### Fansteel Expands in West


Fansteel Metallurgical Corp., North Chicago, Ill., now has a plant at 1015 Hope St., South Pasadena, Calif., for the assembly of selenium rectifiers. Stocks of tantalum capacitors will be carried. R. T. Morrison is manager. Gorman Co. is distributor in ten western states.

### Plans To Build Plant in Peru

Harbison - Walker Refractories Co., Pittsburgh, will build a plant in Lima, Peru, to produce fireclay, silica and basic refractories. Its associates are Cerro de Pasco Corp., New York, and Miguel Damert Muelle, San Isidro, Peru. Harbison-Walker will have the majority interest in the company, Refractories Peruanos, S. A.

### Federal-Mogul, Bower Merge

Bower Roller Bearing Co., now merged into Federal-Mogul Corp., will operate as Federal-Mogul-Bower Bearings Inc. G. S. Peppiatt, president and chief executive officer of the merged company, says that Bower will be operated as a division of the new company and will retain its basic organizational



**HEVI DUTY FURNACES**  
In Tool Room Service

**Are Versatile . . . . .  
and Dependable**

● These Hevi Duty Box Furnaces at the A. O. Smith Corp. of Milwaukee, Wisconsin are used for hardening production tools that vary in weight from a few ounces to several hundred pounds. Hevi Duty Furnaces provide the uniform temperatures needed for precision heat treating.

Send for bulletins HD-341 and HD-441

**HEVI DUTY ELECTRIC COMPANY**

HEAT TREATING FURNACES **HEVI-DUTY** ELECTRIC EXCLUSIVELY

DRY TYPE TRANSFORMERS — CONSTANT CURRENT REGULATORS

**MILWAUKEE 1, WISCONSIN**




## FACTS THAT FIGURE

*in lower costs*

### FACT:

Steel is two to three times as strong as gray iron.



### FACT:

Steel is two and one half times more rigid than gray iron.



### FACT:

Steel costs only a third as much as gray iron.




**AND SO...** by manufacturing your products from welded steel, costs can be reduced an average of 50%.

## HOW WELDED STEEL BUILDS STRONGER PRODUCTS ...for lower cost

**B**Y using welded steel design, material costs can be reduced up to 86% compared to using gray iron.

The amount of saving depends on how well the design utilizes steel's superior strength and rigidity.

The substantial saving in material cost leaves a wide margin in which to fabricate the steel by welding and still realize overall savings of 50% on many types of products.



**Costs 23% Less.** Base for machine weighs 50% less than former casting construction, is stronger, more rigid, neater in appearance. Fabricated in only 6 hours... former design took 14 hours.

### How to design in steel


Handbook and bulletins on welded design are available to designers and engineers by writing:

**THE LINCOLN ELECTRIC COMPANY**  
Dept. 1607  
Cleveland 17, Ohio  
THE WORLD'S LARGEST MANUFACTURER OF  
ARC WELDING EQUIPMENT

structure. H. Gray Muzzy is chairman. S. A. Strickland is vice chairman of the board of the new company. Chief products of the Detroit firms are: Federal-Mogul, sleeve and ball bearings; Bower, straight and tapered roller bearings.

## Rockwell Mfg. Expands Plant

Rockwell Mfg. Co., Pittsburgh, is constructing a 104,000-sq-ft parts plant in Russellville, Ky. Cost of the plant is estimated at over \$1 million, exclusive of production equipment.



## VACATIONS

Plant and offices of Whiting Corp., Harvey, Ill., will be closed the first two weeks in August for vacations. A skeleton force will handle emergency orders and incoming materials.

Automatic Transportation Co., Chicago, is closing its plant the first two weeks of August for vacations and will reopen Aug. 15. A

skeleton crew will provide emergency service.

**National Research Corp.**, Newton Highlands, Mass., has closed its plant (July 30 through Aug. 13) for vacations.



## ASSOCIATIONS

**American Iron & Steel Institute**, New York, elected two vice presidents: W. W. Sebald, president Armco Steel Corp., Middletown, O. and William M. Akin, president Laclede Steel Co., St. Louis.

E. M. Krech, director of purchases, J. M. Huber Corp., was elected president of the **Purchasing Agents Association of New York**. Other officers are: W. F. Rae Jr., Menen Co., and D. S. Gibson, Worthington Corp., vice presidents; E. I. Fiels, treasurer.

**Investment Casting Institute**, Chicago, has voted to affiliate with the **National Castings Council**, Cleveland. The council affords co-operative action among the a



## U. S. Steel Opens Iron Ore Storage Yard on Lake Erie

Iron ore pours from an inloading conveyor pit into an earth moving diesel unit for stocking at United States Steel Corp.'s new 170-acre Perry Bluff, O., iron ore reservoir yard on Lake Erie near the Pennsylvania state line. Railroad cars of ore from Pittsburgh & Conneaut Dock Co., about 2 miles from the storage area, are unloaded at the two conveyor pits, each with a capacity of about 1500 tons per hour. A conveyor system then dumps the ore into earth moving units for stocking. Perry Bluff was constructed to provide additional ore storage for U. S. Steel mills in the Pittsburgh and Youngstown area.

ociations, societies and institutes  
erving the foundry industry on  
atters beyond the scope of the  
individual groups. The institute  
ill hold its fall meeting in De-  
roit, Nov. 1-3.

C. W. Stone, executive vice presi-  
ent, Interstate Drop Forge Co.,  
Milwaukee, was elected president  
F Drop Forging Association,  
Cleveland.

United States Trade Mark Asso-  
ciation, New York, elected to its  
board of directors Herbert E.  
Markley, secretary of Timken  
Roller Bearing Co., Canton, O.



## ANNIVERSARIES

Leslie Co. is celebrating its 50th  
year at its present site in Lynd-  
hurst, N. J. It makes pressure,  
temperature and liquid level regu-  
lators and controllers, steam and  
air whistles and strainers for the  
protection of equipment in fluid  
piping systems.



## REPRESENTATIVES

Structo Systems Inc., Elyria, O.,  
maker of steel framework angles,  
appointed these additional distrib-  
utors: Wrenn Bros., Charlotte,  
N. C.; Wurzburg Bros. Inc., Mem-  
phis, Tenn.; Chalmers Wood, Kan-  
sas City, Mo.; Safway Steel Scaf-  
fold Co., Sioux City, Iowa; Safway  
Scaffolds Co. of Texas Inc., Dallas;  
and Alton Inc., McKeesport, Pa.

Bond Welding Service Co., Drex-  
el Hill, Pa., was appointed distrib-  
utor in the greater Philadelphia  
area for resistance welding mate-  
rials made by WW Alloys Inc., a  
division of Fansteel Metallurgical  
Corp., North Chicago, Ill. R. H.  
Lunn Jr. was appointed district  
manager of the Pittsburgh area  
for the division.

Cleveland Tapping Machine Co.,  
Canton, O., appointed Hoffman &  
Heartt, Los Angeles, its represent-  
atives for Southern California and  
Arizona; C. F. Bulotti Machinery  
Co., San Francisco, for Northern  
California.

# PRICE LIST

## ON HANNIFIN STOCK HYDRAULIC PRESSES

1-TON .....	\$ 552
2-TON .....	\$ 627
5-TON .....	\$1,286
8-TON .....	\$1,581
10-TON .....	\$1,855
25-TON .....	\$3,681

Prices complete with motors and starters F.O.B. our  
press plant, St. Marys, Ohio, subject to change without notice.

### DELIVERY FROM STOCK


Demand for these popular presses is so consist-  
ent we are able to produce them in quantity and  
pass the savings along to you.

Construction-wise and quality-wise these small  
general-purpose presses are identical to the  
larger Hannifin presses, up to 150 tons. Special,  
optional controls when needed.

WRITE for complete information on the  
Hannifin Hydraulic Press you're interested in.

# HANNIFIN

HANNIFIN CORPORATION, 523 S. WOLF ROAD, DES PLAINES, ILLINOIS



**MOTORIZED**  
**COIL LIFTER**  
**SAVES**  
**STORAGE SPACE...**  
**HANDLES COILS FASTER... SAFER**

*1 Lifter Handles Both Wide  
and Narrow Coils With  
Same Speed and Economy*

This C-F Coil Lifter, under control of  
the Crane operator handles hundreds  
of coils a day in a large mill... wide,  
narrow, and of varying tonnage. Fast,  
infinite adjustments of the motorized  
legs permit quick pick-up and set-  
down. Legs can be opened to any width  
and held... no need to open to maxi-  
mum width to handle narrow coil.  
Maximum of 12" required between  
coils of any width—saves storage room.

Positive tong grip on coil tightens as  
lift is made... insures safe handling.  
Made in motorized models for crane  
cab or pendant operation as well as  
manual types with chain wheel, in  
capacities from 3 tons up. Powered  
Rotating Heads available. Opening  
ranges to suit your re-  
quirements. Write for  
Bulletin and complete in-  
formation.



## CULLEN-FRIESTEDT CO.

1308 South Kilbourn Avenue • Chicago 23, Illinois





# The Facts Stood Me on My Ear!

"When I found out from the Detrex field representative that the average metalworking plant had  $\frac{1}{4}$  to  $\frac{1}{3}$  of their operations tied up in metal cleaning and surface preparation, I was astonished to say the least! It started me thinking as to just what percentage of our operations were of that type. I found that in our plant nearly a third of all the operations had to do with metal cleaning and surface preparation. That fact not only stood me on my ear but it changed my thinking completely regarding the importance of these operations.

"The Detrex man pointed out many dollar-saving improvements we could make. For example, take degreasing solvent. Detrex Perm-A-Clor\* is saving us hundreds of dollars per year because it goes further. Why? Because

it's a premium solvent and at the price of regular solvent too! He also showed us ways to conserve solvent, improve product quality and even helped us train operators. He did all this without charge too!

"Maybe you're like me. Perhaps you have never stopped to consider the number of metal cleaning and surface preparation operations in your plant, or the money you might save from an overall standpoint. If not, the facts will probably startle you.

"Why don't you give the Detrex man in your area a chance to make a survey of your plant? Chances are you'll be surprised at the result. It won't cost you a cent and he may prove he can save you big money. Give it a whirl . . . you've got everything to gain . . . nothing to lose."

*\*Detrex Perm-A-Clor (trichlorethylene degreasing solvent) costs no more than ordinary solvent, yet it goes much further . . . far more parts degreased per pound. You can buy Perm-A-Clor in the manner most economical for your needs . . . by the drum, by tank truck or by tank car. A nationwide network of distribution and supply points provides fast delivery at all times.*



*Service with a Saving!*



## DETREX CORP.

Dept. 201 • Box 501, Detroit 32, Mich.  
 DEGREASERS • DEGREASING SOLVENTS • WASHERS  
 ALKALI & EMULSION CLEANERS • DRYCLEANING  
 EQUIPMENT • PHOSPHATE COATING PROCESSES

# Technical Outlook

**LESS CHROME FATIGUE**—A special high-concentration chromium plating bath containing 600 g/l  $\text{CrO}_3$  and 4.8 g/l of sulphate reduces the fatigue limit of 266,000-psi superstrength steel less than 2 per cent after chromium plating. Plating is done at 130° F at a current density of 3 amp/sq in. Parts are baked 4 hr at 450° F after plating. Bath was described by E. J. Seyb, United Chromium Research Laboratories, Detroit, at the American Electroplaters' convention.

**STRONGER MOLY WIRE**—A small amount of cobalt added to a high-purity molybdenum base makes a stronger wire for electronic tube grids, says Fansteel Metallurgical Corp. It's designed to minimize breakage on grid winding machines without perceptibly changing the electrical properties of pure molybdenum.

**LOW-TEMP BRAZING**—A new titanium brazing process uses low temperatures with silver or silver-manganese brazing alloy. Developed by the Stainless Processing division, Wall Colmonoy Corp., Detroit, the method employs no flux. It is a form of vacuum brazing—offers a minimum of distortion.

**LIGHTER REACTOR**—Much of the weight and bulk of a conventional atomic reactor has been eliminated in a pilot model by nesting a liquid metal reactor inside a cylindrical heat exchanger. The reactor may solve the weight per horsepower problem standing in the way of an atomic power plant for aircraft.

**FLATNESS INSURANCE**—Porcelain - enamel - faced sandwich panels that will sheathe the 12-story Ford Central Staff Office Building in Dearborn, Mich., have a built-in flatness factor. It's

a 1/4-in. thick aluminum honeycomb immediately behind the porcelain-coated steel face. Backing up the honeycomb is 2 in. of Foamglas insulation between galvanized steel sheets. Each panel is sealed on the edges with an aluminum frame.

**DYED ALUMINUM STRIP**— You can buy it in coils, already anodized and colored. Available in about any color, commercial coils come in gages from 0.003 to 0.020 in., widths from ¾ to 20 in.

**TELLTALE TESTING**—Newer testing techniques are paying off in the automotive field. Radioisotopes measure oil and coolant leaks, reveal efficiency of filters, disclose wear. Sonic and pneumatic volume measurements give extreme accuracy in studies on carbon deposition, combustion chamber volume and engine timing.

**STRENGTH FOR SHEET**—The Alcoa research laboratories are about ready with an alloy for sheet, plate and extrusions which will have excellent properties in the 300 to 400° F range—a valuable product for supersonic aircraft. New Alcoa alloy X2219 is good for extrusions and forgings at 500 to 600° F. This temperature range is needed for applications in and near aircraft and automotive engines.

**RADIOACTIVITY TRACES WEAR.**—After exposing dies used to hot extrude steel to the neutron stream of an atomic pile for two days, the tungsten in the tool became sufficiently radioactive to permit accurate studies of wear. B. J. Jaoul, Ecole Nationale Supérieure des Mines de Paris, told the Boston meeting of the ASME that the method should detect wear on tools, gears, rams and even automobile tires.





Rocket nozzle liners made of super refractories

Norton Co.

# Beyond the Metals

## PART I

By VAN CALDWELL  
Associate Editor

TEMPERATURE at the combustor of a large gas turbine reaches 3000°F. But before the hot gas hits the turbine blades it must be cooled to 1500°F; otherwise the blades can't take it.

That doesn't keep designers from talking turbine temperatures of 2000°F and higher. They have their eyes on three possibilities: 1. A small group of metals (molybdenum, tungsten, tantalum, columbium) with survival potential above 1800°F. 2. Combinations of metals and ceramics called cermets. 3. Super refractories.

**Furnace Born**—Super refractories have been growing up for years. Mostly they are synthetic products of the electric furnace. Greater resistance to heat distinguishes them from most of the "natural" refractories, but that's not their only or even their most valuable quality.

Some show superior wear resistance. Some are insulators; others good conductors of heat and elec-

- Extra copies of this article, and Part II on the carbides, borides, nitrides and other members of the super refractory family which will appear next week, are available in quantities from one to three until supply is exhausted. Write Editorial Department, STEEL, Penton Bldg., Cleveland 13, O.

tricity. They stand out for resistance to corrosion, or thermal shock, or oxidation. Combinations of such qualities, plus great resistance to heat, give super refractories their special importance.

**Heat Aside**—They find uses as abrasives, forming rolls, nozzles, containers for corrosive chemicals and parts of electrical devices where heat plays a minor role.

Silicon carbide and oxides of aluminum, magnesium and zirconium have established uses as furnace linings, wear resistant parts, muffles and crucibles where heat is not the only killer.

Out on the heat frontier are materials that ten years ago were curiosities on a laboratory shelf. Tantalum carbide, zirconium nitride, cermets, coatings like molybdenum disilicide. Rocket, jet and turbine designers look to them for answers.

**Outlook**—The super refractories picture breaks down to this: 1. Bread and butter applications in melting, wear resistance, heat treating and fabricating. 2. Blue sky applications in aircraft engines, turbines, atomic energy, chemical processes and metal handling.

You'd expect these materials to supplement the tonnage refractories. That's their biggest field so far, but they are going much further. A few have taken the big

ump as actual substitutes for metals.

**Names**—Usage spreads the term "super refractory" over considerable territory, including high-melting-point ceramics, refractory hard metals and intermetallics. Some refractory makers prefer to confine the term to products of the electric furnace.

Whatever the name, it's important to realize that few of these materials are used pure. Most shapes, for instance, contain binders that modify the properties of the base material. Still, you'll find them classed by their major chemical components as oxides, carbides, nitrides, and borides and silicides.

## OXIDES

Alumina, magnesia and stabil-

ized zirconia are the big three of the oxide refractory group.

**Alumina**—Fused aluminum oxide (alumina) is dense, white, hard (2000 Knoop), crystalline, chemically inert. It can be formed into shapes for service up to 3450°F. Thermal conductivity about three times that of fireclay brick, great resistance to wear, good electrical insulation values at all temperatures, chemical stability and resistance to flame and slag erosion are typical qualities of refractories made from it.

You'll find alumina refractories in muffles, hearths and cores for wire-wound furnaces where their long service life outweighs relatively high cost. Heat treating and enameling furnaces are two hot spots in which they have

proved especially useful.

Many aluminum oxide cements and castables are available for lining, patching and bricklaying, especially in the hottest zones of metal-melting furnaces, and for embedding resistance wires in appliances and furnaces.

**Insulation** — Alumina bubbles and grain make excellent high-temperature insulation. Bubble brick, another type of alumina refractory, combines insulating ability with ability to resist direct flame impingement at above 3200°F.


Several builders offer bright annealing atmosphere furnaces lined with this brick which contains virtually no reducible oxides. It's a good thermal insulator at high temperatures, and is light in

## Where Super Refractories Are Used

	Aluminum oxide	Beryllium oxide	Magnesium oxide	Zirconium oxide	Boron carbide	Silicon carbide	Ti, Zr carbides	Boron nitride	Cr, Zr, Ti borides
Furnace shapes-----	X		X	X		X			
Arc and induction furnace linings-----		X	X	X		X			
Crucibles-----	X	X	X	X	X	X	X	X	X
Heat exchangers, recuperators-----	X			X		X			
Nuclear reactors-----		X			X	exp			
Wear-resistant parts-----	X				X	X	pos		X
Furnace muffles-----	X					X			
Refractory coatings-----	X			X		X			
Electrical resistors, heating elements-----	X		X	X	X	X			
Brazing and welding fixtures-----						X			
Alloy additions-----					X	X			
Jet engine and rocket parts-----	X	X		X	X	X	X		X
Roller hearth rolls-----				X		X			
Acid spray nozzles-----						X			
Molten metal nozzles, pumps, piping-----			pos	X		X	pos		X
Sand blasting nozzles-----					X	X	X		
Burner tips-----						X			
Abrasives-----	X			pos	X	X	pos	pos	
Metal cutting tools-----	exp	X				X	X		
Gages-----					X				
Metal forming rolls-----					X				
Mold washes, high temperature lubricants-----				X				X	
Electrical insulators-----	X	X	X			X		X	
Thermal insulation-----	X			X	X			X	
Sheet metal and wire guides-----						X	pos		
Bearings, bushings-----	X				X	X	X		X
Dies-----							pos		X

Key: pos = possible; exp = experimental





## REFRACTORINESS PLUS

A Hough Payloader handles crude silicon carbide in Norton Co.'s Crystolon Plant. It's dusty work with one of the most abrasive of materials.

In September, 1948, the machine's 4-cylinder Waukesha engine was fitted with aluminum oxide (Alundum) cylinder liners. Since then it has logged 8618 hours of operating time and is still good for long service. Based on engine rpm, that equals 258,500 miles of wear on an automobile engine.

The engine has been rebuilt six times, but the cylinder liners show no measurable wear. Valves, valve seats and bearings wore out. Equivalent service life for a standard cast iron block is about 1200 hours.

With super refractories, the plus values often count for more than sheer refractoriness.

weight, especially important because the furnaces are shipped with the brick installed. It's also used in powder metallurgy furnaces, gas synthesis generators, electric resistance and reverberatory furnaces.

**Magnesia**—Most of the magnesia refractories are tonnage products, but fused magnesium oxide (periclase) is properly grouped with the super refractories.

Fused magnesia brick has been used successfully for the linings of both ferrous and nonferrous metal melting furnaces, for crucibles and for a nitrogen fixation furnace operating at 4000°F. It has great resistance to basic slags, but cannot be used in reducing atmospheres above 3100°F. The burners in your electric stove are probably sheathed in fused magnesia because of its high resistivity and thermal conductivity.

**Zirconia**—Stabilized zirconia is a relative newcomer, but its use is growing fast. Because pure zirconium oxide changes crystal form at about 1800°F with great volume contraction, its use is limited.

By fusing it with about 5 per cent CaO, it maintains its low temperature crystal form to 4900°F. The resulting product has twice the density of fireclay brick, but is a much better thermal insulator and will carry a considerable load under high heat.

**Steelmaking**—The cost is still high for stabilized zirconia refractories, but their thermal conductivity at high temperatures is so

low that they can be used profitably for extreme applications in metal melting, including steel and platinum melting.

One of the tricks in the continuous casting plant of Atlas Steel Co. Ltd. at Welland, Ont., is a stabilized zirconia nozzle which is not wetted or eroded by the steel. After leaving the nozzle the molten steel is conducted to the mold through a zirconia tube. The metal does not solidify because of the low thermal conductivity of the refractory.

**Beryllia**—Beryllium oxide is a tough ceramic material which has already found a number of uses: Linings for rocket combustion chambers, jet engine turbine parts, aircraft spark plug insulation, high-temperature electric furnace linings. Beryllium oxide can be made gas tight at 4000°F, and has operated at 3600°F both in vacuum and under pressure in the presence of carbon, carbon monoxide and hydrogen without reaction.

Resistance to alkali attack at high temperatures makes it suitable for high-purity melting. Moreover, its thermal shock resistance is superior to quartz. Although it is one of the hardest of refractories, it can be machined to shape after casting or pressing.

Beryllia is readily dissolved by acids, even dilute ones. It is volatile in the presence of moisture at elevated temperatures, a property which ruled it out when it was tried as a moderator in an atomic pile.



**High Purity**—When a refractory has physical properties that block its use, greater purity won't necessarily improve the situation. Many can be obtained 97 to 99 per cent pure, but refractory mixtures equivalent to alloys frequently produce better results.

One such complex product widely used in glass melting tanks and electric metal-melting furnaces is fusion-cast mullite ( $3\text{Al}_2\text{O}_3 \cdot 2\text{SiO}_2$ ). It has excellent resistance to heat shock, low thermal conductivity and stands up well to many slags and molten metallic oxides. Some varieties can be used to 3200°F.

Magnesia - alumina, magnesia chromia, and zirconia-alumina are other complex oxide fusions in the experimental stage that show promise for metalworking applications.

**Most Basic** — Fused lime, although it melts at about 4600°F and is the most basic refractory can be used only in dry atmospheres because it slakes. Fused thorium, dense as lead and radioactive like uranium, is not likely to be available in quantity for obvious reasons.

It could have real importance in melting problem metals because it is the least reactive at high temperatures of all the oxides and melts at 5500°F. Thorium crucibles have been used on a small scale for melting titanium, zirconium and thorium. Hafnium oxide, another rare one, is a lot like zirconium oxide, but maintains a stable crystal form to 3100°F.



This turret punch press is turning out nearly twice the work it once did. Operator feeds it a stack of cards, loads the sheet and steps back

# Punched Cards Automate This Press

**AUTOMATIC CONTROL** of machines from punched-card information is out of the laboratory stage. General Electric Co. is marketing a system which can run a number of machines in the factory.

Already proving itself on a Wiedemann turret punch press in GE's Philadelphia works, the control is primarily for machines which involve point-to-point positioning between work cycles. Punches, drill presses, shears, riveters, plate-cut machines are examples.

**Simple and Practical**—GE put design emphasis on simplicity, using proved methods where possible. The control uses a business machine card reader to activate a positioning control system.

At least three machine motions can be accurately positioned to  $\pm 0.010$  in. without difficulty. Accuracies of  $\pm 0.001$  in. can be obtained with increased care in the design of the machine-control com-

bination. On some jobs a fourth motion is possible.

The control also can provide for functions like turning off a coolant pump, selecting a different tool or telling the operator when he must do a manual operation.

**First Application**—The first production model on the Wiedemann press punches formed holes in flat steel sheets for low voltage switch-gear equipment. Holes must be located in two dimensions. Since a number of differently shaped holes are needed, the control must select the proper punch from the 32 on the turret.

In-and-out motion has a travel of 48 in., the crosswise motion, 80 in. The flat sheet is held by clamps on the crosswise motion and located by stops which represent the zero index point for each motion. Doing the job manually, the operator had to position the table with handwheels, select the punch by


moving the turret and then punch the hole.

**Easy Now**—With the numerical punched card control system this slow and fatiguing job has been eliminated. The operator places a stack of cards into the reader and initiates the cycle.

The first card directs the table motion to the loading position and stops the machine. Then the operator clamps the steel sheet on the table and again initiates the control. From that point, the reader will go through the stack of cards automatically, performing the exact function that was punched on each card.

The last card directs the machine to the unloading position. An end-of-run light indicates that all operations are completed. The operator removes the piece and cards, and he's ready for the next one. Any stops during the sequence can be programmed easily.





## WHICH SLEEVE BEARING?

# A Guide to Bearing and Bushing

**SLEEVE BEARING USERS** have a lot in common with the small boy at the candy counter. With so much goodness to choose from, the "best" looks like a matter of opinion.

Fortunately, bearing buyers have better guides to go on. Often it's a matter of neatly balancing physical requirements (yield strength, corrosion resistance, etc.) against cost. Extreme conditions sometimes point directly at one kind of bearing, but usually there's a wide range of choice.

**Take Your Pick**—Six types of sleeve bearing alloys are in common use today: Babbitt, copper-lead, leaded-bronze, bronze, silver and aluminum. They come in a variety of forms and surfaces, sometimes backed or overlaid with other metals.

Some of their properties are acquired from the ways they were produced, which include sev-

eral kinds of casting, electroplating and sintering.

Starting point for choosing bearings and bushings is the service required. Here are some factors you should consider:

- Wear resistance
- Yield strength (load carrying capacity)
- Corrosion resistance
- High-speed performance
- Conformability
- Ability to seat
- Seizure resistance

**Wear Resistance**—This is an important property of the bronzes. High hardness of copper-tin alloys accounts for it. Bronzes are often used for this reason, but the bearing must be kept free of dirt to avoid abrasive wear, and there will be more wear on the shaft than with a softer alloy.

Wear is usually due to dirt. Where wear is a primary factor, a bronze bearing, a hard shaft and

clean oil are indicated. Where a soft shaft is used and dirt cannot be avoided, it is often desirable to use a babbitt bearing; the babbitt wears but is inexpensive to replace. This avoids reconditioning or replacing the shaft.

**Yield Strength**—A bearing is limited by its capacity to carry loads. The alloy must not deform or pound out. High yield strength of the bronzes allows them to carry a heavy load. Of course, if a large bearing area can be used to obtain a low unit load, other bearing materials may be used.

**Corrosion Resistance**—The bearing must not corrode. Hot, uninhibited oil is particularly corrosive to lead. Modern oils contain additives to overcome this corrosion. With use, additives lose some of their inhibiting properties so corrosion of lead is still a problem.

Tin and aluminum have good corrosion resistance to hot oils, al-

# ART I

## Bearing Materials

J. B. MOHLER  
Consultant  
Newcastle, Pa.

## Choice

ough it is unlikely that these materials would be selected for this property alone.

**High-Speed Performance**—If an film could be maintained at all and if dirt could be kept out of the bearing, speed would not be a factor. At high speeds a material is required that will not generate excessive heat if the oil film is momentarily broken or if dirt gets between the journal and the bearing. Alloys of lead and tin are best for high-speed applications.

**Conformability**—Alloys of lead and tin, including the overlay alloys and the babbitts, have the best ability to conform under conditions of local overloading owing to misalignment, shaft deflection or foreign particles that get to the bearing surface. A related property is embeddability. The soft alloys will engulf a particle of dirt so that it will not be held against the journal surface to generate heat

and promote failure in the bearing.

**Ability To Seat**—The bronzes and the aluminum alloys have a greater ability for the entire bearing to move than do the babbitts. The babbitts will conform to the shaft but only by movement of material. Under some conditions this

Mr. Mohler formerly was director of research for Johnson Bronze Co., Newcastle, Pa.

is desirable; the bearing deforms so that unit loading is reduced by spreading it over a larger area. In other cases the condition requiring this conformance may be local overloading that can result in fatigue and early failure of the bearing.

The bronzes and aluminum alloys have an ability to seat without local deformation. Under conditions of misalignment the entire bearing will tend to bend into place so that the final shape will not be greatly distorted.

**Seizure Resistance**—Some alloys seize more readily than others. This property depends on the ability of the alloy to remain wet with oil and the ability to run without welding to the shaft after the oil film is broken. Lead and tin alloys have the best seizure resistance, and, in general, the lower melting alloys are more seizure resistant than the higher melting ones.

Because no one bearing material combines all these qualities in ideal proportion, combination bearings are common. For example, sleeve bearings are made with a high-strength metal backing and a low melting point lining for high speeds under heavy load. A hard bearing may be indented and the indentations filled with a soft material to combine strength with

low friction and embeddability.

**Many Materials**—The special requirements of bearings have fostered a group of bearing materials ranging from wood to glass, but the commonest are metals. In terms of speed and load-carrying qualities, the usual metal bearing materials may be rated in this order:

High Speed		Heavy Load
1	Babbitt	6
2	Copper-lead	5
3	Aluminum	4
4	Leaded bronze	3
5	Silver	2
6	Bronze	1

In general, these qualities are related to hardness and melting point. High-speed properties are embeddability, conformability, low friction, oiliness and seizure resistance. Heavy load properties are load capacity, fatigue and wear resistance.

**The Babbitts**—These alloys of lead and tin have high-speed properties. There are many variations. SAE alloys widely used are shown in Table 1.

If corrosion resistance is desired, the tin babbitts are chosen. If maximum fatigue strength is required, SAE 15, lead-base babbitt, sometimes referred to as arsenic-babbitt, is chosen. SAE 13 is soft and ductile compared with other babbitts and may be employed for high-speed applications where the maximum in surface properties is desired. Intermediate in properties between SAE 13 and SAE 15 lie SAE 14 and the three tin-base babbitts.

**Backed Babbitts**—Babbitt on a cast iron back is an improvement over the original poured babbitt bearings. Thin babbitt linings are used, and precision bearings are made so that no scraping-in is required. If the babbitt should be

Table 1—Lead and Tin Bearing Alloys

S.A.E. No.	Tin	Lead	Antimony	Copper	Arsenic
10	90	..	5	5	..
11	87	..	7	6	..
12	89	..	8	3	..
13	5	85	10	..	..
14	10	75	15	..	..
15	1	83	15	..	1



worn away, graphite in the cast iron acts as a solid lubricant.

Babbitt on a bronze backing is an old and popular combination of metals, uniting the properties of babbitt with the convenience of precision fitting. An electroplated tin overlay on large bronze piston pin bushings is used as a break-in surface.

**Indented Bearings**—For some applications the bronze backing is indented and the indents are cast full of babbitt. The bearing is then machined to present a gridded surface. This provides a strong backing with the journal directly supported by the bronze over part of the area. At the same time, it's exposed to a large percentage of babbitt for low friction and embeddability.

Babbitt on steel is a popular modern construction available in many lead-base and tin-base alloys. Fatigue life is greatly increased by the use of a thin babbitt lining. Microbearings are being manufactured with a babbitt lining 0.002 to 0.005 in. thick.

**The Copper Alloys**—Typical copper alloys are shown in Table 2. Bronzes are at the top of the table, the leaded bronzes in the middle and the copper-leads at the bottom. Alloys at the top are for heavy loads, those at bottom, high speeds.

Alloys 1 to 4 are essentially bushing alloys used where low wear and heavy load capacity are desired, such as for a piston pin bushing. Such alloys, used with a hard shaft, are subjected to loads up to 10,000 psi.

**General Purpose**—Alloys 5 and 6 are general-purpose types containing a moderate amount of tin for strength and a moderate amount of lead to add surface properties. They can be used at heavier loads than the copper-leads and at higher speeds than the bronzes or leaded bronzes with high tin and low lead content, but they are essentially for steady load conditions. They are generally lubricated by wick, oil cup or forced feed; there is little likelihood of loss of lubrication due to rupture of the oil film.

Alloys 7 to 10 contain enough lead to add considerably to embeddability, seizure resistance and low friction. They're known as

**Table 2—Typical Copper Bearing Alloys**

No.	Copper	Tin	Lead	Zinc
1.	90	10	..	..
2.	88	10	..	2
3.	80	10	10	..
4.	88	4	4	4
5.	83	7	7	3
6.	85	5	9	1
7.	70	10	20	..
8.	80	5	15	..
9.	75	..	25	..
10.	65	..	35	..

bearing alloys or high-speed bushing alloys. They are commonly used for high speed and unsteady loads under conditions where the speed of the bearing and the clearance help maintain the oil film (hydrodynamic lubrication). The alloys containing tin have the greatest strength; those containing high lead and no tin have the best surface properties.

**Backed Bronzes**—Bronze on steel is used where a heavy load, precision bushing or bearing is required. In some applications the bronze is indented with hemispherical, oblong or diamond shapes to act as multiple reservoirs to hold oil and to collect dirt. In other applications the indentations are filled with graphite to act as a solid lubricant.

Copper-lead on steel is used for relatively heavy loads and speeds that require a strong bearing with a considerable amount of lead for surface properties.

Where loads are heavier than copper-lead on steel will take, an overlay will prolong the fatigue life or increase the load capacity. The overlay usually consists of an electrodeposited lead-tin-copper alloy, 0.001 in. thick. By means of electrodeposition it is possible to produce a thinner, precise lead alloy surface than by casting methods. But a similar bearing is made with a cast overlay 0.001 to 0.003 in. thick on a sintered copper-nickel alloy on a steel back. Electrodeposited tin overlays on copper-lead have also been used.

**The Aluminum Alloys**—Two aluminum alloys are becoming popular as bearings for internal combustion

engines. One is an aluminum-tin alloy containing small amounts of copper and nickel as hardeners. The other is an aluminum-silicon alloy containing a small amount of cadmium. There is little difference between them. They are roughly in a class with the copper-lead and are replacing them in some cases because of their greater load capacity and adequate surface properties.

Aluminum on steel is a relatively new bearing construction that is proving to have good surface properties and greater load capacities than the copper-leads. It is manufactured without an overlay with a lead-tin overlay and with tin overlay.

**Silver**—Silver is used for high speed and heavy-load aircraft bearings. The silver bearing with a lead-alloy overlay and a steel back is widely used. It will carry the heaviest loads at high speed. Originally, the overlay consisted of a diffused lead-indium alloy, but this has been extensively replaced by lead-tin. A silver grid bearing with lead-tin in the indentation and a lead-tin overlay is also being manufactured.

This is the first section of a two-part article on sleeve bearings and bushings. Part two will appear in next week's issue of STEEL.

## LIKE SPECTACULAR COST CUTTING MACHINERY . . . .

that consolidates production operations in a single machine to speed up production and eliminate wasteful handling



# CMP *cold rolled strip steel...*

## can help step up your production rate

By working to restricted specifications for size, physical characteristics and finish, realized through precision cold rolling and heat treating processes, CMP can help in many ways to step up the production of parts made from flat rolled steel.

In many cases, "working qualities" can be so improved that machine speeds can be stepped up as much as 25%.


Frequently, qualities can be developed which permit simplification of tooling.

In some instances, restricted specifications may be developed which completely eliminate operations.

Where precision fitting is encountered, dimensional accuracy can be developed to greatly speed assembly and eliminate rejections.

In all cases, users enjoy the usual time-saving advantages of CMP's customary precision gauge and width tolerances . . . more footage per coil . . . fewer production shutdowns for coil replacement on automatic-feed operations . . . longer tool life.

CMP's extensive experience in development of steel specifications for more efficient and economical production is always at your service.




**the Cold Metal Products co.**  
GENERAL OFFICES: YOUNGSTOWN 1, OHIO

PLANTS: YOUNGSTOWN, OHIO AND INDIANAPOLIS, INDIANA  
OFFICES: Chicago • St. Louis • Los Angeles • San Francisco  
SALES New York • Cleveland • Detroit • Indianapolis

**CMP** WHERE YOU CAN GET  
SPECIFIC SPECS. FOR SPECIFIC JOBS

LOW CARBON	STAINLESS
HIGH CARBON	ALLOY
Annealed or	ELECTRO ZINC
Tempered	COATED





Key move in the latest expansion was replacing the old 22-in. tilting mill with a 32-in. blooming mill. Now they can pour 700-lb ingots instead of 2500-lb ones and improve operation yields

# Prairie Steel Plant Still Growing

Thirty years in a continuous expansion program, Sheffield Steel, Kansas City, Mo., is pretty well used to construction hubbub. The end isn't in sight

By THOMAS F. HRUBY  
Associate Editor

**KEEPING UP** with its growing market is a full-time job for the Sheffield Steel division of Armco Steel Corp., Kansas City, Mo. Start talking about its expansion program and Sheffield officials probably will ask, "Which one?"

Sprawled out on 264 acres in a valley to the east of Kansas City its modern plant has a product diversity that could come close to filling the bins of any steel warehouse. That kind of product mix involved about 30 years of expansion and modernization with hardly a breather.

**The Beginning**—Sheffield start-

ed as the Kansas City Bolt and Nut Co. in 1888. Its products were special bolts and nuts for the railroads whose tracklayers were feverishly opening up the West. Bolts and nuts are still big business, but so are wire products, grinding balls, bar joists, long span joists, forgings, merchant shapes, structurals, reinforcing bars, welded wire fabric, track spikes and rivets.

Sheffield also operates a large, fully-integrated plant at Houston and a smaller steel-producing plant at Sand Springs, Okla.


Being hundreds of miles from

big steelmaking centers seems to have accentuated Sheffield's pioneering spirit. Taking advantage of available scrap, the company became the first to use a 100 per cent scrap charge in open hearths. That was 1920. Last year Sheffield added its newest "first"—completely automatic screwdown positioning control on its new 32-in. blooming mill.

**Just Good Business**—"If we've pioneered anything along the way, it happened to coincide with our appraisal of the best way to do business in this area," commented F. C. Herbster, division manager.

**with 4-SIDED welded steel enclosure**

*another  
H-W Metalkase  
development*




**HARBISON-WALKER**

**metalkase**

steel-encased, chemically-bonded basic refractory

Since the time of the Maccallum invention, more than forty years ago, the original metal-encased basic brick introduced by Harbison-Walker has been manufactured with many noteworthy improvements.

METALKASE, tried and proved in its newest form, is completely enclosed in 22 gauge steel on all four contact sides. The magnesite-chrome refractory rigidly controlled for highest quality is fully formed under great pressure before it is encased. Firm adherence of the welded steel casing to the refractory is assured by the tight grip of the indentation.



**HARBISON-WALKER  
REFRATORIES COMPANY**  
AND SUBSIDIARIES

World's Largest Producer of Refractories  
General Offices: Pittsburgh 22, Pa.

Typical section of open-hearth furnace front wall built of METALKASE. For maximum stability steel plates are used at intervals of two to four courses vertically. These are tack-welded to steel bars which in turn extend behind the buckstay and are free to move vertically.





That philosophy stands out in practically every Sheffield operation.

Take the melt shop. Through the years, the 1920-vintage open hearths had been expanded several times until the shop reached its present size, five 125-ton furnaces. In 1937, a scrap-charged cupola was installed to make this, in effect, a hot-metal shop.

"This 15,000 to 16,000 tons of hot metal a month, in terms of steel output, gives us the equivalent of another open hearth," Mr. Herbster stated. To the 500,000 tons of open hearth ingot capacity was added another 150,000 tons when a 100-ton electric furnace was installed in 1952. With room for three more furnaces in the electric melt shop, it's not hard to figure where future capacity will be centered.

**Bigger Ingots**—Ingot breakdown facilities became the big bottleneck about the time the electric furnace went into operation. The 22-in. tilting-table mill which had served Sheffield's needs so well in former years was totally inadequate. Last year, out it went. Taking its place is a Birdsboro 32-in. two-high reversing mill. Instead of ingots weighing a little more than a ton, the new mill rolls 7600 lb ingots.

Eight 16-ft soaking pits were built to handle the stepped up rolling schedules, and the six-stand 18-in. continuous billet mill was arranged in line with the bloomer. All tonnage goes through these two mills before going to the merchant mill or the rod mill.

Two operators run the new blooming mill at capacity, thanks to the automatic screwdown built by Electric Controller & Mfg. Co., Cleveland. The control helped Sheffield speed the training of operators, enabling them to concentrate on roll reversal and table manipulating.

**Finishing Mills**—From the billet mill, stock goes either to the rod mill, merchant mill or to an old 10-in. hand mill used only for special or small order bars. The rod mill (rated capacity, 225,000 tons per year) has 17 stands. Most of it goes into wire and wire products.

The 12-in. merchant mill is one of the latest of its kind. Rolls on each of the 12 stands are individually driven, and stands are all on movable bases. Rated capacity is about 250,000 tons.

Again taking advantage of local conditions, the Kansas City plant buys up old track rails, heats them in a furnace and runs them


through the 16-in. mill. This splits the rail head away from the flange, and the former is further rolled into reinforcing rod. About 25,000 tons a year can be made this way.

**Other Products**—A good third of all Sheffield tonnage goes into wire drawing rod. Thirty-four draw blocks take over from there, making wire from 22 gage to 1 in. The rest of the wire department includes: 68 nail machines, 3 staple machines, 16 barbed wire machines, 7 wire fence machines, 16 bale tie machines and two galvanizing units.


A fast-growing segment of Sheffield's business is high strength bolts for structural applications. This and grinding ball business spread Sheffield's name world-wide.

Other equipment is for hot up-setting track bolts, nuts and spikes. Automatic cold heading machines and boltmakers produce other bolts, nuts and rivets in sizes from  $\frac{1}{4}$  to 2 in.

Sheffield's Kansas City operation comes close to the optimum utilization of capital equipment. As the market grows, it's safe to bet that the company will be growing just a little faster and will be ready with the steel that's needed . . . when it's needed.



Rumor has it that this 75-ton electric will soon be joined by others. There's room for three more in the electric melt shop



Latest addition in the finishing end is this completely automatic boltmaking machine for sizes up to 2-in. in diameter





Crucible Steel, Midland, Pennsylvania


## Cities Service Heat Prover helps make special steel, saves fuel"

Crucible Steel Company of America is another leading steel company that has found the Cities Service Heat Prover a valuable aid in its furnace operation.

Here's what Crucible has to say about the Heat Prover at its Midland Works, one of several where it is in constant use.

"The Heat Prover has become our standard tool for the setting up and checking of combustion controls on our many furnaces at Midland. It has also helped immensely in setting up special atmospheres for special grades of steel by providing fast and reliable analyses, and has been particularly instrumental in the improvement of fuel economy. Cities Service has kept the Heat Provers in perfect running order and on many occasions has gone out of its way to help us."

You, like Crucible Steel, can achieve better results in *your* furnace operation with the Cities Service Heat Prover. Supplied and maintained free by Cities Service, it offers easy portability, rapid continuous sampling, simultaneous reading of oxygen and combustibles. For more information, talk with a Cities Service Lubrication Engineer. Or write: Cities Service Oil Company, Sixty Wall Tower, New York 5, N. Y.



### THE CITIES SERVICE HEAT PROVER...

Not an instrument that you buy...  
but a service we supply!

FREE!

# CITIES SERVICE

QUALITY PETROLEUM PRODUCTS





*Whether out in the yard or on the charging floor . . .*


## One Crane Truck Does All Jobs

**WHY BUY** two pieces of handling equipment when one can do double-duty? That's the way a leading New England malleable iron foundry looked at the problem of handling scrap from the storage yard to the cupola.

One 6000-lb capacity crane truck equipped with a magnet now spends part of its busy day loading skid boxes out in the scrap yard, the rest of the time loading the side dump bucket that feeds the cupola-charging skip. Some 200,000 lb of scrap are handled daily.

**Here's How**—After finishing its cupola charging, usually in the late afternoon, the vehicle moves outside to begin loading skip boxes for the next day's charge. Approximately 20 boxes make up a charge, and each box takes about 10,000 lb. Since this operation is the same, winter and summer, the user equipped the Elwell-Parker truck with an enclosed cab to provide the operator with all-weather protection.

As soon as the boxes are loaded, a platform truck moves them inside and positions them in a



semi-circle around the spot from which the crane truck will operate. In this way, the crane has access to all boxes and the dump bucket without moving from the spot.

**Charging Cycle**—In the morning, the crane moves into position and the operator plugs the control cables for the dump bucket into the back of his cab. Now he can control both his own crane and the movement of the dump bucket from within the cab. At the same time, a battery charging unit located in back of the crane, is

plugged in and the crane's batteries are charged during the in-plant operating hours.

The charge consists of various types of scrap, pig iron and sprue. Each portion of the load is weighed automatically after it is dropped into the dump bucket. When the dump bucket is full, the operator causes it to move forward on its track and discharge into the skip hoist. All motions are actuated by air cylinders.

The same operator also controls the dumping of the skip hoist when it is filled.



THE BEARINGS WITH A MILLION OIL WELLS

# Keystone Selflube BEARINGS

POROUS BRONZE

and POROUS IRON

## BETTER BEARINGS

*because of*

UNIFORM POROSITY

HIGHER OIL CONTENT

COMPLETELY ALLOYED STRUCTURE

GREATER MACHINABILITY

TRUE CAPILLARY ACTION

CLOSER TOLERANCES

LONGER LIFE

Keystone controlled particle size and shape plus closely controlled sintering atmospheres provide a uniformly porous and completely alloyed bearing structure. Keystone's special vacuum impregnation technique achieves higher oil content per bearing, providing longer, quieter life. True capillary action through uniformly distributed voids meters oil evenly to bearing surface when shaft is in motion and retains oil when motion is stopped.

• For better bearings, let Keystone quote on your needs!

*Write* for your copy of our new "Standard Bearing Sizes" booklet, just off the press.

### Keystone



CARBON COMPANY

POWDERED METAL DIVISION

ST. MARYS, PA.

Keystone Selflube Bearing Material is also available in solid bar, cored bar, and plate stock.





1. Front tool block turns the OD on the tool joint box forging. Rear blocks face both ends and make a groove. Load-unload clamps are at the rear

## Machine Gets Automatic Loader

THE MACHINING of a tool joint box forging is shown. It becomes part of an oil drilling rig.

A semistandard machine was adapted to turn, groove and face automatically. Cycle time is about 3 minutes, 15 seconds. Forgings weigh 75 lb. The machine was made by Gisholt Machine Co., Madison, Wis.

**Delivery**—Rough forgings come to the machine on a roller con-

veyor. A timing device delivers one each cycle to the load position on the conveyor.


A loading clamp, riding on a common carriage with an unload-clamp, picks up the rough forging, carries it over to the working position on the machine, and places it between two mandrels for cutting.

**Exit** — The unloading clamp takes the completed part from the


mandrels, carries it to the rear of the machine and drops it on the unload conveyor.

The load-unload mechanism is air operated. An oscillating conveyor takes all chips away from the machine.

The machine is one of a series. Others are on the job for a Texas oil-tool builder. This machine is being held for exhibit at the Machine Tool Show.



6. Clamps simultaneously put completed part on one conveyor, lift a rough forging off another. Timing device puts one rough forging at a time in pickup position



5. Chucking completed, the spindle starts and the machining cycle begins. Clamps move to the rear to put finished part on conveyor—pick up another rough forging



## Automated Units

This transfer machine is an assembly of independent components. It eases changeovers.

**PIECE-BY-PIECE** automation promises to decrease the cost of obsolescence, permits part design flexibility and makes maintenance easier.

The concept is guiding the construction of a 111-ft long, 75-station inline transfer machine at Snyder Tool & Engineering Co., Detroit. Snyder engineers call it "segmented automation."

The machine will turn out 140 pump bodies an hour at 80 per cent efficiency. Parts are cast iron.

**Individual**—Machining is done by individual machines or segments. Each has its own base and slide units and control panel.

The only connection between segments is a transfer bar that raises parts from dowel locators at each station, moves them to the next station and locates them for the next operation.


**Changes**—It is relatively simple to add or remove segments as part design changes. The transfer bar is disconnected, and bases, control panels and transfer bar sections are added or taken out of the setup. Necessary alterations are made in the master control panel that co-ordinates individual control panels.

Another advantage: Design and construction of machine portions can be under way before part design becomes final.


**Grouped**—The pump-body machine has 23 separate segments. They are divided into two groups, the first with 14 segments, the second with nine.

Either section can be loaded independently, operated and unloaded. Material can be stockpiled or finished regardless of the operating condition of the other section.

The segment between these two machine sections is a hydraulic index fixture. It turns the part over and rotates it before it enters the second machine section. It also can be used as the auxiliary loading station if the first section is shut down.




When machining is finished, spindle mandrel unchucks, tailstock retracts, pulling part into unload position. Clamps are in position over the part




Unload clamp drops to grab the machined part. The tailstock mandrel releases the part and retracts to clear for unloading. The loading claw stands by

The unload clamp lifts the finished part up and forward. At the same time the load clamp moves the rough piece into position for chucking







Teamed with an extrusion press at Scovill Manufacturing Co. . . .

## Induction Heating Enters Brass Tube Picture

**LOW FREQUENCY** induction heating has moved into the brass alloy field. At Scovill Manufacturing Co.'s tube mill in Waterbury, Conn., a three-cell unit feeds a Schloemann vertical extrusion press which produces tube shells for cold drawing.

Magnethermic Corp. built the heaters, which operate on standard 60-cycle, 2300-v, 3-phase current. The cylindrical extrusion billets (7 in. in diameter and 11½-in. long) are nicely inside the limit (6 in. in diameter) at which low frequency heating becomes efficient.

**Cycle**—The 140-lb billets are fed by gravity conveyor to each of the three cells in rotation. Each cell brings its billet from room temperature to extrusion temperature in about 4 minutes (extrusion temperature varies with different alloys, but approximates a cherry red).

Billets are hydraulically ejected from the heaters and sent to the press on a 1½-minute cycle. The central heater ejects directly to a roller conveyor; billets from the flanking heaters are moved to the

central conveyor by hydraulically actuated flippers.

**Contrast**—The old way was to heat the billets for 3½-hours in a large oil-fired furnace (10 x 40 ft). The induction unit by comparison is only 7 ft, 6 in. x 11 ft. If you include the electronic control cabinets, it still occupies only half the space of the old furnace.

There's no longer any need to bring in a man in the middle of the night to get the billets heated for the first shift. Start-up time is a matter of minutes.

Greater precision in quality control is another outstanding contribution. Each copper and brass alloy requires a different extrusion temperature, a controlling factor in the uniformity and quality of finished cold-drawn tubing.


With the oil-fired furnace, operators were lucky to hold the temperature of billets entering the press within  $\pm 25^{\circ}\text{F}$ . The induction heaters hold temperatures within  $\pm 15^{\circ}\text{F}$  in regular production, and permit practically instantaneous change in heating temperature for different alloys.

## Continuous Charging

Conveyor system enables foundry to pour 55 to 65 tons of malleable castings an hour

A **MECHANIZED** conveyor system insures constant, uniform charging during the 16 hours of pouring each day at the Cleveland Works of National Malleable & Steel Castings Co.

Heart of the system for each battery of two cupolas is a continuous, circular conveyor system in a pit, about 50 ft in back of the cupolas. Nine cone-bottom Whiting charging buckets travel on this conveyor and pass under the hoppers containing coke, limestone and metal. One bucket of coke and limestone and two buckets of metal are used for each 4-ton charge.



**HOISTING CHARGING BUCKET**


. . . circular conveyor is in foreground

**Central Control**—One operator controls all loading from his station in the center of the pit. Scales under hoppers are placed so that the operator and crane-man can read them from their control stations. When a loaded bucket reaches one of the pickup points, the same operator controls the Whiting horseshoe charger that hoists the bucket, carries it into the wishbone support in the cupola, discharges the load and returns the bucket to its position on the conveyor. Each cupola is served by a 7½-ton horseshoe charger.

The foundry has four Whiting cupolas—two 120-in. units and two 108-in. units.




# Giving a lift to steel mill skip hoists...



Elliott Crocker-Wheeler 600 Series Mill Motors driving a skip hoist in a mid-Western steel mill

## ELLIOTT C-W MILL MOTORS


These dependable motors are naturals under rugged, heavy duty operations. They stand up to punishing overloads, constant starting and stopping, reversing strains, etc., and come back for more every time. Their compact durability plus advanced engineering features assure greater power per standard frame size. The tough cast-steel frame is split for easy access to armature, bearings, and field coils. Standard 600 series motors can be readily adapted to separately forced-ventilated, protected self-ventilated or built-in back gear types. For details, ask your local Elliott field engineer, or write for the Mill Motor Bulletin. Address Elliott Company, Crocker-Wheeler Division, Jeannette, Pa.






The split frame is hinged for easy access to all motor parts.

## ELLIOTT Company

W5-3







## New Jobs for Alloy Plating

A heat treated electroplate of 0.0002-0.0004-in. nickel, plus 0.0001-0.0002-in. cadmium, gives corrosion resistance to low alloy jet engine parts up to 1000° F.

PLATING with single metals sometimes won't do the job.

Pratt & Whitney Aircraft Co. has a case in point. Straight cadmium plate gives good corrosion protection on low-alloy steel parts used in jet engines, but above 550° F, stress-alloying results.

Dimensional requirements restrict the thickness of plate to 0.0005-in. maximum. Single plating with zinc, cadmium, tin, nickel and chromium and combination plating with nickel-zinc were tried. None gave adequate corrosion resistance and freedom from stress-

alloying at elevated temperature.

**Answer** — Tests did show that 0.0003-in. nickel, plus 0.0001-in. cadmium, diffused at 630° F for 1 hour, would withstand 100 hours of salt spray without rusting—even if subjected to 23 hours at 700° F and 1 hour at 1000° F prior to exposure.

Details of the nickel-cadmium plating process were given by R. W. Moeller of Pratt & Whitney at the 42nd annual meeting of the American Electroplaters' Society in Cleveland.

**Plating Solution**—Deposits are

produced from baths found in most plating departments. The nickel solution is of the chloride or chloride-sulphate (Watts) type containing no organic addition agents.

AMS specification 2416 allows use of other nickel solutions to give a low stress plate which will operate at high temperature without embrittling effects—the nickel sulphamate bath is being tried at Pratt & Whitney. Results are promising.

**Second Coat**—Cadmium is plated from a regular cyanide bath. To prevent a stained and finger-printed



pearance, the plate is given a chromate treatment.

Next, all parts are heat treated 1 hr at 630° F to diffuse the nickel and cadmium coatings.

The nickel plate must be deposited uniformly on the complex shapes of the jet engine parts. Because of the relatively poor throwing power of nickel plating baths, special fixtures (see illustrations of page 90) are used to insure uniform coating.


**Proof**—To pass the 100-hr salt spray test without corrosion of the fused 0.0002-0.0004-in. nickel, 0.0001-0.0002-in. cadmium plating, distribution of the plate must insure at least 0.0002-in. nickel at the center as well as at edges of the test panel.

**More Alloy**—Straight alloy plating is doing another job at Pratt Whitney. It's a lead-base alloy plated to contain 11 per cent tin and 7 per cent antimony for bearing use.

The ternary alloy is plated from fluoborate bath (below) which is described in a paper by R. T. Ham and E. J. Roser before the Electroplaters' Society.

#### Lead-Tin-Antimony Plating

Material	Alloy Composition
Lead	11.0%
Antimony	7.0%
Balance	Remainder
	Solution Composition (Nominal) g/l
Lead Fluoborate	100
(lead)	
Fluoborate	30
(Stannous Tin)	
Antimony Fluoborate	6
(Antimony)	
Free Fluoboric Acid	80
Free Acid	25
Hydroquinone	0.5
Temperature	15
(Albumin Peptone)	
Temperature	70°F
Density	0.28 amp./sq. in.
Plating	Mild



## HOW RUGGED IS YOUR ABRASIVE?



Is it rugged enough to prove itself in performance? You can't judge an abrasive by looks, claims or promises. The only test of any abrasive is its *cost per ton of castings cleaned*. Because of exclusive metallurgical characteristics, Malleabrasive gives you the lowest cost per ton cleaned of any premium abrasive on the market! This has been proved in hundreds of production tests by users throughout the country. Prove it in your own production test. We **GUARANTEE** that Malleabrasive will give you lowest cost per ton of castings cleaned.

To order Malleabrasive, or for additional information on running a test, contact Globe Steel Abrasive Co., Mansfield, Ohio.

U. S. Patent #2184926 (Other patents pending)

# MALLEABRASIVE



# Norgren...the most complete line of AIR LINE LUBRICATORS

**FOR BETTER PERFORMANCE • LONGER LIFE • LESS MAINTENANCE COSTS**

**79 MODELS...3 OZ. TO 5 GAL. OIL CAPACITIES... $\frac{1}{4}$ " TO 1 $\frac{1}{2}$ " PIPE SIZES**

## MICRO-FOG LUBRICATORS for Tools, Cylinders and Other Air Equipment

### $\frac{1}{2}$ PT. OIL CAPACITY

#### Constant Oil Level

5 pipe sizes,  $\frac{1}{4}$ " to 1" incl.  
Replaceable, transparent oil  
reservoir. Series 30-41-LC.



#### Without Constant Oil Level

5 pipe sizes,  $\frac{1}{4}$ " to 1" incl.  
Replaceable, transparent oil  
reservoir. Series 30-41-L.



### $\frac{1}{2}$ PT. OIL CAPACITY

$\frac{1}{4}$ " and  $\frac{3}{8}$ " pipe sizes.  
Replaceable, transparent oil  
reservoir. Series 30-40-L.



### 1 QT. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" incl.  
Replaceable metal reservoir.  
Constant Oil Level.  
Series S3406-LC.



### 1 $\frac{3}{4}$ GAL. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" incl.  
Replaceable, metal oil reservoir.  
Constant Oil Level.  
Series X3400-LC.



### 4 $\frac{1}{2}$ GAL. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" incl.  
Replaceable, metal oil reservoir.  
Constant Oil Level.  
Series Y3400-LC.

## MICRO-FOG BEARING LUBRICATORS of 32, 200, 300, 1000 bearing inch capacities

### $\frac{1}{2}$ PT. OIL CAPACITY

Model 30-40-2S— $\frac{1}{4}$ " pipe size.  
32 bearing inch capacity.



### 1 QT. OIL CAPACITY

Model S3406-2S— $\frac{1}{4}$ " pipe size.  
32 bearing inch capacity.  
Model S3406-6S— $\frac{3}{4}$ " pipe size.  
200 bearing inch capacity.  
Model S3406-8S—1" pipe size.  
300 bearing inch capacity.



### $\frac{1}{2}$ PT. OIL CAPACITY

Model 30-41-2S— $\frac{1}{4}$ " pipe size.  
32 bearing inch capacity.

### 1 $\frac{3}{4}$ GAL. OIL CAPACITY

Model X3400-2S— $\frac{1}{4}$ " pipe size.  
32 bearing inch capacity.  
Model X3400-6S— $\frac{3}{4}$ " pipe size.  
200 bearing inch capacity.  
Model X3400-8S—1" pipe size.  
300 bearing inch capacity.




### 4 $\frac{1}{2}$ GAL. OIL CAPACITY

Model Y3400-2S— $\frac{1}{4}$ " pipe size.  
32 bearing inch capacity.

Model Y3400-6S— $\frac{3}{4}$ " pipe size.  
200 bearing inch capacity.

Model Y3400-8S—1" pipe size.  
300 bearing inch capacity.



### Model 33AB-4

$\frac{1}{2}$ " Inlet, 2" Outlets.  
1000 bearing inch capacity.

## OIL-FOG LUBRICATORS for Tools, Cylinders and other Air Equipment

### 3 OZ. OIL CAPACITY

$\frac{1}{4}$ " pipe size.  
Permanent, metal oil reservoir.  
Model 399LB-2.



### $\frac{1}{2}$ PT. OIL CAPACITY

$\frac{1}{4}$ " and  $\frac{3}{8}$ " pipe sizes.  
Replaceable, transparent oil reservoir.  
Reversible. Series O-40.



$\frac{1}{4}$ " pipe size.  
Permanent, metal oil reservoir.  
Model 399-2.



### $\frac{1}{2}$ PT. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" inclusive.  
Replaceable, transparent oil reservoir.  
Reversible.  
Series O-41 and O-42.



$\frac{1}{4}$ " and  $\frac{1}{2}$ " pipe sizes.  
Permanent, metal oil reservoir.  
Series 406.



### 1 QT. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" inclusive.  
Replaceable, metal oil reservoir.  
Reversible.  
Series S406.



### 2 QT. OIL CAPACITY

5 pipe sizes,  $\frac{1}{2}$ " to 1 $\frac{1}{2}$ " inclusive.  
Permanent, metal oil reservoir.  
Series 408.



### 2 GAL. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" inclusive.  
Replaceable, metal oil reservoir.  
Reversible.  
Series X400 and X402.

$\frac{1}{4}$ " and  $\frac{1}{2}$ " pipe sizes.  
Replaceable, metal oil reservoir.  
Series X406.




### 5 GAL. OIL CAPACITY

5 pipe sizes,  $\frac{1}{4}$ " to 1" inclusive.  
Replaceable, metal oil reservoir.  
Reversible.  
Series Y400 and Y402.



$\frac{1}{4}$ " and  $\frac{1}{2}$ " pipe sizes.  
Replaceable, metal oil reservoir.  
Series Y408.

### LUBRO-CONTROL UNIT



showing typical combination of  
Micro-Fog Lubricator with Automatic-Drain  
Filter and Air-Pressure Regulator.

**OVER 1,100,000 NORGREN LUBRICATORS PUT TO USE IN INDUSTRY**




Phone the Norgren representative listed in telephone  
directory classified section under "Norgren Pneumatic  
Products"... or

**WRITE FOR CATALOG** →

showing latest developments in Micro-Fog lubrication and  
giving data on Norgren's complete line of lubricators,  
air filters, pressure regulators, valves, hose assemblies.



## Resistance Welder Joins Strip Steel To Forgings



This double end welder, a new development, cuts production time and costs by simultaneously joining both ends of a strip of steel to a forging. Product: Automatic transmission bands for automobiles.


Flash-butt welding of rolled steel band stock to high-strength forgings produces low cost bands of lasting strength. Welding both ends at once cuts production costs even more. Designed for the lightest possible weight, bands must withstand the severe service of repeated loading.

Welds are of the same cross section as the band, since resistance flash-butt welding gives a 100 per cent efficient joint. No special preparation of the forging is needed to make the welded joint.

After welding, the joints are broached free of flash; the forging is severed and machined.

The welder is adjustable for many band sizes and forging shapes. Write: Taylor-Winfield Corp., Warren, O. Phone: 2252-1

## Automatic Tracing Lathe Hogs 1/2-in. Cuts



This new, sequentially controlled machine takes up four automatically controlled tracing cuts. A two-position automatic indexing tool holder on the trace-slide of the carriage permits heavy roughing with tool, accurate finishing cuts with another. A 12 in. backarm can be set to rock in any time during the carriage cycle for cutting grooves and rough or finish facing.

Feed and speed changes are automatic during a run for optimum cutting speeds on changing diameters or angles. Write: Jones & Lamson Machine Co., 40 Woolson St., Springfield, Vt.

## Lightweight Shipping Container Is Easily Set Up



This compact combination of steel pallet, container sides and top, is fully nestable in its component parts. The cover insures cleanliness and protection of contents during shipment or extended storage.

Tierable, it is a pallet and shipping box combination that can be used for inter or intraplant use.

The unit is manufactured in three standard sizes, which weigh 85, 99.5 and 122 lb each. Parts of a given size are interchangeable. When not in use, the unit can be knocked down and nested for storage.

The unit supports static loads of over 10,000 lb; the bottom alone, over 60,000 lb. Write: Ackerman Mfg. Co., Wheeling, W. Va. Phone: Warwood-175



## Sandblast Nozzles

Venturi nozzles give higher square foot blasting per hour. They will fit all sandblast units in use.



The design produces higher impact and a larger pattern. Uniform impact, without the large fringe area, permits the blaster to clean a surface faster and cleaner.

Orifices are from  $\frac{3}{16}$  to  $\frac{3}{4}$ -in. A tungsten carbide lining insures long life. Write: Clementina Ltd., 2277 Jerrold Ave., San Francisco 24, Calif. Phone: Atwater 2-1429

## Portable Pyrometer

Surface temperature measurements are accurate within 0.5 per cent in the 100 to 2400° F range. The pyrometer may be used for oxidized steel or cast iron, many oxidized nonferrous metals and painted surfaces even though surrounded by cooler air.




The measuring head of the instrument is mounted on a telescopic arm which can be extended to 9 ft. It is connected by a trailing lead to a portable millivolt

meter that is calibrated in degrees. The unit requires no external power supply. Write: Fielden Instrument Division, Robertshaw-Fulton Controls Co., 2920 N. Fourth St., Philadelphia 33, Pa. Phone: Garfield 6-6750

## Single Action Press

This 300-ton hydraulic press is electronically controlled for automatic or semiautomatic operation. The slide return is controlled by either pressure or length of stroke setting. The slide return may be inched up or down or the press



may be manually operated when the slide is in the up position. The pump by-passes at zero pressure. Write: Clifton Hydraulic Press Co., 288 Allwood Rd., Clifton, N. J. Phone: Prescott 8-3474

## Plastic Coated Wire Rope


Preformed galvanized steel or stainless steel wire rope is coated with strong, tough, flexible plastic. Coating thickness varies with diameter.

Wire sizes range from  $\frac{1}{16}$  to  $\frac{1}{4}$ -in.; coating thicknesses are  $\frac{1}{8}$  to  $\frac{3}{8}$ -in. Strengths are from 480 to 7000 lb.

Flexibility of the rope is not affected by the coating. It resists most acids, bases, salts, oils and greases—exceptions: Hydrofluoric acid and methyl ethyl ketone. Write: Macwhyte Co., Kenosha, Wis. Phone: Olympic 7-7121

## Tube Fittings


Perfect sealing even in repeated use is the feature of a new tube fitting design that utilizes an O ring and boss combination to obtain a leak proof seal.



Fitting bodies: Straight, 45 and 90 degree elbows and male outlet and male run tees. They are available to fit  $\frac{1}{4}$ -to-1-in. tubing. Write: Monarch Machine Tool Co., Sidney, O. Phone: 2-1381

## Conveyor Frames

Prepunched conveyor frames make it possible to reposition rollers to meet changes in product or container shapes.



Tearing down the setup is eliminated because roller spacing can be changed quickly with quick-acting spring lock axles. Frames are available in all roller sizes and 11 different frame sizes. Write: Sage Equipment Co., Inc., 30 Essex St., Buffalo 13, N. Y. Phone: Elmwood 5242

## Primer for Magnesium

A new primer can be sprayed or dipped and is fast drying. Designed to check electrolytic decomposition in assemblies where magnesium is joined to a less active metal, it

**360° hoist hook service...**

**WITH -**

**AMERICAN  
MONORAIL**

**PEDESTAL JIB**

Here's the answer to economical local handling service to process machines, particularly beneath heavy mill type cranes... it's the American MonoRail Pedestal Jib.

These jibs are recommended for capacities between 500 to 4,000 pounds, headroom 9 and 12 feet, and boom length 8 and 12 feet... a truly precision built, skillfully engineered job.

Turn to American MonoRail for any overhead handling requirements. Your American MonoRail engineers will be glad to consult with you.



**AMERICAN**

OVERHEAD  
HANDLING  
EQUIPMENT

**MonoRail** COMPANY

13102 ATHENS AVENUE • CLEVELAND 7, OHIO

[IN CANADA—CANADIAN MONORAIL CO., LTD., GALT, ONT.]

Write for Bulletin PJ-1  
For Continuous Flow of Light Loads  
Use Landahl Chainless Conveyors



primer also resists the solvent action of hydraulic fluids in aircraft.

The primer can be applied directly to either untreated or chemically treated magnesium. A film thickness of 1½ mills provides salt spray resistance. *Write:* Stanley Chemical Co., subsidiary of Stanley Works, New Britain, Conn. *Phone:* Baldwin 9-2021

## Barrel Finisher

Three different barrels (capacities, 5 gal and 1.1 and 2 cu ft) are fitted to this finisher. With the smaller barrels on one side of the unit, loads on either end of the shaft are balanced.

Antifriction ball bearings are used throughout; a variable speed drive gives speeds from 12 to 36 rpm. Barrels can be furnished with a vinyl plastic lining.

Movable chutes tilt forward and




backward to help drain liquids and materials separately. *Write:* Rampe Mfg. Co., 14915 Woodworth Ave., Cleveland 10, O. *Phone:* Express 1-8455

## Variable Speed Motor

All gears and mechanical means of power transmission are eliminated. The alternating current motor is capable of running at variable speeds and ranges. It can provide from ½ to 1000 hp, with speeds ranging from 30:1 to 1.5. It operates on 3-phase power at 50, 60 or 400 cycles. The motor is adapted to high-starting torque loads. *Write:* Bogue Electric Mfg. Co., 52 Iowa Ave., Paterson, N. J. *Phone:* Lambert 5-2200

## Beryllium Copper Pins

Slotted chamfered tubular spring pins, heat treated for maximum strength, are from 0.062 to 0.25 in. in diameter and come in a wide range of lengths. Among their applications: They are used with other copper base alloy components where galvanic action



is an important design consideration. The pins are nonmagnetic, have good electrical conductivity and a high resistance to corrosion. *Write:* Elastic Stop Nut Corp., America, Union, N. J. *Phone:* Murdock 6-6000

**the first new  
zinc phosphate  
coatings in  
twenty years!**

Cowles TY-BONDS . . . amorphous and non-sludging . . . are *not* revisions of old-type coatings. They are completely new coatings—completely new formulations.

Cowles TY-BONDS form tight, hard, clean coatings . . . even the most severe bending, flexing or twisting cannot remove TY-BONDS. They cover the metal completely, no pin-points of metal are left unprotected. Old-type coatings leave as much as 60% exposed to corrosion!

Cowles TY-BONDS are economical because they are non-sludging. There is remarkably little waste . . . more than 90% goes into the surface treatment. TY-BONDS save time by reducing coating cycles and tank clean-outs, and meet all government specifications.



Your Cowles Technical Representative will be happy to give you complete information on the uses and applications of Cowles TY-BOND zinc phosphate coatings. Write or call today.

*Cowles*

**CHEMICAL COMPANY**

7016 Euclid Ave. • Cleveland 3, Ohio

# Literature

Directly to the company for a copy

## Rod Weight Table

This table estimates the weight of setting brass rod required for machine products fabrication. 20 pages. Scovill Mfg. Co., Waterbury, Conn.

## Stainless Steel Welds

These rupture properties of chromium-nickel stainless steel weld deposits are given—technical data card 8. Tubular Products Division, Babcock Wilcox Co., Beaver Falls, Pa.

## Stainless Steel

This is a detailed materials selection chart that covers more than 300 stainless steel solutions; engineering data also includes design and dimensional information on stainless steel and its joining—catalog 55, 16 pages. Public Relations Division, Inco Alloy Corp. Hillside 5, N. J.

## Truck Rating Table

This truck selection guide and rating table helps the comparison of job requirements with truck features—catalog 411, 4 pages. Hyster Co., 2902 E. Blackamas, Portland 8, Ore.

## Super Spacers

Operating instructions and specifications on 8 and 12 in. super-spacers and their accessories are detailed—bulletin S-104, 20 pages. Machine Accessory Division, Hartford Machinery Co., Hartford 12, Conn.

## Adhesive Bonding

Selection of the correct formula and process for adhesive bonding is illustrated—8 pages. Rubber Products Corp., Dept. P, 225 Belle Ave., Bloomfield, N. J.

## Dust Collector

These are 24 cost-cutting ideas for dust collectors, platform trucks, cranes and other models. Elwell-Parker Electric Co., 4205 St. Clair Ave., Cleveland 3, O.

## Dust Collector

Crubbing with water for dust collection is described—bulletin 55, 10 pages. National Dust Collector Corp., Machinery Hall Bldg., Chicago 6, Ill.

## Preheated Heat

Examples of infrared uses in baking, preheating and degreasing are illustrated—20 pages. Foster Pressed Steel Corp., Fostoria, O.

## Pool Washing Screen

Diagrams explain how the pool washing screen gives efficient wet screening and effective recovery of materials such as limestone, lead, zinc, iron ore and tungsten—bulletin 07B8214, 8 pages. Allis-Chalmers Mfg. Co., 1021 S. 70th St., Milwaukee, Wis.

## Drills


Installation, operation and maintenance of bench, floor and multispin-dle drills are covered—catalog D-135, 24 pages. Cincinnati Lathe & Tool Co., Cincinnati 9, O.

## Roller Bearings

Featured are ball bearing pillow blocks, flange cartridge mounts and other power transmission machinery. Engineering drawings, dimensions, shaft sizes, weights and radial load ratings are given—bulletin A-638, 52 pages. Dodge Mfg. Corp., Mishawaka, Ind.

## Weldment Cleaning


Abrasive blast cleaning of rust, flux and spatter from welded pieces is covered—bulletin PE-6. American Wheelabrator & Equipment Corp., 1157 S. Byrkit St., Mishawaka, Ind.



Installation of three 351-DBZ-B Thomas Couplings in Columbia Breweries, Tacoma, Wash. between motors and Vilter refrigeration compressors.

Patented Flexible Disc Rings of special steel transmit the power and provide for parallel and angular misalignment as well as free end float.

DISTINCTIVE ADVANTAGES	
FACTS	EXPLANATION
NO MAINTENANCE	Requires No Attention. Visual Inspection While Operating.
NO LUBRICATION	No Wearing Parts. Freedom from Shut-downs.
NO BACKLASH	No Loose Parts. All Parts Solidly Bolted.
CAN NOT "CREATE" THRUST	Free End Float under Load and Misalignment. No Rubbing Action to cause Axial Movement.
PERMANENT TORSIONAL CHARACTERISTICS	Drives Like a Solid Coupling. Elastic Constant Does Not Change. Original Balance is Maintained.



THOMAS COUPLINGS ARE MADE FOR A WIDE RANGE OF SPEEDS, HORSEPOWER AND SHAFT SIZES.

Write for our new Engineering Catalog No. 51A



**THOMAS FLEXIBLE COUPLING COMPANY**  
Largest Exclusive Coupling Manufacturer in the World  
WARREN, PENNSYLVANIA, U.S.A.



Number of  
AMERICAN Phillips Screws  
Driven per Minute

Seconds Saved  
on Every Screw

Result: \_\_\_\_\_ { Lower Costs  
Higher Profits

(Write in your  
own figures)

You start to save money with the first American Phillips Screw driven in your assembly departments. And your savings multiply from then on. No waste motion, less fatigue. No screws dropped or lost. No backing out and re-driving . . . because American Phillips Screws *drive straight automatically*. No broken screwheads. No gouged work-surfaces . . . because the 4-winged driver can't slip out to rip and scar. Now add up all these savings, and you come out as much as 50% ahead of old-fashioned fastening methods.

Next — add up all the advantages of buying *American* . . . still the first-choice source for Phillips Screws. American's capacity, unmatched experience, and *engineering pioneering* mean that you have a top supplier that you can always bank on to keep your production rolling. Yes, you lift a load off your mind when you buy American. Let's talk it over . . . *any time you say*.

✕ marks the spot . . . the mark of extra quality

**AMERICAN SCREW CO.**

PHILLIPS HEADquarters  
WILLIMANTIC, CONNECTICUT

Plants at Willimantic, Conn. and at Norristown, Pa.  
Warehouse and office at Chicago  
Office, Detroit, Michigan



August 1, 1955

# Market Outlook

STEEL production appears headed for a new record. All that's necessary is for the furnaces to average 90 per cent capacity in the closing six months. They operated at 91.6 per cent and produced 57,194,835 net tons in the first half. If they do no better than 90 per cent in last half, 1955 output will come pretty close to 114 million net tons, topping the 1953 record of 111,609,719 tons by more than 2 million.

**ON ITS WAY**—Right now it certainly looks like the industry is on its way to an outstanding performance. Except for to-be-expected maintenance problems, there is nothing in sight to even hint a serious check on production in the months ahead. Since the strike-induced suspensions at end of June, the ingot rate has scored an impressive recovery. It has climbed 22 percentage points the past month. Still the furnaces haven't made up all ground lost because of the strike. Last week, ingot operations stood at 93 per cent, off ½-point from the preceding week and 2 points under the prestrike rate. Last week's decline was due largely to equipment repairs.

**SEASONAL SURPRISE**—What makes the production showing particularly comforting is that July operations ordinarily are hampered by vacations and hot weather. The seasonal factors were present, but, surprisingly, they were offset by relentless demand pressure. New business has continued to come out despite higher prices, while anticipated order cutbacks from the automotive industry and other consumers haven't materialized.


**MILLS OVERSOLD**—Producers are oversold

on about every product. Carry-over into the fourth quarter may necessitate blanking out up to six weeks of production. Certain sheetmakers are cutting back fourth quarter allotments as much as 35 per cent. Some flat-rolled producers are out of the market for the remainder of the year, not only on hot and cold-rolled grades but on galvanized and electrical sheets as well as other specialties. Rails appear to be the only major product not under extreme pressure. With railroad car needs mounting and larger ship requirements in the offing, fourth quarter steel supply promises to be the most stringent since early 1953.

**INVENTORIES LOW**—Failure of a third quarter slump to materialize has producers guessing to some extent. Consumers evidently didn't replenish stocks materially in recent months. Still, since summer ordinarily is a period of stock accumulation, inventories are bound to get increasing attention as weeks pass. As in 1953, stocks in the hands of consumers could be the key to the market situation in the months ahead.

**PRICES FIRM**—Except for a downward revision on cooperage hoops from \$5.325 per 100 lb to \$4.75, representing a net increase of \$5.50 per ton over the price in effect before the recent general steel increase, prices are firm. Foundry coke, however, is up \$1.25 a ton at several points, and the increase is expected to become general. Scrap also continues to rise, the composite on steelmaking grades being up \$1.83 to \$42. The finished steel composite is steady at \$126.64.

## NATIONAL STEELWORKS OPERATIONS



## DISTRICT INGOT RATES

(Percentage of capacity engaged)

	Week Ended July 31	Change	Same Week 1954	Same Week 1953
Pittsburgh .....	99.5	+ 2.5*	80	95.5
Chicago .....	96	- 0.5*	66.5	90
Mid-Atlantic .....	94	— 1	57	97.5
Youngstown .....	98	0	64	105
Wheeling .....	92.5	0	76	99
Cleveland .....	88	-10*	65	102
Buffalo .....	105	0	56	106.5
Birmingham .....	93.5	0	75	100
New England .....	82	- 1	55	89
Cincinnati .....	86	+ 2	55	90.5
St. Louis .....	97.5	+ 9.5	47.5	93
Detroit .....	89.5	+ 2	54.5	102
Western .....	101	+ 2	82	107.5
National Rate ..	93	- 0.5	64	96.5

## INGOT PRODUCTION†

	Week Ended July 31	Week Ago	Month Ago	Year Ago
INDEX .....	142.2†	138.6	106.8	95.4
(1947-1949=100)				
NET TONS ...	2,284†	2,195	1,716	1,532
(In thousands)				

\*Change from preceding week's revised rate.  
†Estimated. ‡Amer. Iron & Steel Institute.  
Weekly capacity (net tons): 2,413,278 in 1955;  
2,384,549 in 1954; 2,254,459 in 1953.



# Price Indexes and Composites

## FINISHED STEEL PRICE INDEX (Bureau of Labor Statistics)

	July 26 1955	July 19 1955	Month Ago	June Average
(1947-1949=100) .....	153.9	153.9	144.9	144.8

## AVERAGE PRICES OF STEEL (Bureau of Labor Statistics)

Week Ended July 26

Prices include mill base prices and typical extras and deductions. Units are 100 lb except where otherwise noted in parentheses. For complete description of the following products and extras and deductions applicable to them write to STEEL.

Rails, Standard, No. 1...	\$4.800	Sheets, Electrical .....	\$10.200
Rails, Light, 40 lb .....	6.217	Strip, C.R., Carbon .....	7.993
Tie Plates .....	5.625	Strip, C.R., Stainless, 430	
Axles, Railway .....	8.000	(lb) .....	0.444
Wheels, Freight Car, 33		Strip, H.R., Carbon .....	5.350
in. (per wheel) .....	52.50	Pipe, Black, Buttweild (100	
Plates, Carbon .....	4.950	ft) .....	16.366
Structural Shapes .....	4.867	Pipe, Galv., Buttweild (100	
Bars, Tool Steel, Carbon		ft) .....	19.971
(lb) .....	0.460	Pipe, Line (100 ft) .....	158.925
Bars, Tool Steel, Alloy, Oil		Casing, Oil Well, Carbon	
Hardening Die (lb) .....	0.560	(100 ft) .....	165.120
Bars, Tool Steel, H.R.,		Casing, Oil Well, Alloy	
Alloy, High Speed W		(100 ft) .....	244.670
6.75, Cr 4.5, V 2.1, Mo		Tubes, Boiler (100 ft) .....	39.470
5.5, C 0.60 (lb) .....	1.185	Tubing, Mechanical, Car-	
Bars, Tool Steel, H.R.,		bon .....	20.980
Alloy, High Speed W 18,		Tubing, Mechanical, Stain-	
Cr 4, V 1 (lb) .....	1.680	less, 304 (100 ft) .....	178.952
Bars, H.R., Alloy .....	9.375	Tin Plate, Hot-dipped, 1.25	
Bars, H.R., Stainless, 303		lb .....	8.533
(lb) .....	0.450	Tin Plate, Electrolytic,	
Bars, H.R., Carbon .....	5.350	0.25 lb .....	7.233
Bars, Reinforcing .....	5.313	Black Plate, Canmaking	
Bars, C.F., Carbon .....	8.660	Quality .....	6.333
Bars, C.F., Alloy .....	12.175	Wire, Drawn, Carbon...	8.575
Bars, C.F., Stainless, 302		Wire, Drawn, Stainless,	
(lb) .....	0.468	430 (lb) .....	0.578
Sheets, H.R., Carbon ....	5.145	Bale Ties (bundle) .....	6.473
Sheets, C.R., Carbon .....	6.239	Nails, Wire, 8d Common.	8.618
Sheets, Galvanized .....	7.690	Wire, Barbed (80-rod spool)	7.847
Sheets, C.R., Stainless,		Woven Wire Fence (20-rod	
302 (lb) .....	0.583	roll) .....	18.635

## STEEL'S FINISHED STEEL PRICE INDEX\*

	July 27 1955	Week Ago	Month Ago	Year Ago	5 Yrs. Ago
Index (1935-39 av.=100)...	207.63†	207.63	194.53	195.87	156.69
Index in cents per lb .....	5.625†	5.625	5.270	5.306	4.245

†Revised

## STEEL'S ARITHMETICAL PRICE COMPOSITES

Finished Steel, NT* .....	\$126.64	\$126.64	\$118.45	\$117.43	\$94.36
No. 2 Fdry, Pig Iron, GT..	58.99	58.99	56.54	56.54	46.85
Basic Pig Iron, GT .....	58.49	58.49	56.04	56.04	45.97
Malleable Pig Iron, GT....	59.77	59.77	57.27	57.27	47.49
Steelmaking Scrap, GT ....	42.00	40.17	35.00	27.33	37.33

\*For explanation of weighted index see STEEL, Sept. 19, 1949, p. 54; for arithmetical price composite, STEEL, Sept. 1, 1952, p. 130.

# Comparison of Prices

Comparative prices by districts, in cents per pound except as otherwise noted. Delivered prices based on nearest production point.

## FINISHED STEEL

	July 27 1955	Week Ago	Month Ago	Year Ago	5 Yrs.
Bars, H.R., Pittsburgh ....	4.65	4.65	4.30	4.30	3
Bars, H.R., Chicago .....	4.65	4.65	4.30	4.30	3
Bars, H.R., deld. Philadelphia	4.90	4.90	4.55	4.55	3
Bars, C.F., Pittsburgh .....	5.90	5.90	5.40	5.40	4.10
Shapes, Std., Pittsburgh ....	4.60	4.60	4.25	4.25	3
Shapes, Std., Chicago .....	4.60	4.60	4.25	4.25	3
Shapes, deld., Philadelphia ..	4.88	4.88	4.53	4.53	3
Plates, Pittsburgh .....	4.50	4.50	4.225	4.225	3
Plates, Chicago .....	4.50	4.50	4.225	4.225	3
Plates, Coatesville, Pa. ....	4.50	4.50	4.225	4.225	3
Plates, Sparrows Point, Md..	4.50	4.50	4.225	4.225	3
Plates, Claymont, Del. ....	4.50	4.50	4.225	4.225	3
Sheets, H.R., Pittsburgh ...	4.325	4.325	4.05	4.05	3
Sheets, H.R., Chicago .....	4.325	4.325	4.05	4.05	3
Sheets, C.R., Pittsburgh ....	5.325	5.325	4.95	4.95	4
Sheets, C.R., Chicago .....	5.325	5.325	4.95	4.95	4
Sheets, C.R., Detroit .....	5.325-5.425	5.325-5.425	5.10	5.10	4
Sheets, Galv., Pittsburgh ...	5.55	5.55	5.45	5.45	4
Strip, H.R., Pittsburgh ....	4.325	4.325	4.05	4.425	3.25
Strip, H.R., Chicago .....	4.325	4.325	4.05	4.05	3
Strip, C.R., Pittsburgh .....	6.317	6.317	5.75	5.75	4.15
Strip, C.R., Chicago .....	6.35-6.45	6.45-6.55	5.55	6.00	4
Strip, C.R., Detroit .....	6.35	6.35-6.55	5.55	5.60-5.90	4.35
Wire, Basic, Pittsburgh .....	6.25	6.25	5.75	5.75	4
Nails, Wire, Pittsburgh ....	7.60	7.60	6.85	6.85	5
Tin plate (1.50 lb), box, Pitts.	\$9.05	\$9.05	\$9.05	\$8.95	\$7

## SEMIFINISHED STEEL

Billets, Forging, Pitts. (NT)	\$84.50	\$84.50	\$78.00	\$78.00	\$6
Wire Rods, $\frac{3}{8}$ -" Pitts....	5.025	5.025	4.675	4.525	\$6

## PIG IRON, Gross Ton

Bessemer, Pitts. ....	\$59.50	\$59.50	\$57.00	\$57.00	\$18
Basic, Valley .....	58.50	58.50	56.00	56.00	46
Basic, deld. Phila. ....	56.16	56.16	56.66	56.66	49
No. 2 Fdry, Pitts. ....	59.00	59.00	56.50	56.50	46
No. 2 Fdry, Chicago .....	59.00	59.00	56.50	56.50	46
No. 2 Fdry, Valley .....	59.00	59.00	56.50	56.50	46
No. 2 Fdry, deld. Phila. ....	59.66	59.66	56.16	56.16	46
No. 2 Fdry, Birm. ....	55.00	55.00	52.88	52.88	42
No. 2 Fdry (Birm.) deld. Cin.	62.70	62.70	60.58	60.43	42
Malleable, Valley .....	59.00	59.00	56.50	56.50	46
Malleable, Chicago .....	59.00	59.00	56.50	56.50	46
Ferromanganese, Duquesne.	190.00†	190.00†	190.00†	200.00†	175

\*75-82% Mn, gross ton, Etna, Pa. †74-76% Mn, net ton.

## SCRAP, Gross Ton (Including broker's commission)

No. 1 Heavy Melt, Pitts...	\$42.00	\$39.50	\$35.50	\$28.50	\$41
No. 1 Heavy Melt, E. Pa....	43.00	42.00	39.00	24.50	33
No. 1 Heavy Melt, Chicago.	41.00	39.00	35.00	29.00	38
No. 1 Heavy Melt, Valley..	41.50	40.50	37.50	26.50	40
No. 1 Heavy Melt, Cleve....	39.50	38.50	35.00	24.50	38
No. 1 Heavy Melt, Buffalo.	34.50	34.50	29.50	26.50	36
Rails, Re-rolling, Chicago ..	59.00	59.00	52.50	43.50	44
No. 1 Cast, Chicago .....	45.50	45.50	42.50	35.50	44

## COKE, Net Ton

Beehive, Furn, Connsvl. ...	\$13.75	\$13.75	\$13.75	\$14.75	\$14
Beehive, Fdry, Connsvl....	16.75	16.75	16.75	16.75	15
Oven, Fdry, Chicago .....	24.50	24.50	24.50	24.50	21

Quotations in cents per pound based on COPPER, deld. Conn. Valley; LEAD, common grade, deld. St. Louis; ZINC, prime western, E. St. Louis; STRAITS, deld. New York; NICKEL, electrolytic cathodes, 99.9%, base size refinery, unpacked; ALUMINUM, primingots, 99+%, deld.; MAGNESIUM, 99.8%, Freeport, Tex.

# Daily Nonferrous Price Record

	Price July 27	Last Change	Previous Price	June Avg.	May Avg.	July 1954 Avg.
Copper .....	36.00	Mar. 29, 1955	33.00	36.000	36.000	30.000
Lead .....	14.80	Oct. 4, 1954	14.55	14.800	14.800	13.800
Zinc .....	12.50	June 16, 1955	12.00	12.250	12.000	11.000
Tin .....	98.25	July 27, 1955	98.625	98.668	91.410	98.558
Nickel .....	64.50	Nov. 24, 1954	60.00	64.500	64.500	60.000
Aluminum ..	23.20	Jan. 12, 1955	22.20	23.200	23.200	21.500
Magnesium ..	28.50	Mar. 21, 1955	27.00	28.500	28.500	27.000

## What You Can Use the Markets Section for:

- A source of price information. Current prices are reported each week. Price changes are shown in italics. Price trends are shown in tables of indexes and comparisons.
- A directory of producing points. Want to know who makes something, or where it is made? The steel price tables alphabetically list the cities of production and indicate the producing company. If you are a buyer, you may want to make a map showing comparative distances of sources of supply and to help you compute freight costs. If you are a seller of supplies you can make a map to spot your sales possibilities.

- A source of price data for making your own comparisons. Maybe you want to keep a continuous record of price spread between various forms of steel. You can get your base price information from STEEL's price tables.
- A source of information on market trends. Newsy items tell you about the supply-demand situation of materials, including iron and steel, nonferrous metals and scrap. Other articles analyze special situations of interest and importance to you.
- Reports on iron and steel production, and materials and product shipments.

Announcing the *-Newly Designed-* Integral

**ALL-STEEL**

# FALK Motoreducer

(Gearmotor Type-Supplementing Falk All-Motor Line)

... with completely standard round-frame, D-flange motor


## Check and Compare these features...

Meet a faithful old friend in a new, modern dress! The famous, time-proved Integral Type *all-steel* Falk Motoreducer (Supplementing Falk All-Motor Line) has been redesigned into a compact, streamlined unit providing the utmost in space economy—but retaining all the application versatility, long-life performance, easy-maintenance features and superior structural qualities that have made Falk Motoreducers the recognized standard throughout industry.

In this new Integral unit—rated in accordance with AGMA standards—a *completely standard* round-frame, D flange NEMA motor is mounted directly on the all-steel Motoreducer housing. The motor remains a separate piece of equipment, readily replaceable with any other type or make. Output speed (ratio) can be changed within unit's torque capacity without modifying motor. Size and arrangement of the standard housing permit wide ratio range—from 3.36:1 to 542:1.

In order to meet the greatest number of industrial application needs, the newly designed Integral Motoreducers are available in horizontal and vertical models, both in concentric and right-angle types; double, triple and quadruple reduction; horsepower range, 1 to 40 HP. Prompt stock shipment in standard ratios is offered.

Whatever your reduction requirements, you get greatest dollar-for-dollar value in the long run by standardizing on Falk products. Write for Bulletin 3104.



Every FALK Motoreducer has these "In-built" Factors—

**Precision Gearing.** Heat treated alloy steel, precision cut and shaved helical gearing throughout . . . quiet-operating crown shaved pinions . . . taper bored gears for easy ratio changes.

**All-steel Housings.** Unbreakable, strong, rigid. Generous overhung load capacities provided by wide bearing spans, large shafts and bearings.


**Streamlined inside and outside.** Smooth, clean surfaces; machine welded construction conforms to NEMA motor frames.

**Positive Lubrication.** Large sump capacity . . . oil-tight construction assures clean lubricant . . . direct dip of revolving elements provides positive lubrication at all speeds.

**Wide Speed Range.** Selective ratio combinations provide output speeds from 1.5 rpm to 1430 rpm with stock gears.

**Sealed Housings.** Dual closures and one-way vents keep oil in, dust and moisture out. Units are splash-proof, leakproof, dustproof.

The basic E design permits maximum use of standardized parts . . . closer control over materials, processing, inspection and assembly . . . resulting in faster delivery from interchangeable stocked assemblies.



# FALK

... a good name in industry

THE FALK CORPORATION • 3001 W. Canal St. • Milwaukee 8, Wis.

WRITE FOR BULLETIN 3104



# Nonferrous Metals

**Government restricts exports of copper scrap and refined copper of foreign origin. But the total supply advantage for domestic consumers won't ease the pinch**

Nonferrous Metal Prices, Pages 104 & 105

THE COPPER SHORTAGE is becoming increasingly difficult to live with, and nobody knows that better than the government. In an attempt to relieve the situation a little, the Commerce department last week cut third-quarter export quotas of copper scrap by 45 per cent, compared with what they were the second quarter.

The percentage is about what was expected in view of the stand taken by the State department. U. S. exports, especially to Germany, have been a vital part of the nation's efforts to get Europe back on her feet. The State department didn't want to disrupt that program. But the needs of our own economy were strong enough to call for some cutback, even though it was not so much as domestic users desired.

**Not Much**—What does it all amount to? In terms of tonnage, it's just a drop in the bucket, but right now even that is mighty important. Total tonnage of the second-quarter scrap quota was 16,000 tons—5000 tons for unalloyed, 10,000 for alloyed and 1000 for alloyed ingots. The new figures are 2750 tons for unalloyed copper scrap, 5500 for alloyed and 550 for alloy ingots. The net advantage to domestic users for all scrap in the third quarter is 7200 tons—not much when you consider that by last week the industry had lost well over 50,000 tons of basic production because of the copper strike.

At the same time, the Commerce department announced it has set a quota of 54,000 tons on exports of refined copper of foreign origin in the third quarter. This represents no gain in supply, but it does assure the industry that such exports will not rise above the 1954 rate.

**No Break**—Last week left plenty of room for improvement in the negotiations going on between the union and western producers. In fact, the situation was so bad it seems that further developments could only be for the better. After Anaconda Co. settled, it was a good bet the union would come to terms with Kennecott, Phelps Dodge and American Smelting & Refining. But despite efforts of producers to follow the Anaconda and steel settlements, the union took a negative position, which continues to baffle most observers. What is to be gained by either party by further pro-

longing the strike is a question nobody can answer.

In an attempt to ease the tension, A. D. Ross Fraser, president of Rome Cable Corp. and chairman of the wire and cable section of the National Electrical Manufacturers Association, sent a telegram to President Eisenhower asking him to invoke the 60-day cooling-off period provided for in the Taft-Hartley Act. If this happens, workers will return to the mines and smelters for at least two months.

**New High in London**—In the meantime, the London market advanced to the highest point of the year last week when it stood at better than 46 cents a pound. The last time it reached the 46-cent level was on Mar. 22. The domestic shortage, plus this high foreign price, has created record-high prices in the open market here, too, for copper and scrap.

## ODM Studies Nickel Allocations

Even though there are no strikes in the nickel and aluminum industries, metal is nearly as hard to get there, too. Nickel continues to be the mystery metal as defense requirements outdistance stated requirements drawn from bills of materials. The Business & Defense Services Administration has asked Defense Mobilizer Arthur S. Flemming to release an additional 1 million lb of nickel from stockpile-destined shipments, bringing the total third-quarter release up to 5 million lb. But Mr. Flemming has said he has no intention of making deferments indefinitely. He also wants to know why defense shipments are exceeding estimated needs before granting too much relief to civilian users. Some industry spokesmen have contended right along that those estimates were low, and now say that there is nothing fishy in the beefed-up orders.

If the Office of Defense Mobilization decides that the demands of national defense have been the cause of the shortage, then the provisions of the Defense Production Act permitting allocations may be put into effect. Allocation controls have been under consideration for about two months (STEEL, June 6, p. 47).

## Setasides Have Little Effect

The new setasides announced for the fourth quarter will have little, if

any, effect on civilian consumption of aluminum, copper and steel. ODM allocated 121 million lb of aluminum, which is greater than the third-quarter figure, but not enough to disturb the civilian supply, tight as it is. The new setasides represents about 1 per cent of total supply, only 1 per cent more than in the present quarter. One aluminum official said, "The difference is insignificant. We have learned to live with the setasides and are used to minor fluctuations in the amount. We could use the extra metal, but with production increasing we won't be any worse off in fourth quarter than we are now."

Copper received a cut for fourth quarter, down to 53 million lb, which may help the civilian supply somewhat. But, at present, it is an academic question of how much. Steel allocation for defense users also was down from the third quarter, having been set at 675,000 tons.

## Profits, Earnings Look Good

Midyear financial reports from nonferrous companies are beginning to show up, and they confirm the feeling of prosperity that pervaded the industry until the copper strike came along. Both sales and earnings were up in most cases. National Lead Co. reports 34 per cent greater earnings on 23 per cent greater sales during the first six months of 1955, compared with the same period last year. St. Joseph Lead Co. reports earnings of \$6,741,906, compared with \$2,749,192; and sales of \$62,427,726, compared with \$39,927,130. Climax Molybdenum Co. had record sales and earnings in both the second quarter and first half. Bridgeport Brass Co. had higher sales for the first half but lower profit. The latter was accounted for by the heavy cost starting the company's aluminum division at Adrian, Mich. Not until June did that division break into the black. Revere Copper & Brass Co. shows an increase of 27.5 per cent sales and 26.6 per cent in earnings over the first half of 1954.

## Minerals Bill Passes House

Chances are good that the Senate will approve the bill passed by the House calling for continued stockpiling of tungsten, manganese, chromite, mica, asbestos, beryl and columbium-tantalum bearing ores and concentrates. The bill will require ODM to buy these minerals until July 1958, even though the goals set by years ago have been reached.

# American Zinc inc and its products from A to

## HERE'S WHERE YOUR AMERICAN ZINC COMES FROM



### PRODUCERS OF

ALL GRADES OF SLAB ZINC  
ZINC ANODES (Plating & Galvanic)  
METALLIC CADMIUM  
SULPHURIC ACID  
LEAD-FREE and LEADED ZINC OXIDES  
ZINC CARBONATE  
GERMANIUM DIOXIDE  
AGRICULTURAL LIMESTONE  
CRUSHED STONE

*Distributors for*

**American  
Zinc sales  
company**

AMERICAN ZINC, LEAD & SMELTING COMPANY  
Columbus, Ohio • Chicago • St. Louis • New York • Detroit • Pittsburgh



# Nonferrous Metals

Cents per pound, carlots, except as otherwise noted.

## PRIMARY METALS AND ALLOYS

**Aluminum:** 99 + %, ingots 23.20, pigs 21.50, 10,000 lb or more, f.o.b. shipping point. Freight allowed on 500 lb or more.

**Aluminum Alloy:** No. 13, 12% Si, 25.00; No. 43, 5% Si, 24.80; No. 142, 4% Cu, 1.5% Mg, 2% Ni, 26.50; No. 185, 4.5% Cu, 0.8% Si, 25.90; No. 214, 3.5% Mg, 26.40; No. 356, 7% Si, 0.3% Mg, 24.90.

**Antimony:** R.M.M. brand, 99.5%, 28.50, Lone Star brand, 29.00, f.o.b. Laredo, Tex., in bulk. Foreign brands, 99.5%, 27.00-28.00, New York, duty paid, 10,000 lb or more.

**Beryllium:** 97%, lump or beads, \$71.50 per lb, f.o.b. Cleveland or Reading, Pa.

**Beryllium Aluminum:** 5% Be, \$72.75 per lb of contained Be, f.o.b. Reading, Pa., Elmore, O.

**Beryllium Copper:** 3.75-4.25% Be, \$40 per lb of contained Be, with balance as Cu at market price on shipment date, f.o.b. Reading, Pa., or Elmore, O.

**Bismuth:** \$2.25 per lb, ton lots.

**Cadmium:** Sticks and bars, \$1.70 per lb, deld. Cobalt: 97-99%, \$2.60 per lb for 550-lb keg; \$2.62 per lb for 100-lb case; \$2.67 per lb under 100 lb.

**Columbium:** Powder, \$119.20 per lb, nom.

**Copper:** Electrolytic, 36.00 deld. Conn. Valley; 36.00 deld. Midwest; Lake, 36.00 deld; Fire refined, 35.75 deld.

**Germanium:** 99.9%, \$295 per lb, nom.

**Gold:** U. S. Treasury, \$35 per oz.

**Indium:** 99.9%, \$2.25 per troy oz.

**Iridium:** \$90-\$100 nom, per troy oz.

**Lead:** Common, 14.80, chemical, 14.90, cor-rodng, 14.90, St. Louis. New York basis, add 0.20.

**Lithium:** 99%+, cups or ingot, \$11.50; rod, \$13.50; shot or wire, \$14.50, f.o.b. Minneapolis, 100 lb lots.

**Magnesium:** 99.8%, self-palletizing pig, 28.50; notched ingot, 29.25, 10,000 lb or more, f.o.b. Freeport, Tex. For Port Newark, N. J., add 1.40 for pig and 1.45 for ingot; for Madison, Ill., add 1.20 for pig and 1.25 for ingots; for Los Angeles, add 2.50 for both pig and ingot. Sticks 1.3 in. diameter, 49.00, 100 to 499 lb, f.o.b. Madison, Ill.

**Magnesium Alloys:** AZ31C and alloys C, H, G and R, 34.00; alloy M, 36.00, 10,000 lb or more, f.o.b. Freeport, Tex. For Port Newark, N. J., add 1.40; for Madison, Ill., add 0.50; for Los Angeles, add 2.50.

**Mercury:** Open market, spot, New York, \$262-\$264 per 76-lb flask.

**Molybdenum:** Powder 99% hydrogen reduced, \$3-\$3.25 per lb; pressed ingot, \$4.06 per lb; sintered ingot, \$5.53 per lb.

**Nickel:** Electrolytic cathodes, sheets (4 x 4 in. and larger), unpacked, 64.50; 10-lb pigs, unpacked, 67.65; "XX" nickel shot, 69.00; "F" nickel shot or ingots for addition to cast iron, 64.50; prices f.o.b. Port Colborne, Ont., including import duty. New York basis, add 0.92.

**Osmium:** \$80-\$100, nom., per troy oz.

**Palladium:** \$22-\$24 per troy oz.

**Platinum:** \$80-\$85 per troy oz from refineries.

**Radium:** \$16-\$21.50 per mg radium content, depending on quantity.

**Rhodium:** \$118-\$125 per troy oz.

**Ruthenium:** \$45-\$55 per troy oz.

**Selenium:** 99.5%, \$6-\$7.25 per lb.

**Silver:** Open market, 90.75 per troy oz.

**Sodium:** 16.50, c.i.; 17.00, l.c.i.

**Tantalum:** Sheet, rod, \$68.70 per lb; powder, \$56.63 per lb.

**Tellurium:** \$1.75 per lb.

**Thallium:** \$12.50 per lb.

**Tin:** Straits, N. Y., spot, 98.25; prompt, 98.00.

**Titanium:** Sponge, 99.3%, grade A-1 ductile (0.3% Fe max), \$3.95, grade A-2 (0.5% Fe max), \$3.50 per pound.

**Tungsten:** Powder, 98.8%, carbon reduced, 1000-lb lots, \$4.35-\$4.40 per lb, nom., f.o.b. shipping point; less than 1000 lb add 15.00; 99 + % hydrogen reduced, \$4.65. Treated ingots, \$6.70.

**Zinc:** Prime Western, 12.50; brass special, 12.75; intermediate, 13.00, E. St. Louis, freight allowed over 0.50 per pound. High grade, 13.85; special high grade, 14.00, deld. Diecast-ing alloy ingot No. 3, 16.50; Nos. 2 and 5, 17.00, deld.

**Zirconium:** Ingots, commercial grade, \$14.40 per lb; low-hafnium reactor grade, \$23.07.

**Sponge:** \$7.50 per lb. Powder electronics grade, \$15 per lb; flash grade, \$11.50.

(Note: Chromium, manganese and silicon metals are listed in ferroalloy section.)

## SECONDARY METALS AND ALLOYS

**Aluminum Ingot:** Piston alloys, 28.75-30.75; No. 12 foundry alloy (No. 2 grade), 27.50-28.00; 5% silicon alloy, 0.60 Cu max, 29.25-30.25; 13 alloy, 0.60 Cu max, 29.50-30.25; 195 alloy, 29.25-30.25; 108 alloy, 28.00-28.50. Steel deoxidizing grades, notch bars, granulated or shot; Grade 1, 23.50-29.50; grade 2, 27.50-28.50; grade 3, 26.50-27.50; grade 4, 26.00.

**Brass Ingot:** Red brass, No. 115, 37.50; tin bronze No. 225, 49.50; No. 245, 42.75; high-leaded tin bronze No. 305, 40.75; No. 1 yellow No. 405, 31.75; manganese bronze No. 421, 34.75.

**Magnesium Alloy Ingot:** AZ63A, 32.00; AZ91B, 32.00; AZ91C, 32.00; AZ92A, 32.00.

## NONFERROUS MILL PRODUCTS

### BERYLLIUM COPPER

(Base prices per lb, plus mill extras, 2000 to 5000 lb, f.o.b. Temple, Pa.; nominal 1.9% Be alloy) Strip, \$1.74; rod, bar, wire, \$1.71.

### COPPER WIRE

Bare, soft, f.o.b. eastern mills, 100,000-lb lots, 41.35; 30,000-lb lots, 41.45; l.c.i., 41.98. Weatherproof, 100,000-lb, 40.78; 30,000 lb, 41.03; l.c.i., 41.53. Magnet wire deld., 15,000 lb or more, 48.15; l.c.i., 48.90.

### LEAD

(Prices to jobbers, f.o.b. Buffalo, Cleveland, Pittsburgh) Sheets, full rolls, 140 sq ft or more, \$20 per cwt; pipe, full coils, \$20 per cwt; traps and bends, list prices plus 30%.

### TITANIUM

(Prices per lb, 10,000 lb and over, f.o.b. mill) Sheets, \$14.00-\$14.50; sheared mill plate, \$11.00; strip, \$14.00-\$14.50; wire, \$10.00-\$10.50; forging billets, \$8.75; hot-rolled and forged bars, \$8.75.

### ZINC

(Prices per lb, c.i., f.o.b. mill) Sheets, 23.00; ribbon zinc in coils, 20.00-20.50; plates, 19.00.

### ZIRCONIUM

Plate, \$22; H.R. strip, \$19; C.R. strip, \$29; forged or H.R. bars, \$17; wire, 0.015 in., 1.00c per linear foot.

## NICKEL, MONEL, INCONEL

	"A" Nickel	Monel	Inconel
Sheet, C.R. ....	102	78	99
Strip, C.R. ....	102	87	125
Plate, H.R. ....	97	82	95
Rod, Shapes H.R. ....	87	69	93
Rod, Shapes C.R. ....	91	75	115
Seamless Tubes ....	122	108	153
Shot, Blocks ....	...	65	...

## ALUMINUM

**Screw Machine Stock:** 5000 lb and over.  
Diam. (in.) or —Round— —Hexagonal—  
across flats 2011-T3 2017-T4 2011-T3 2017-T4

Drawn				
0.125	63.5	62.0	...	...
0.156-0.172	53.9	52.3	...	...
0.188	53.9	52.3	...	66.8
0.219-0.234	51.1	49.5	...	...
0.250-0.291	51.1	49.5	...	63.7
0.313	51.1	49.5	...	60.8

Cold-finished				
0.375-0.547	49.9	47.5	59.8	57.2
0.563-0.688	49.9	47.5	56.9	53.7
0.750-1.000	48.7	46.3	52.1	50.6
1.063	48.7	46.3	...	48.9
1.125-1.500	46.9	44.6	50.4	48.9

Rolled				
1.563	45.7	43.4	...	...
1.625-2.000	45.1	42.8	...	47.2
2.125-2.500	44.0	41.7	...	...
2.563-3.375	42.7	40.5	...	...

## BRASS MILL PRICES

	Sheet, Strip, Plate	Rod	Wire	Seamless
Copper .....	54.76b	52.36c	...	54.82
Yellow Brass .....	46.27	37.22d	46.81	49.18
Red Brass, 85% .....	50.99	50.93	51.53	53.80
Low Brass, 80% .....	49.75	49.69	50.29	52.56
Naval Brass .....	49.99	44.30	57.05	53.15
Com. Bronze, 90% .....	52.78	52.72	53.32	55.84
Nickel Silver, 10% .....	60.20	62.53g	62.53	...
Phos. Bronze, A, 5% .....	73.03	73.53	73.53	74.71
Silicon Bronze .....	58.82	58.01	58.86	60.80e
Manganese Bronze .....	53.73	47.83	58.24	...
Muntz Metal .....	48.14	43.95	...	...

a. Cents per lb, f.o.b. mill; freight allowed on 500 lb or more. b. Hot-rolled. c. Cold-drawn. d. Free cutting. e. 3% silicon. f. Prices in cents per lb for less than 20,000 lb, f.o.b. shipping point. On lots over 20,000 lb at one time, of any or all kinds of scrap, add 1 cent per lb. g. Lead.

## ALUMINUM

**Sheets and Circles:** 1100 and 3003 mill finish (30,000 lb base; freight allowed over 499 lb).

Thickness Range Inches	Flat Sheet	Flat Sheet Circles*	Coiled Sheet	Coiled Sheet Circles
0.249-0.136	35.9	40.4	...	...
0.135-0.096	36.4	41.3	...	...
0.095-0.077	37.1	42.3	34.6	39.3
0.076-0.061	37.7	43.2	34.8	39.3
0.060-0.048	38.2	43.6	35.1	40.0
0.047-0.037	38.7	44.5	35.6	40.0
0.037-0.030	39.1	45.0	36.0	41.0
0.029-0.024	39.7	45.5	36.3	41.0
0.023-0.019	40.4	46.9	37.1	41.0
0.018-0.017	41.2	...	37.7	...
0.016-0.015	42.1	...	38.5	...
0.014	43.1	...	39.5	...
0.013-0.012	44.3	...	40.2	...
0.011	45.3	...	41.4	...
0.010-0.0095	46.5	...	42.5	...
0.009-0.0085	47.8	...	44.0	...
0.008-0.0075	49.4	...	45.2	...
0.007	50.9	...	46.7	...
0.006	52.5	...	48.1	...

\*48 in. max diam. †26 in. max diam.

## ALUMINUM

**Plates and Circles:** Thickness 0.250-3 in. 24-60 in. width or diam, 72-240 in. lengths.

Alloy	Plate Base	Circle Base
1100-F, 3003-F ....	34.6	39.5
5050-F .....	35.7	38.5
3004-F .....	36.7	41.6
5052-F .....	38.4	43.4
6061-T6 .....	39.6	44.0
2024-T4* .....	41.8	47.9
7075-T6* .....	49.6	56.2

\*24-48 in. widths or diam, 72-180 in. lengths.

## ALUMINUM

**Forging Stock:** Round, Class 1, 47.80-57.10 in. specific lengths 36-144 in., diameters 0.875 in. Rectangles and squares, Class 1, 63.70-141.00 in. random lengths, 0.875-4 in. thicknesses 0.750-10 in.

**Pipe:** A.S.A. Schedule 40, alloy 6063-T6, 20 lengths, plain ends, 90,000-lb base, per 100.

Nom. Pipe Size (in.)	Nom. Pipe Size (in.)	
1/2	2	\$4.49
1	4	136
1 1/4	6	244
1 1/2	8	368

## MAGNESIUM

**Sheet:** AZ31, commercial grade, 0.032-72.20; 1 x 4 in., 67.00. Rod, 1 in., 69.00 lb and over, f.o.b. mill.

**Plate:** Hot-rolled AZ31, 59.00, 30,000 lb or more, 0.250 in. and over, widths to 48 in. lengths to 144 in.; raised pattern floor plate 62.00, 30,000 lb or more, 1/4-in. thick, widths 24-72 in., lengths 60-192 in.

**Extrusion Stock:** AZ31, Rectangles, 1/4 x 2 1/2 in., 66.50. Tubing, 1 in. OD x 0.065 in. wall. Angles, 1 x 1 x 1/4-in., 76.90; 2 x 1/4-in., 70.00. Channels, 5 in., 70.90. 1-bead, 5 in., 70.20.

## NONFERROUS SCRAP

### DEALER'S BUYING PRICES

(Cents per pound, New York, in ton lots)  
**Aluminum:** 1100 clippings, 16.50-18.00; sheets, 14.50-16.00; borings and turnings, 10.50; crankcases, 14.50-16.00; industrial castings, 14.50-16.00.

## SCRAP ALLOWANCES

	Sheet, Strip, Plate	Rod	Wire	Seamless	Clean Heavy	Rod Ends	Cold-drawn Turn
Copper .....	54.76b	52.36c	...	54.82	32.000	32.000	31.4
Yellow Brass .....	46.27	37.22d	46.81	49.18	23.875	23.825	22.0
Red Brass, 85% .....	50.99	50.93	51.53	53.80	28.125	27.875	27.7
Low Brass, 80% .....	49.75	49.69	50.29	52.56	27.000	26.750	26.7
Naval Brass .....	49.99	44.30	57.05	53.15	22.125	21.875	21.1
Com. Bronze, 90% .....	52.78	52.72	53.32	55.84	29.250	29.000	28.3
Nickel Silver, 10% .....	60.20	62.53g	62.53	...	27.625	27.375	13.7
Phos. Bronze, A, 5% .....	73.03	73.53	73.53	74.71	32.250	32.000	31.0
Silicon Bronze .....	58.82	58.01	58.86	60.80e	31.125	30.875	30.1
Manganese Bronze .....	53.73	47.83	58.24	...	22.125	21.875	21.1
Muntz Metal .....	48.14	43.95	...	...	22.125	22.125	21.1

a. Cents per lb, f.o.b. mill; freight allowed on 500 lb or more. b. Hot-rolled. c. Cold-drawn. d. Free cutting. e. 3% silicon. f. Prices in cents per lb for less than 20,000 lb, f.o.b. shipping point. On lots over 20,000 lb at one time, of any or all kinds of scrap, add 1 cent per lb. g. Lead.

and Brass: No. 1 heavy copper and 14.50-35.00; No. 2 heavy copper and 33.50-34.00; light copper, 31.50-32.00; composition red brass, 27.50-28.00; No. position turnings, 26.50-27.50; yellow turnings, 16.50-17.00; new brass clip- 22.00-23.00; light brass, 16.50-17.50; yellow brass, 20.00-20.50; new brass rod 1.00-22.00; auto radiators, unsweated, 1.50; cocks and faucets, 22.00-22.50; pipe, 22.00-23.00.

Heavy, 11.50-12.00; battery plates, 6.50- notype and stereotype, 14.00-14.25; elec- 12.00-12.50; mixed babbitt, 14.50.

ium: Clippings, 18.50-19.50; clean cast- 3.00-19.00; iron castings, not over 10% ble Fe, less full deduction for Fe, 16.00-

Clippings, 38.50-42.00; old sheets, 34.00- turnings, 29.50; rods, 38.50-42.00. Sheets and clips, 80.00-90.00; rolled 80.00-90.00; turnings, 65.00-75.00; rod 0.00-90.00.

old zinc, 5.00-5.50; new die-cast scrap, 0; old die-cast scrap, 3.50-3.75.

#### REFINERS' BUYING PRICES

per pound, carlots, delivered refinery)

ium: 1100 clippings, 21.00; 3003 clip- 20.75-21.00; 6151 clippings, 20.50-21.50; clippings, 20.50-21.50; 2014 clippings, 2017 clippings, 20.00; 2024 clippings, mixed clippings, 20.00-20.50; old sheet, 2.50; old cast, 17.50; clean old cable steel, 20.50-21.00; borings and turn- 7.50-18.50.

m Copper: Heavy scrap, 0.020-in. and not less than 1.5% Be, 48.00; light 49.00.

and Brass: No. 1 copper, 38.00; No. 2 36.50; light copper, 34.50-34.75; re- brass (60% copper) per dry copper 33.00.

#### WROUGHTMAKERS' BUYING PRICES

(cents per pound, carlots, delivered)

and Brass: No. 1 copper, 37.50; No. 2 36.00; light copper, 34.00-34.25; No. 1 tion borings, 30.00-30.50; No. 1 com- solids, 30.50-31.00; heavy yellow brass 22.50-23.50; yellow brass turnings, radiators, 23.50-24.50.

#### PLATING MATERIAL

shipping point, freight allowed on es)

#### ANODES

m: Special or patented shapes, \$1.70

Flat-rolled, 51.42, oval, 50.92, 5000- lb; electrodeposited, 45.73, 2000-5000 lb at, 52.54, 5000-10,000 lb quantities.

Depolarized, less than 100 lb, \$1.015; lb, 99.50; 500-4999 lb, 95.50; 5000- lb, 93.50; 30,000 lb, 91.50. Carbonized, 3 cents a lb. All prices eastern delivery Jan. 1, 1955.

Bar or slab, less than 200 lb, \$1.175; lb, \$1.16; 500-999 lb, \$1.155; 1000 lb, \$1.15.

Bar, 21.00; bar or flat top, 20.00, ton

#### CHEMICALS

m Oxide: \$2.15 per lb, in 100-lb drums. Acid: Less than 10,000 lb, 28.50; over lb, 27.50.

Cyanide: 100 lb, 76.80; 200 lb, 76.05; 75.80; 400-900 lb, 75.05; 1000 lb and 3.05; effective Mar. 24, 1955.

Sulphate: Crystal, 100 lb, 21.50; 200 lb, 20.00 lb, 17.50; 400 lb, 17.00; 500-1900 lb, 2000-70,000 lb, 15.25; 10,000 lb and up, Powder, add 0.5 to above prices. Ef- Mar. 29, 1955.

Chloride: 100 lb, 46.50; 200 lb, 44.50; 43.50; 400-4900 lb, 41.50; 5000-9900 lb, 10,000 lb and over, 38.50. All prices delivery, effective Jan. 1, 1955.

Sulphate: 100 lb, 38.25; 200 lb, 36.25; 35.25; 400-4900 lb, 33.25; 5000-35,900 5; 36,000 lb, 30.25. All prices eastern effective Jan. 1, 1955.

Cyanide: (Cents per ounce) 4-oz bottle, 16-oz bottle, 81.875; 80-oz bottle, 100-oz bottle, 79.375; f.o.b. St. Louis, ark and Los Angeles. Effective Apr. 6,


Cyanide: Egg, under 1000 lb, 19.80; 900 lb, 18.80; 20,000 lb and over, granular, add 1-cent premium to above. Stannate: Less than 100 lb, 74.00; 100- 59.60; 700-1900 lb, 57.10; 2000-9900 0; 10,000 lb or more, 54.20.

s Chloride (Anhydrous): Less than 50 06; 50 lb, \$1.266; 100-300 lb, \$1.116; lb, \$1.092; 1000-1900 lb, \$1.068; 2000- \$1.031; 5000-19,900 lb, 97.00; 20,000 ore, 90.90.

s Sulphate: Less than 50 lb, \$1.304; \$1.004; 100-1900 lb, 98.40; 2000 lb or 8.40.

anide: Under 1000 lb, 54.30; 1000 lb 98.70; 100-1900 lb, 96.70; 2000 lb or ar, 52.30.

## FOR FINE WIRE PRODUCTS . . .




## Almet Stainless Steels

### MEET MORE REQUIREMENTS THAN OTHER ENGINEERING MATERIALS

Does your Fine Wire application call for resistance to heat? . . . to corrosion? Does it require good fatigue properties . . . excellent weaving or other forming characteristics? There's a good chance you will find the material you need among the more than 20 grades of stainless steel we fabricate into high quality Fine Wire. No other family of metals has the combination of properties common to the stainless steels.

Learn more about the interesting properties and applications of our stainless steel Fine Wire, as well as our stainless Rod and Strip . . . send today for a copy of our new 40 page Stainless Steel Design Handbook.



## ALLOY METAL WIRE DIVISION



H. K. PORTER COMPANY, INC.  
Prospect Park, Pennsylvania



# Steel Prices

Mill prices as reported to STEEL, cents per pound except as otherwise noted. Changes shown in italics. Code numbers following mill points indicate producing company. Key on page 107. Key to footnotes, page 109.

## SEMI-FINISHED

### INGOTS, Carbon, Forging (NT)

Munhall, Pa. U5 .....\$65.50

### INGOTS, Alloy (NT)

Detroit R7 .....\$69.00  
Houston S5 .....74.00  
Midland, Pa. C1S .....89.00  
Munhall, Pa. U5 .....89.00

### BILLETS, BLOOMS & SLABS

#### Carbon, rerolling (NT)

Alquippa, Pa. J5 .....\$68.50  
Bessemer, Pa. U5 .....65.50  
Bridgeport, Conn. N19 .....69.00  
Buffalo R2 .....68.50  
Clairton, Pa. U5 .....68.50  
Emsley, Ala. T2 .....68.50  
Fairfield, Ala. T2 .....68.50  
Fontana, Calif. K1 .....76.00  
Gary, Ind. U5 .....68.50  
Johnstown, Pa. B2 .....68.50  
Lackawanna, N.Y. B2 .....68.50  
LoneStar, Tex. L6 .....70.00  
Munhall, Pa. U5 .....68.50  
Pittsburgh J5 .....68.50  
So. Chicago, Ill. R2, U5 .....68.50  
So. Duquesne, Pa. U5 .....68.50  
Youngstown R2 .....68.50

#### Carbon, Forging (NT)

Alquippa, Pa. J5 .....\$84.50  
Bessemer, Pa. U5 .....84.50  
Bridgeport, Conn. N19 .....83.00  
Buffalo R2 .....84.50  
Clairton, Pa. U5 .....86.50  
Conshohocken, Pa. A3 .....89.50  
Emsley, Ala. T2 .....84.50  
Fairfield, Ala. T2 .....84.50  
Fontana, Calif. K1 .....92.00  
Gary, Ind. U5 .....84.50  
Geneva, Utah C11 .....84.50  
Houston S5 .....89.50  
Johnstown, Pa. B2 .....84.50  
Lackawanna, N.Y. B2 .....84.50  
Los Angeles B3 .....94.00  
Midland, Pa. C18 .....84.50  
Munhall, Pa. U5 .....84.50  
Pittsburgh J5 .....84.50  
Seattle B3 .....98.00  
So. Chicago R2, U5, W14 84.50  
So. Duquesne, Pa. U5 .....84.50  
So. San Francisco B3 .....94.00

#### Alloy, Forging (NT)

Bethlehem, Pa. B2 .....\$96.00  
Buffalo R2 .....96.00  
Canton, O. R2, T7 .....96.00  
Conshohocken, Pa. A3 .....103.00  
Detroit R7 .....96.00  
Fontana, Calif. K1 .....115.00  
Gary, Ind. U5 .....96.00  
Houston S5 .....101.00  
Ind. Harbor, Ind. Y1 .....96.00  
Johnstown, Pa. B2 .....96.00  
Lackawanna, N.Y. B2 .....96.00  
Los Angeles B3 .....116.00  
Massillon, O. R2 .....96.00  
Midland, Pa. C1S .....96.00  
Munhall, Pa. U5 .....96.00  
So. Chicago R2, U5, W14 96.00  
So. Duquesne, Pa. U5 .....96.00  
Struthers, O. Y1 .....96.00  
Warren, O. C17 .....96.00

### ROUNDS, SEAMLESS TUBE (NT)

Buffalo R2 .....\$103.50  
Canton, O. R2 .....103.50  
Cleveland R2 .....103.50  
Gary, Ind. U5 .....103.50  
So. Chicago R2, W14 .....103.50  
So. Duquesne, Pa. U5 .....103.50

### SKELP

Alquippa, Pa. J5 .....4.325  
LoneStar, Tex. L6 .....4.30  
Munhall, Pa. U5 .....4.225  
SparrowsPoint, Md. B2 .....4.225  
Warren, O. R2 .....4.225  
Youngstown R2, U5 .....4.225

### WIRE RODS

Alabama City, Ala. R2 .....5.025  
Alquippa, Pa. J5 .....5.025  
Alton, Ill. L1 .....5.20  
Buffalo B1, W12 .....5.025  
Cleveland A7 .....5.025  
Donora, Pa. A7 .....5.025  
Fairfield, Ala. T2 .....5.025  
Houston S5 .....5.275  
Indiana Harbor, Ind. Y1 .....5.025  
Johnstown, Pa. B2 .....5.025  
Joliet, Ill. A7 .....5.025  
Kansas City, Mo. S5 .....5.275  
Kokomo, Ind. C16 .....5.125

Los Angeles B3 .....5.825  
Minneapolis, Colo. C10 .....5.275  
Monessen, Pa. P7 .....4.675  
Mo. Tonawanda, N.Y. B11 .....4.675  
Pittsburgh, Calif. C11 .....5.675  
Pittsburgh P12 .....5.025  
Riding, N.J. R5 .....5.125  
So. Chicago, Ill. R2 .....5.025  
SparrowsPoint, Md. B2 .....5.125  
Sterling, Ill. (1) N15 .....5.025  
Sterling, Ill. N15 .....5.125  
Struthers, O. Y1 .....5.025  
Worcester, Mass. A7 .....5.325

## STRUCTURALS

### Carbon Steel Std. Shapes

Ala. City, Ala. R2 .....4.60  
Alquippa, Pa. J5 .....4.60  
Bessemer, Ala. T2 .....4.60  
Bethlehem, Pa. B2 .....4.65  
Birmingham C15 .....4.60  
Clairton, Pa. U5 .....4.60  
Fairfield, Ala. T2 .....4.60  
Fontana, Calif. K1 .....5.25  
Gary, Ind. U5 .....4.60  
Geneva, Utah C11 .....4.60  
Houston S5 .....4.60  
Ind. Harbor, Ind. I-2 .....4.60  
Johnstown, Pa. B2 .....4.65  
Kansas City, Mo. S5 .....4.70  
Lackawanna, N.Y. B2 .....4.65  
Los Angeles B3 .....5.30  
Minneapolis, Colo. C10 .....4.60  
Munhall, Pa. U5 .....4.60  
Niles, Calif. P1 .....4.90  
Portland, Ore. O4 .....5.35  
Phoenixville, Pa. P4 .....4.65  
Seattle B3 .....5.35  
So. Chicago U5, W14 .....4.60  
So. San Francisco B3 .....5.25  
Torrance, Calif. C11 .....5.30  
Weirton, W. Va. W6 .....4.60

### Wide Flange

Bethlehem, Pa. B2 .....4.65  
Clairton, Pa. U5 .....4.60  
Fontana, Calif. K1 .....5.40  
Lackawanna, N.Y. B2 .....4.65  
Munhall, Pa. U5 .....4.60  
Phoenixville, Pa. P4 .....4.65  
So. Chicago, Ill. U5 .....4.60

### Alloy Std. Shapes

Clairton, Pa. U5 .....5.65  
Fontana, Calif. K1 .....7.30  
Gary, Ind. U5 .....5.65  
Houston S5 .....5.75  
Munhall, Pa. U5 .....5.65  
So. Chicago, Ill. U5 .....5.65

### H.S., L.A. Std. Shapes

Alquippa, Pa. J5 .....6.75  
Bessemer, Ala. T2 .....6.75  
Bethlehem, Pa. B2 .....6.80  
Clairton, Pa. U5 .....6.75  
Fairfield, Ala. T2 .....6.75  
Fontana, Calif. K1 .....7.40  
Gary, Ind. U5 .....6.75  
Geneva, Utah C11 .....6.675  
Houston S5 .....6.85  
Ind. Harbor, Ind. I-2, Y1 6.75  
Johnstown, Pa. B2 .....6.80  
Kansas City, Mo. S5 .....6.85  
Lackawanna, N.Y. B2 .....6.80  
Los Angeles B3 .....7.45  
Munhall, Pa. U5 .....6.75  
Seattle B3 .....7.50  
So. Chicago, Ill. U5, W14 6.75  
So. San Francisco B3 .....7.40  
Struthers, O. Y1 .....6.75

### H.S., L.A. Wide Flange

Bethlehem, Pa. B2 .....6.80  
Lackawanna, N.Y. B2 .....6.80  
Munhall, Pa. U5 .....6.75  
So. Chicago, Ill. U5 .....6.75

## PILING

### BEARING PILES

Bethlehem, Pa. B2 .....4.65  
Lackawanna, N.Y. B2 .....4.65  
Munhall, Pa. U5 .....4.60  
So. Chicago, Ill. U5 .....4.60

### STEEL SHEET PILING

Ind. Harbor, Ind. I-2 .....5.45  
Lackawanna, N.Y. B2 .....5.45  
Munhall, Pa. U5 .....5.45  
So. Chicago, Ill. U5 .....5.45

## PLATES

### PLATES, Carbon Steel

Ala. City, Ala. R2 .....4.50

Alquippa, Pa. J5 .....4.50  
Ashland, Ky. (15) A10 .....4.50  
Bessemer, Ala. T2 .....4.50  
Bridgeport, Conn. N19 .....4.75  
Buffalo R2 .....4.50  
Clairton, Pa. U5 .....4.50  
Claymont, Del. C22 .....4.50  
Cleveland J5, R2 .....4.60  
Coatesville, Pa. L7 .....4.50  
Conshohocken, Pa. A3 .....4.50  
Detroit M1 .....4.60  
Ecorse, Mich. G5 .....4.60  
Fairfield, Ala. T2 .....4.50  
Fontana, Calif. (30) K1 .....5.15  
Gary, Ind. U5 .....4.50  
Geneva, Utah C11 .....4.50  
Granite City, Ill. G4 .....4.70  
Harrisburg, Pa. C5 .....4.50  
Houston S5 .....4.50  
Ind. Harbor, Ind. I-2, Y1 4.50  
Johnstown, Pa. B2 .....4.50  
Lackawanna, N.Y. B2 .....4.50  
LoneStar, Tex. L6 .....4.55  
Mansfield, O. B6 .....4.50  
Minneapolis, Colo. C10 .....5.35  
Munhall, Pa. U5 .....4.50  
Newport, Ky. N9 .....4.50  
Pittsburgh J5 .....4.50  
Riverdale, Ill. A1 .....4.50  
Seattle B3 .....4.50  
Sharon, Pa. S3 .....4.50  
So. Chicago R2, U5, W14 4.50  
SparrowsPoint, Md. B2 .....4.50  
Stevensville, Pa. W10 .....4.50  
Warren, O. R2 .....4.50  
Weirton, W. Va. W6 .....4.50  
Youngstown R2, U5, Y1 4.50

### PLATES, Carbon Abras. Resist.

Fontana, Calif. K1 .....6.30  
Geneva, Utah C11 .....5.65  
Johnstown, Pa. B2 .....5.65  
SparrowsPoint, Md. B2 .....5.65

### PLATES, Wrought Iron

Economy, Pa. B14 .....10.40

### PLATES, High-Strength Low-Alloy

Alquippa, Pa. J5 .....6.725  
Bessemer, Ala. T2 .....6.725  
Clairton, Pa. U5 .....6.725  
Cleveland J5, R2 .....6.725  
Coatesville, Pa. L7 .....6.725  
Conshohocken, Pa. A3 .....6.725  
Ecorse, Mich. G5 .....6.825  
Fairfield, Ala. T2 .....6.725  
Fontana, Calif. (30) K1 .....7.375  
Gary, Ind. U5 .....6.725  
Geneva, Utah C11 .....6.725  
Houston S5 .....6.825  
Ind. Harbor, Ind. I-2, Y1 6.725  
Johnstown, Pa. B2 .....6.725  
Los Angeles B3 .....6.725  
Munhall, Pa. U5 .....6.725  
Pittsburgh J5 .....6.725  
Seattle B3 .....6.725  
Sharon, Pa. S3 .....6.725  
So. Chicago, Ill. U5, W14 6.725  
SparrowsPoint, Md. B2 .....6.725  
Youngstown U5, Y1 .....6.725

### PLATES, Alloy

Bridgeport, Conn. N19 .....6.55  
Claymont, Del. C22 .....6.30  
Coatesville, Pa. L7 .....6.30  
Fontana, Calif. K1 .....6.95  
Gary, Ind. U5 .....6.30  
Houston S5 .....6.40  
Ind. Harbor, Ind. Y1 .....6.30  
Johnstown, Pa. B2 .....6.30  
Munhall, Pa. U5 .....6.30  
Newport, Ky. N9 .....6.30  
Seattle B3 .....7.20  
Sharon, Pa. S3 .....6.30  
So. Chicago, Ill. U5, W14 6.30  
SparrowsPoint, Md. B2 .....6.30  
Youngstown Y1 .....6.30

### FLOOR PLATES

Cleveland J5 .....5.575  
Conshohocken, Pa. A3 .....5.575  
Harrisburg, Pa. C5 .....5.575  
Ind. Harbor, Ind. I-2 .....5.575  
Munhall, Pa. U5 .....5.575  
So. Chicago, Ill. U5 .....5.575

### PLATES, Ingot Iron

Ashland c.l. (15) A10 .....4.75  
Ashland i.c.l. (15) A10 .....5.25  
Cleveland c.l. R2 .....5.10  
Warren, O. c.l. R2 .....5.10

## BAR

### BAR, Hot-Rolled Carbon

Ala. City, Ala. R2 .....4.65  
Alquippa, Pa. J5 .....4.65

Alton, Ill. L1 .....4.85  
Atlanta A11 .....4.85  
Bessemer, Ala. T2 .....4.65  
Birmingham C15 .....4.65  
Bridgeport, Conn. N19 .....4.80  
Canton, O. R2 .....4.65  
Clairton, Pa. U5 .....4.65  
Cleveland R2 .....4.65  
Ecorse, Mich. G5 .....4.75  
Emeryville, Calif. J7 .....5.40  
Fairfield, Ala. T2 .....4.65  
Fairless Hills, Pa. U5 .....4.80  
Fontana, Calif. K1 .....5.35  
Gary, Ind. U5 .....4.65  
Houston S5 .....4.90  
Ind. Harbor, Ind. I-2, Y1 4.65  
Joliet, Ill. P22 .....4.65  
Kansas City, Mo. S5 .....4.90  
Lackawanna, N.Y. B2 .....4.65  
Los Angeles B3 .....5.35  
Massillon, O. R2 .....4.75  
Midland, Pa. C18 .....4.65  
Milton, Pa. M18 .....4.65  
Minneapolis, Colo. C10 .....5.10  
Niles, Calif. P1 .....5.00  
N. Tonawanda, N.Y. B11 .....4.50  
Pittsburgh, Calif. C11 .....5.35  
Pittsburgh J5 .....4.65  
Portland, Ore. O4 .....5.40  
Seattle B3 .....5.40  
So. Chicago R2, U5, W14 4.65  
So. Duquesne, Pa. U5 .....4.65  
So. San Fran., Calif. B3 .....5.40  
Sterling, Ill. (1) N15 .....4.65  
Sterling, Ill. N15 .....4.75  
Struthers, O. Y1 .....5.35  
Torrance, Calif. C11 .....5.65  
Warren, O. R2 .....4.65  
Weirton, W. Va. W6 .....4.65  
Youngstown R2, U5 .....4.65

### BAR, H.R. Loaded

Warren, O. C17 .....6.325

### BAR, Hot-Rolled Alloy

Bethlehem, Pa. B2 .....5.575  
Bridgeport, Conn. N19 .....5.725  
Buffalo R2 .....5.675  
Canton, O. R2, T7 .....5.575  
Clairton, Pa. U5 .....5.575  
Detroit R7 .....5.575  
Ecorse, Mich. G5 .....6.875  
Fontana, Calif. K1 .....6.825  
Fairless Hills, Pa. U5 .....5.725  
Gary, Ind. U5 .....5.575  
Houston S5 .....5.825  
Ind. Harbor, Ind. I-2, Y1 5.575  
Johnstown, Pa. B2 .....5.575  
Kansas City, Mo. S5 .....5.825  
Lackawanna, N.Y. B2 .....5.575  
Los Angeles B3 .....6.825  
Massillon, O. R2 .....5.575  
Midland, Pa. C18 .....5.575  
So. Chicago R2, U5, W14 5.575  
So. Duquesne, Pa. U5 .....5.575  
Struthers, O. Y1 .....5.575  
Warren, O. C17 .....5.575  
Youngstown U5 .....5.575

### BAR & SMALL SHAPES, H.R.

#### High-Strength Low-Alloy

Alquippa, Pa. J5 .....6.80  
Bessemer, Ala. T2 .....6.80  
Bethlehem, Pa. B2 .....6.80  
Clairton, Pa. U5 .....6.80  
Cleveland R2 .....6.80  
Ecorse, Mich. G5 .....6.90  
Fontana, Calif. K1 .....7.50  
Gary, Ind. U5 .....6.80  
Houston S5 .....7.05  
Ind. Harb. Ind. I-2, Y1 6.80  
Johnstown, Pa. B2 .....6.80  
Kansas City, Mo. S5 .....7.05  
Lackawanna, N.Y. B2 .....6.80  
Los Angeles B3 .....7.50  
Pittsburgh J5 .....6.80  
Seattle B3 .....7.55  
So. Chicago W14 .....6.80  
So. Duquesne, Pa. U5 .....6.80  
So. San Francisco B3 .....7.55  
Struthers, O. Y1 .....6.80  
Warren, O. R2 .....6.80  
Youngstown U5 .....6.80

### BAR SIZE ANGLES; H.R. Carbon

Bethlehem, Pa. B2 .....4.80

### BAR SIZE ANGLES; S. Shapes

Alquippa, Pa. J5 .....4.65  
Atlanta A11 .....4.85  
Fontana, Calif. K1 .....5.35  
Niles, Calif. P1 .....5.00  
Pittsburgh J5 .....4.30  
Portland, Ore. O4 .....5.05  
San Francisco S7 .....5.05

### BAR SHAPES, Hot-Rolled Alloy

Clairton, Pa. U5 .....5.65  
Gary, Ind. U5 .....5.65  
Houston S5 .....5.90  
Kansas City, Mo. S5 .....5.90  
Youngstown U5 .....5.90

### BAR, C.F. Loaded

Bridgeport, Pa. W18 .....7.525  
Camden, N.J. P13 .....7.525  
Chicago W18 .....7.525  
Cleveland C20 .....7.525  
Monaca, Pa. S17 .....8.325  
Newark, N.J. W18 .....7.70  
Spring City, Pa. K3 .....8.325  
Warren, O. C17 .....8.325

### BAR, Cold-Finished Carbon

Bridgeport, Pa. W18 .....5.90  
Beaver Falls, Pa. M12 R2 5.90  
Buffalo B5 .....5.95  
Camden, N.J. P13 .....6.35  
Carnegie, Pa. C12 .....5.90  
Chicago W18 .....5.90  
Cleveland A7, C20 .....5.90  
Detroit R7 .....5.90  
Donora, Pa. P17 .....6.10  
Donora, Pa. A7 .....5.90  
Elyria, O. W8 .....5.90  
Pittsburgh W8, Ill. N5 .....5.90  
Gary, Ind. R2 .....5.90  
Green Bay, Wis. F7 .....5.90  
Hammond, Ind. L2 M13 5.90  
Hartford, Conn. R2 .....6.40  
Harvey, Ill. B5 .....5.90  
Los Angeles R2 S30 .....7.35  
Mansfield, Mass. B5 .....6.45  
Massillon, O. R2, R8 .....5.90  
Midland, Pa. C18 .....5.90  
Monaca, Pa. S17 .....5.90  
Newark, N.J. W18 .....6.35  
New Castle, Pa. (17) B4 .....5.90  
Pittsburgh J5 .....5.90  
Plymouth, Mich. P5 .....6.15  
Putnam, Conn. W18 .....8.45  
Reading, Mass. C14 .....6.45  
So. Chicago, Ill. W14 .....5.90  
Spring City, Pa. K3 .....6.35  
Struthers, O. Y1 .....5.90  
Waukegan, Ill. A7 .....5.90  
Worcester, Mass. W19 .....6.35  
Youngstown F3, Y1 .....5.90

### BAR, Cold-Finished Carbon (Turned and Ground)

Cumberland, Md. C19 .....5.15

### BAR, Cold-Finished Alloy

Bridgeport, Pa. W18 .....7.425  
Beaver Falls, Pa. M12 R2 7.425  
Bethlehem, Pa. B2 .....7.425  
Buffalo B5 .....7.425  
Camden, N.J. P13 .....7.60  
Canton, O. T7 .....7.425  
Carnegie, Pa. C12 .....7.425  
Chicago W18 .....7.425  
Cleveland A7, C20 .....7.425  
Detroit R7 .....7.425  
Detroit B5, P17 .....7.625  
Donora, Pa. A7 .....7.425  
Elyria, O. W8 .....7.425  
Gary, Ind. R2 .....7.425  
Green Bay, Wis. F7 .....7.425  
Hammond, Ind. L2 M13 7.425  
Hartford, Conn. R2 .....7.725  
Harvey, Ill. B5 .....7.425  
Lackawanna, N.Y. B2 .....7.425  
Los Angeles S30 .....9.10  
Mansfield, Mass. B5 .....7.725  
Massillon, O. R2, R8 .....7.425  
Midland, Pa. C18 .....7.425  
Monaca, Pa. S17 .....7.425  
Newark, N.J. W18 .....7.60  
Plymouth, Mich. P5 .....7.625  
So. Chicago W14 .....7.425  
Spring City, Pa. K3 .....7.60  
Struthers, O. Y1 .....7.425  
Warren, O. C17 .....7.425  
Waukegan, Ill. A7 .....7.425  
Worcester, Mass. A7 .....7.725  
Youngstown F3, Y1 .....7.425

### BAR, Reinforcing (To Fabricators)

Ala. City, Ala. R2 .....4.65  
Atlanta A11 .....4.85  
Birmingham C15 .....4.65  
Buffalo R2 .....4.65  
Cleveland R2 .....4.65  
Ecorse, Mich. G5 .....4.75  
Emeryville, Calif. J7 .....5.40  
Fairfield, Ala. T2 .....4.65  
Fairless Hills, Pa. U5 .....4.80  
Fontana, Calif. K1 .....5.35  
Ft. Worth, Tex. (42) T4 .....5.10  
Gary, Ind. U5 .....4.65  
Houston S5 .....4.90



nd Harbor, Ind. I-2, Y1	4.65
ohnstown, Pa. B2	4.45
ollet, Ill. P22	4.45
ansas City, Mo. S5	4.60
Lackawanna, N.Y. B2	4.45
Los Angeles B3	5.35
Milton, Pa. M18	4.65
Minneapolis, Colo. C10	5.10
Niles, Calif. P1	5.00
Pittsburgh, Calif. C11	5.35
Pittsburgh J5	4.65
Portland, Oreg. O4	5.40
Sand Springs, Okla. S5	5.15
Seattle B3, N14	5.40
So. Chicago R2	4.65
So. Duquesne, Pa. U5	4.65
So. San Francisco B3	5.40
Sparrows Point, Md. B2	4.65
Sterling, Ill. (1) N15	4.45
Sterling, Ill. N15	4.75
Struthers, O. Y1	4.65
Torrance, Calif. C11	5.35
Youngstown R2, U5	Y1 4.65

#### BAR, Reinforcing (Fabricated; to Consumers)

Johnstown, Pa. 1/4-1" B2	6.15
Kansas City, Kans. S5	6.45
Lackawanna, N.Y. B2	6.17
Marion, O. P11	5.55
Pittsburgh U8	6.17
Seattle B3, N14	6.10
Sparrows Pt. 1/4-1" B2	6.65
Williamsport, Pa. S19	6.00

#### RAIL STEEL BARS

Arvs. Pa. (3) J8	4.25
Chicago Hts. (3) C2, I-2	4.55
Chicago Hts. (4) C2, I-2	4.65
Ft. Worth, Tex. (26) T4	4.95
Franklin, Pa. (3) F5	4.55
Franklin, Pa. (4) F5	4.65
Marion, O. (3) P11	4.20
Moline, Ill. (3) R2	4.65
Tonawanda (3) B12	4.65
Tonawanda (4) B12	4.65
Williamsport, Pa. (3) S19	4.65

#### BAR, Wrought Iron

Economy, Pa. (S.R.) B14	11.50
Economy, Pa. (D.R.) B14	14.30
Economy (Staybolt) B14	14.65
McK Rks. (S.R.) L5	11.50
McK Rks. (D.R.) L5	16.00
McK Rks. (Staybolt) L5	17.00

## SHEETS

### SHEETS, Hot-Rolled Steel (18 Gage and Heavier)

Ala. City, Ala. R2	4.325
Allenport, Pa. P7	4.325
Ashland, Ky. (8) A10	4.325
Cleveland J5, R2	4.325
Conshohocken, Pa. A3	4.325
Detroit (8) M1	4.425
Dravosburg, Pa. U5	4.425
Ecorse, Mich. G5	4.425
Fairfield, Ala. T2	4.325
Fairless Hills, Pa. U5	4.375
Fontana, Calif. K1	5.075
Gary, Ind. U5	4.325
Geneva, Utah C11	4.425
Granite City, Ill. G4	4.525
Ind. Harbor, Ind. I-2, Y1	4.325
Kokomo, Ind. C16	4.425
Lackawanna, N.Y. B2	4.325
Mansfield, O. E6 (37)	4.325
Minhall, Pa. U5	4.325
Newport, Ky. (8) N9	4.325
Niles, O. N12	4.325
Pittsburgh, Calif. C11	5.025
Pittsburgh J5	4.325
Portsmouth, O. P12	4.325
Riverdale, Ill. A1	4.325
Sharon, Pa. S3	4.325
So. Chicago, Ill. W14	4.325
Sparrows Point, Md. B2	4.325
Steubenville, O. W10	4.325
Warren, O. R2	4.325
Weirton, W. Va. W6	4.325
Youngstown U5, Y1	4.325

### SHEETS, H.R. (19 Ga. & Lighter)

Ala. City, Ala. R2	5.625
Kokomo, Ind. C16	5.475
Niles, O. N12	5.325

### SHEETS, H.R. Alloy

Ind. Harbor, Ind. Y1	7.20
Youngstown Y1	7.20

### SHEETS, H.R. (14 Ga. & Heavier) High-Strength Low-Alloy

Cleveland J5, R2	8.375
Conshohocken, Pa. A3	8.425
Dravosburg, Pa. U5	8.375
Ecorse, Mich. G5	8.475
Fairfield, Ala. T2	8.375
Fairless Hills, Pa. U5	8.425
Fontana, Calif. K1	7.125

Gary, Ind. U5	6.375
Ind. Harbor, Ind. I-2, Y1	6.375
Lackawanna (35) B2	6.375
Munhall, Pa. U5	6.375
Pittsburgh J5	6.375
Sharon, Pa. S3	6.375
So. Chicago, Ill. U5	6.375
Sparrows Point (36) B2	6.375
Warren, O. R2	6.375
Weirton, W. Va. W6	6.375
Youngstown U5, Y1	6.375

### SHEETS, Hot-Rolled Ingot Iron (18 Gage and Heavier)

Ashland, Ky. (8) A10	4.575
Cleveland R2	4.925
Ind. Harbor, Ind. I-2	4.575
Warren, O. R2	4.925

### SHEETS, Cold-Rolled Steel (Commercial Quality)

Allenport, Pa. P7	5.325
Cleveland J5, R2	5.325
Conshohocken, Pa. A3	5.375
Dravosburg, Pa. U5	5.325
Detroit M1	5.325
Ecorse, Mich. G5	5.425
Fairfield, Ala. T2	5.325
Fairless Hills, Pa. U5	5.375
Follansbee, W. Va. B20	5.325
Fontana, Calif. K1	6.425
Gary, Ind. U5	5.325
Granite City, Ill. G4	5.525
Ind. Harbor, Ind. I-2, Y1	5.325
Lackawanna, N.Y. B2	5.325
Mansfield, O. E6	5.325
Middletown, O. A10	5.325
Newport, Ky. N9	5.325
Pittsburgh, Calif. C11	6.275
Pittsburgh J5	5.325
Portsmouth, O. P12	5.325
Sparrows Point, Md. B2	5.325
Steubenville, O. W10	5.325
Warren, O. R2	5.325
Weirton, W. Va. W6	5.325
Youngstown Y1	5.325

### SHEETS, Cold-Rolled High-Strength Low-Alloy

Cleveland J5, R2	7.875
Dravosburg, Pa. U5	7.875
Ecorse, Mich. G5	7.975
Fairless Hills, Pa. U5	7.925
Fontana, Calif. K1	8.975
Gary, Ind. U5	7.875
Indiana Harbor, Ind. Y1	7.875
Lackawanna (37) B2	7.875
Pittsburgh J5	7.875

Sparrows Point (38) B2	7.875
Warren, O. R2	7.875
Weirton, W. Va. W6	7.875
Youngstown Y1	7.875

### SHEETS, Cold-Rolled Ingot Iron Middletown, O. A10

5.825
-------

### SHEETS, Culvert (16 Gage)

Ashland, Ky. A10	6.90
Canton, O. R2	6.50
Dravosburg, Pa. U5	6.10
Fairfield T2	6.10
Gary, Ind. U5	6.10
Ind. Harbor I-2	6.10
Kokomo, Ind. C16	6.20
Martins Ferry, W. Va. W10	6.10
Newport, Ky. N9	6.10
Pitts., Calif. C11	6.85
Sparrows Pt. B2	6.10

### SHEETS, Culvert—Pure Iron

Ashland, Ky. A10	7.15
Gary, Ind. U5	5.95
Martins Ferry, O. W10	6.85

### SHEETS, Galvanized Steel

#### Hot-Dipped

Ala. City, Ala. R2	5.851
Ashland, Ky. A10	5.851
Canton, O. R2	5.851
Delfos, O. N16	6.801
Dover, O. R1	5.851
Dravosburg, Pa. U5	5.851
Fairfield, Ala. T2	5.851
Gary, Ind. U5	5.851
Granite City, Ill. G4	6.05
Ind. Harbor, Ind. I-2	5.851
Kokomo, Ind. C16	5.851
Martins Ferry, O. W10	5.851
Middletown, O. A10	5.851
Newport, Ky. N9	5.851
Niles, O. N12	6.851
Pittsburgh, Calif. C11	6.801
Sparrows Pt., Md. B2	5.851
Steubenville, O. W10	5.851
Warren, O. R2	5.851
Weirton, W. Va. W6	5.851

\*Continuous and noncontinuous.  
†Continuous, ‡Noncontinuous.

### SHEETS, Well Casing

Fontana, Calif. K1	6.575
--------------------	-------

### SHEETS, Galvanized

#### High-Strength Low-Alloy

Dravosburg, Pa. U5	8.60
Sparrows Point (39) B2	8.60

### SHEETS, Galvanized Steel

Canton, O. R2	6.25
Dravosburg, Pa. U5	6.25
Kokomo, Ind. C16	6.60
Newport, Ky. N9	6.25
Niles, O. N12	7.25

### SHEETS, Galvanized Ingot Iron

#### (Hot-Dipped Continuous)

Ashland, Ky. A10	6.10
Middletown, O. A10	6.10

### SHEETS, Electrogalvanized

Cleveland (28) R2	6.80
Niles, O. (28) R2	6.80
Weirton, W. Va. W6	6.55

### SHEETS, Aluminum Coated

Butler, Pa. A10 (type 1)	8.50
Butler, Pa. A10 (type 2)	8.60

### SHEETS, Enameling Iron

Ashland, Ky. A10	5.90
Cleveland, Pa.	5.90
Dravosburg, Pa. U5	5.90
Gary, Ind. U5	5.90
Granite City, Ill. G4	6.10
Ind. Harbor, Ind. I-2	5.90
Middletown, O. A10	5.90
Niles, O. N12	5.90
Youngstown Y1	5.90

### BLUED STOCK, 29 Gage

Follansbee, W. Va. B20	7.75
Yorkville, O. W10	7.75

### SHEETS, Long Term Steel

#### (Commercial Quality)

Beech Bottom, W. Va. W10	6.25
Gary, Ind. U5	6.25
Mansfield, O. E6	6.25
Middletown, O. A10	6.25
Niles, O. N12	6.25
Weirton, W. Va. W6	6.25

### SHEETS, Long Term, Ingot Iron

Middletown, O. A10	6.65
--------------------	------

## Key to Producers

A1 Acme Steel Co.	C19 Cumberland Steel Co.	I-6 Ivins, E., Steel Tube	N16 New Delphos Mfg. Co.	S13 Superior Steel Corp.
A3 Alan Wood Steel Co.	C20 Cuyahoga Steel & Wire	I-7 Indiana Steel & Wire Co.	N19 Northeastern Steel Corp.	S19 Sweet's Steel Co.
A4 Allegheny Ladium Steel	C22 Claymont Steel Products			S20 Southern States Steel
A5 Alloy Metal Wire Co.	Dept. Twickwire Spencer Steel Division	J1 Jackson Iron & Steel Co.	O3 Oliver Iron & Steel Corp.	S23 Superior Tube Co.
A6 American Shim Steel Co.		J3 Jessop Steel Co.	O4 Oregon Steel Mills	S25 Stainless Welded Products
A7 American Steel & Wire	C23 Charter Wire Inc.	J4 Johnson Steel & Wire Co.	P1 Pacific States Steel Corp.	S26 Specialty Wire Co. Inc.
A8 Anchor Drawn Steel Co.	C24 G. O. Carlson Inc.	J5 Jones & Laughlin Steel	P2 Pacific Tube Co.	S30 Sierra Drawn Steel Corp.
A9 Angell Nail & Chaplet	C31 Chester Blast Furnace Inc.	J6 Joslyn Mfg. & Supply	P3 Phoenix Iron & Steel Co.	
A10 Armco Steel Corp.		J7 Judson Steel Corp.	P4 Pilgrim Drawn Steel	T2 Tenn. Coal & Iron Div.
A11 Atlantic Steel Co.		J8 Jersey Shore Steel Co.	P5 Pittsburgh Coke & Chem.	T3 Tenn. Prod. & Chem.
B1 Babcock & Wilcox Co.	D2 Detroit Steel Corp.	K1 Kaiser Steel Corp.	P6 Pittsburgh Steel Co.	T4 Texas Steel Co.
B2 Bethlehem Steel Co.	D3 Detroit Tube & Steel	K2 Keokuk Electro-Metals	P7 Pollak Steel Co.	T5 Thomas Strip Division,
B3 Beth. Pac. Coast Steel	D4 Disston & Sons, Henry	K3 Keystone Drawn Steel	P12 Portsmouth Division	Pittsburgh Steel Co.
B4 Blair Strip Steel Co.	D6 Driver-Harris Co.	K4 Keystone Steel & Wire	P13 Precision Drawn Steel	T6 Thompson Wire Co.
B5 Bliss & Laughlin Inc.	D7 Dickson Weatherproof Nail Co.	K7 Kenmore Metals Corp.	P14 Pitts. Screw & Bolt Co.	T7 Timken Roller Bearing
B8 Brauburn Alloy Steel	D8 Damascus Tube Co.	L1 Laclede Steel Co.	P15 Pittsburgh Metallurgical	T9 Tonawanda Iron Div.
B9 Brainard Steel Div., Sharon Steel Corp.	D9 Wilbur B. Driver Co.	L2 LaSalle Steel Co.	P16 Page Steel & Wire Div., Amer. Chain & Cable	Am. Rad. & Stan. San.
B10 E. & G. Brooke, Wickwire Spencer Steel Div.	E1 Eastern Gas & Fuel Assoc.	L3 Lathrop Steel Co.	P17 Plymouth Steel Co.	T13 Tube Methods Inc.
B11 Buffalo Bolt Co., Div., Buffalo-Eclipse Corp.	E2 Eastern Stainless Steel	L5 Lockhart Iron & Steel	P19 Pitts. Rolling Mills	U4 Universal-Cyclops Steel
B12 Buffalo Steel Corp.	E4 Electro Metallurgical Co.	L6 Lone Star Steel Co.	P20 Prod. Steel Strip Corp.	U5 United States Steel Corp.
B14 A. M. Byers Co.	E5 Elliott Bros. Steel Co.	L7 Lukens Steel Co.	P22 Phoenix Mfg. Corp.	U6 U. S. Pipe & Foundry
B15 J. Bishop & Co.	E6 Empire Steel Corp.	M1 McLouth Steel Corp.	R1 Reeves Steel & Mfg. Co.	U7 Ubrich Stainless Steels
B20 Berkman Co., Louis	F2 Firth Sterling Inc.	M4 Mahoning Valley Steel	R2 Republic Steel Corp.	U8 U. S. Steel Supply Div.
C1 Calstrip Steel Corp.	F3 Fitzsimons Steel Co.	M6 Mercer Pipe Div., Sawhill Tubular Products	R3 Rhode Island Steel Corp.	V2 Vanadium-Alloys Steel
C2 Calumet Steel Div., Borg-Warner Corp.	F5 Franklin Steel Div., Borg-Warner Corp.	M8 Mid-States Steel & Wire	R4 Roebeling's Sons, John A.	V3 Vulcan Crucible Steel Co.
C3 Carpenter Steel Co.	F6 Fretz-Moon Tube Co.	M12 Moltrup Steel Products	R6 Rome Strip Steel Co.	W1 Wallace Barnes Co.
C4 Central Iron & Steel Div.	F7 Ft. Howard Steel & Wire	M13 Monarch Steel Div., Jones & Laughlin Steel Corp.	R7 Rotary Electric Steel Co.	W2 Wallingford Steel Co.
C5 Barium Steel Corp.	F8 Ft. Wayne Metals Inc.	M14 McInnes Steel Co.	R8 Reliance Div., Eaton Mfg.	W3 Washburn Wire Co.
C7 Cleve. Cold Rolling Mills	G2 Globe Iron Co.	M16 Md. Fine & Special. Wire	R9 Rome Mfg. Co.	W4 Washington Steel Corp.
C8 Cold Metal Products Co.	G4 Granite City Steel Co.	M18 Milton Steel Prod. Div., Merritt-Chapman & Scott	S1 Seneca Wire & Mfg. Co.	W6 Weirton Steel Co.
C9 Colonial Steel	G5 Great Lakes Steel Corp.	N1 National-Standard Co.	S3 Sharon Steel Corp.	W7 W. Va. Steel & Mfg. Co.
C10 Colorado Fuel & Iron	G6 Greer Steel Co.	N2 National Supply Co.	S4 Sheffield Steel Div., Armo Steel Corp.	W8 West. Auto. Mach. Screw
C11 Columbia-Geneva Steel	H1 Hanna Furnace Corp.	N3 National Tube Div.	S6 Shenango Furnace Co.	W9 Wheeling Steel Corp.
C12 Columbia Steel & Shaft.	H7 Helical Tube Co.	N5 Nelsen Steel & Wire Co.	S7 Simmons Co.	W10 Wheeling Steel Corp.
C13 Columbia Tool Steel Co.	I-1 Igoe Bros. Inc.	N6 New Eng. High Carb. Wire	S8 Simonds Saw & Steel Co.	W12 Wickwire Spencer Steel
C14 Compressed Steel Shaft.	I-2 Inland Steel Co.	N9 Newport Steel Corp.	S12 Spencer Wire Corp.	Div., Colo. Fuel & Iron
C15 Connors Steel Div., H. K. Porter Co. Inc.	I-3 Interlake Iron Corp.	N12 Niles Rolling Mill Div.	S13 Standard Forgings Corp.	W13 Wilson Steel & Wire Co.
C16 Continental Steel Corp.	I-4 Ingersoll Steel Div., Borg-Warner Corp.	N14 Northwest Steel Roll. Mills	S14 Standard Tube Co.	W14 Wisconsin Steel Div., International Harvester
C17 Copperweld Steel Co.		N15 Northwestern S.&W. Co.	S15 Stanley Works	W15 Woodward Iron Co.
C18 Crucible Steel Co.			S17 Superior Drawn Steel Co.	W18 Wyckoff Steel Co.
				W19 Worcester Pressed Steel
				Y1 Youngstown Sheet & Tube







## WIRE

(Continued)

### WIRE, Tire Bead

Alton, Ill. L1	14.225
Bartonsville, Ill. K4	14.15
Monessen, Pa. P16	14.20
Roching, N.J. R5	14.35

### WIRE, Cold-Rolled Flat

Anderson, Ind. G6	9.00
Baltimore T6	9.30
Buffalo W12	9.00
Cleveland A7	9.00
Crawfordsville, Ind. M8	9.00
Dover, O. G6	9.00
Fostoria, O. S1	9.00
Franklin Park, Ill. T8	9.10
Kokomo, Ind. C16	9.00
Massillon, O. R8	7.95
Milwaukee C23	9.20
Monessen, Pa. P16	9.00
Pawtucket, R.I. N8	9.30
Riverdale, Ill. A1	9.10
Rome, N.Y. R6	9.00
Trenton, N.J. R5	9.30
Worcester A7, T6, W12	9.30

### NAIL, Stock

Altoona City, Ala. R2	152
Altoona City, Pa. J5	152
Atlanta A11	154
Bartonsville, Ill. K4	154
Chicago, Ill. W13	152
Cleveland A9	157
Crawfordsville, Ind. M8	154
Donora, Pa. A7	152
Duluth, Minn. A7	152
Fairfield, Ala. T2	152
Gaustown, Tex. D7	157
Houston, Tex. S5	157
Johnstown, Pa. B2	152
Joliet, Ill. A7	152
Kansas City, Mo. S5	157
Kokomo, Ind. C16	154
Minneapolis, Colo. C10	157
Monessen, Pa. P7	157
Pittsburg, Calif. C11	171
Rankin, Pa. A7	152
So. Chicago, Ill. R2	152
Sparrows Pt., Md. B2	154
Sterling, Ill. (1) N15	152
Worcester, Mass. A7	158

### NAIS, CUT (100 lb keg)

To Dealers (33)	
Conshohocken, Pa. A3	\$9.05
Wheeling, W. Va. W10	9.05

### STAPLES, Polished Stock

Altoona City, Pa. J5	152
Atlanta A11	154
Bartonsville, Ill. K4	154
Crawfordsville, Ind. M8	154
Donora, Pa. A7	152
Duluth, Minn. A7	152
Fairfield, Ala. T2	152
Johnstown, Pa. B2	152
Joliet, Ill. A7	152
Kokomo, Ind. C16	154
Minneapolis, Colo. C10	157
Monessen, Pa. P7	157
Pittsburg, Calif. C11	171
Rankin, Pa. A2	152
Sparrows Pt., Md. B2	154
Sterling, Ill. (1) N15	152
Worcester, Mass. A7	158

### TIE WIRE, Automatic Baler

(14 1/2 Ga.) (Per 97 lb Net Box)

Altoona City, Ala. R2	\$8.77
Bartonsville, Ill. K4	9.45
Buffalo W12	9.35
Crawfordsville, Ind. M8	9.46
Donora, Pa. A7	9.35
Duluth, Minn. A7	9.35
Johnstown, Pa. B2	9.35
Joliet, Ill. A7	9.35
Kokomo, Ind. C16	9.45
Los Angeles B3	10.14
Minneapolis, Colo. C10	9.60
So. Chicago, Ill. R2	8.77
Sparrows Pt., Md. B2	9.45
Sterling, Ill. N15	9.35
Coil No. 6500 Stand.	
Altoona City, Ala. R2	\$9.05
Bartonsville, Ill. K4	9.75
Buffalo W12	9.60
Crawfordsville, Ind. M8	9.75
Donora, Pa. A7	9.65
Duluth, Minn. A7	9.65
Johnstown, Pa. B2	9.65
Joliet, Ill. A7	9.65
Kokomo, Ind. C16	9.75
Los Angeles B3	10.45
Minneapolis, Colo. C10	9.90
So. Chicago, Ill. R2	9.05
Sparrows Pt., Md. B2	9.75
Sterling, Ill. N15	9.65
Coil No. 6500 Interim	
Altoona City, Ala. R2	\$9.10
Bartonsville, Ill. K4	9.80
Buffalo W12	9.70
Crawfordsville, Ind. M8	9.80
Donora, Pa. A7	9.70

Duluth, Minn. A7	9.70
Johnstown, Pa. B2	9.70
Joliet, Ill. A7	9.70
Kokomo, Ind. C16	9.80
Los Angeles B3	11.05
Minneapolis, Colo. C10	9.95
So. Chicago, Ill. R2	9.10
Sparrows Pt., Md. B2	9.80
Sterling, Ill. N15	9.70

### WIRE, Barbed

Altoona City, Ala. R2	175**
Altoona City, Pa. J5	178*
Atlanta A11	181
Bartonsville, Ill. K4	181
Crawfordsville, Ind. M8	181
Donora, Pa. A7	175*
Duluth, Minn. A7	175*
Fairfield, Ala. T2	175*
Houston, Tex. S5	180*
Johnstown, Pa. B2	179*
Joliet, Ill. A7	175*
Kansas City, Mo. S5	180*
Kokomo, Ind. C16	177*
Minneapolis, Colo. C10	180*
Monessen, Pa. P7	182
Pittsburg, Calif. C11	195*
Rankin, Pa. A7	175*
So. Chicago, Ill. R2	159**
So. San Francisco, Cal. B2	195**
Sparrows Pt., Md. B2	181*
Sterling, Ill. (1) N15	179*

### WOVEN Fence, 9-15 Ga.

Altoona City, Ala. R2	146**
Altoona City, Pa. J5	241**
Atlanta A11	154
Bartonsville, Ill. K4	154
Chicago, Ill. W13	152
Cleveland A9	157
Crawfordsville, Ind. M8	154
Donora, Pa. A7	152
Duluth, Minn. A7	152
Fairfield, Ala. T2	152
Gaustown, Tex. D7	157
Houston, Tex. S5	157
Johnstown, Pa. B2	152
Joliet, Ill. A7	152
Kansas City, Mo. S5	157
Kokomo, Ind. C16	154
Minneapolis, Colo. C10	157
Monessen, Pa. P7	157
Pittsburg, Calif. C11	171
Rankin, Pa. A7	152
So. Chicago, Ill. R2	152
Sparrows Pt., Md. B2	154
Sterling, Ill. (1) N15	152
Worcester, Mass. A7	158

### WIRE (16 Gauge) Stone Stone

Altoona City, Ala. R2	13.15 14.70**
Bartonsville, Ill. K4	14.60 16.50
Buffalo W12	14.50
Cleveland A7	14.50
Crawfordsville, Ind. M8	14.60 16.50
Fostoria, O. S1	14.60 16.15*
Johnstown, Pa. B2	14.15 16.40*
Kokomo, Ind. C16	14.60 16.15*
Minneapolis, Colo. C10	14.75 16.45**
Palmer, Mass. W12	14.50 16.05*
Pittsburg, Calif. C11	14.85 16.40*
So. Chicago, Ill. R2	13.15 14.70
Sparrows Pt., Md. B2	14.60 16.50*
Sterling, Ill. (1) N15	14.50 16.40
Waukegan, Ill. A7	14.50 16.05*
Worcester A7	14.80
Altoona City, Ala. R2	7.40 7.80**

### WIRE, Merchant Quality

(6 to 8 gauge) An'd Galv.	
Altoona City, Ala. R2	7.40 7.925*
Atlanta A11	7.50 8.075
Bartonsville, Ill. K4	7.50 8.075
Buffalo W12	7.40 8.80*
Cleveland A7	7.40
Crawfordsville, Ind. M8	7.50 8.075
Donora, Pa. A7	7.40 7.80*
Duluth, Minn. A7	7.40 7.80*
Fairfield, Ala. T2	7.40 7.80*
Houston, Tex. S5	7.65 8.05*
Jacks'ville, Fla. M8	7.90 8.475
Johnstown, Pa. B2	7.40 7.975*
Joliet, Ill. A7	7.40 7.80*
Kansas City, Mo. S5	7.65 8.05*
Kokomo, Ind. C16	7.50 7.90*
Los Angeles B3	8.35 8.925*
Minneapolis, Colo. C10	7.65 8.05*
Monessen, Pa. P7	7.40 7.45
So. San Francisco, Cal. B2	7.70 8.10*
Pittsburg, Calif. C11	8.35 8.75*
Portsmouth, O. P12	7.40
Rankin, Pa. A7	7.40 7.80*
So. Chicago, Ill. R2	7.40 7.80*
So. S. Fran. Cal. B2	8.35 8.75**
Sparrows Pt., Md. B2	7.40 7.975*
Struthers, O. (48) Y1	7.40 7.901
Worcester, Mass. A7	7.70

\*Based on 12.50c zinc; †5c zinc; ‡10c zinc; §less than 10c zinc; \*\*Subject to zinc equalization extras.

BALE TIES, Single Loop Col.	
Altoona City, Ala. R2	173
Atlanta A11	175
Bartonsville, Ill. K4	175
Crawfordsville, Ind. M8	175
Donora, Pa. A7	173
Duluth, Minn. A7	173
Fairfield, Ala. T2	173
Joliet, Ill. A7	173
Houston S5	178
Kansas City, Mo. S5	178
Kokomo, Ind. C16	175
Minneapolis, Colo. C10	178
Pittsburg, Calif. C11	197
So. San Fran. Cal. B2	197
Sparrows Pt., Md. B2	175
Sterling, Ill. (1) N15	173

## BOLTS, NUTS

### CARRIAGE, MACHINE BOLTS

(Base discounts, per cent off list, f.o.b. midwestern plants)	
4 in. and shorter:	
1/2 in. & smaller diam.	2
Over 4 in. through 6 in.:	
1/2 in. & smaller diam.	+3
6 in. and shorter:	
3/8 in. and 1/2 in.	+4
1/2 in. and larger	+6
Longer than 6 in.:	
All diameters	+15
Lag bolts, all diams:	
6 in. and shorter	6
Over 6 in. long	+2
Blank Necked Carriage Bolt	+4
Ribbed	10
Plow	23
Step, Elevator, Tap and Sleigh Shoe	10
Tire Bolts	+3
Boiler & Fitting-Up Bolts	21

## NUTS

H.P. and C.P., regular & heavy:	
Square, all sizes	55
H.P., Hex, regular & heavy:	
3/8" & smaller	55
3/8" to 1 1/2", inclusive	58
1 1/2" to 1 3/4", inclusive	60
1 3/4" and larger	55
C.P. Hex regular & heavy:	
All sizes	55
Hot Galv. Nuts (all types):	
3/8" or smaller	38
3/8" to 1 1/2", inclusive	41
Finished Hex Nuts:	
New standard, all sizes	55
Semifinished & Slotted Hex:	
Regular and heavy, all sizes	55

## SQUARE HEAD SET SCREWS

(1035 steel; packaged; per cent off list)	
1 in. diam x 6 in. and shorter	34
1 in. and smaller diam x over 6 in.	20

## HEADLESS SET SCREWS

(Packaged; per cent off list)	
No. 10 and smaller	34
1/4 in. diam & larger	14
N.F. thread, all diams.	8

## STEEL STOVE BOLTS

(F.o.b. plant, per cent off list in packages)	
Plain finish	43
Plated finishes	23

## HEXAGON CAP SCREWS

(1020 steel; packaged; per cent off list)	
6 in. or shorter:	
1/4 in. through 3/8 in.	38
3/8 in. through 1 in.	15
Longer than 6 in.:	
1/4 in. through 3/8 in.	20
3/8 in. through 1 in.	7

## Footnotes

- (1) Chicago base.
- (2) Angles, flats, bands.
- (3) Merchant.
- (4) Reinforcing.
- (5) Chicago or Birm. base.
- (6) To jobbers, 3 cols. lower.
- (7) 16 Ga. and heavier.
- (8) Pittsburgh base.
- (9) Cleveland & Pitts. base.
- (10) Worcester, Mass., base.
- (11) Add 0.25c for 17 Ga. & heavier.
- (12) Gage 0.143 to 0.249 in.; for gage 0.142 and lighter, 5.80c.
- (13) 3/4" and thinner.
- (14) 40 lb and under.
- (15) Flats only; 0.25 in. & heavier.

## BOILER TUBES

Net base c.l. prices, dollars per 100 ft. mill; minimum wall thickness, cut lengths 10 to 24 ft. inclusive.

O.D.	B.W. Gage	H.R.	C.D.	Elec. Weld
1 in.	13	19.59	20.41	
1 1/4 in.	13	23.21	20.44	
1 1/2 in.	13	25.65	22.60	
1 3/4 in.	13	30.31	26.71	
2 in.	13	33.97	29.93	
2 1/4 in.	13	31.91	33.72	
2 1/2 in.	12	34.63	36.59	
2 3/4 in.	12	38.15	45.74	40.31
3 in.	12	41.31	49.53	43.65
3 1/2 in.	12	44.05	52.82	46.54

## RAILWAY MATERIALS

RAILS	Standard	All	Tee Rails
Bessemer, Pa. U5	4.725	4.625	4.675
Ensley, Ala. T2	4.725	4.625	5.65
Fairfield, Ala. T2	4.725	4.625	5.65
Gary, Ind. U5	4.725	4.625	5.65
Huntington, W. Va. W7	4.725	4.625	5.65
Indiana Harbor, Ind. I-2	4.725	4.625	5.65
Johnstown, Pa. B2	4.725	4.625	5.65
Lackawanna, N.Y. B2	4.725	4.625	5.65
Lackawanna, N.Y. B2	4.725	4.625	5.65
Steeltown, Pa. B2	4.725	4.625	5.65
Williamsport, Pa. S19	4.725	4.625	5.65

## TIE PLATES

Fairfield, Ala. T2	5.625
Gary, Ind. U5	5.625
Ind. Harbor, Ind. I-2	5.625
Lackawanna, N.Y. B2	5.625
Minneapolis, Colo. C10	5.625
Seattle B3	5.625
Steeltown, Pa. B2	5.625
Torrance, Calif. C11	5.775

## TRACK BOLTS (20) Treated

Cleveland R2	11.50
Kansas City, Mo. S5	11.50
Lebanon, Pa. B2	12.40
Minneapolis, Colo. C10	12.40
Pittsburgh O3, P14	11.50
Seattle B3	12.90

## AXLES

Ind. Harbor, Ind. S13	7.25
Johnstown, Pa. B2	7.25

## METAL POWDERS

(Per pound, f.o.b. shipping point in ton lots for minus 100 mesh, except as otherwise noted)	
Sponge iron	Cents
98+ % Fe, annealed	15.25
Unannealed:	
Minus 100 mesh	11.75
Minus 35 mesh	9.25
Minus 20 mesh	9.00
Swedish, c.i.f. N. Y., c.l. in bags	11.25
Domestic (Swedish), f.o.b. Riverton, N.J., in bags	9.50
Canadian, f.o.b. shipping point	9.50
Electrolytic iron:	
Melting stock, 99.91% Fe, irregular fragments of 1/2 in. x 1 1/2 in.	21.00
Annealed, 99.5% Fe	36.50
Unannealed (99+ % Fe)	32.50
Unannealed (99+ % Fe) (minus 325 mesh)	52.00
Powder Flakes (minus 16, plus 100 mesh)	31.00
Carbonyl Iron:	
97.9-99.8% size 5 to 10 microns	83.00-148.00
Aluminum:	
Atomized, 500 lb drums, freight allowed	
Carlots	32.20
Ton lots	34.20
Antimony, 500 lb lots	32.00*
Brass, 5000-lb lots	39.00-49.00†
Bronze, 5000-lb lots	58.00-61.50†
Copper:	
Electrolytic	13.75*
Reduced	13.75*
Lead	7.50*
Manganese:	
Minus 35 mesh	61.00
Minus 100 mesh	67.00
Minus 200 mesh	72.00



## SEAMLESS STANDARD PIPE, Threaded and Coupled

Size-Inches	2	2½	3	3½	4	5	6							
List Per Ft	37c	58.5c	78.5c	92c	\$1.09	\$1.48	\$1.92							
Pounds Per Ft	3.68	5.82	7.62	9.20	10.89	14.81	19.18							
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*						
Aliquippa, Pa. J5.....	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25
Ambridge, Pa. N2.....	6.5	..	10.5	..	13	..	14.5	..	14.5	..	14	..	16.5	..
Lorain, O. N3.....	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25
Youngstown, Y1.....	6.5	+10	10.5	+7.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25

## ELECTRIC WELD STANDARD PIPE, Threaded and Coupled

Youngstown R2	6.5	+10	10.5	+1.25	13	+4.75	14.5	+3.25	14.5	+3.25	14	+3.75	16.5	+1.25
---------------	-----	-----	------	-------	----	-------	------	-------	------	-------	----	-------	------	-------

## BUTTWELD STANDARD PIPE, Threaded and Coupled

Size-Inches	¾	1	1½	2	2½	3	3½	4						
List Per Ft	5.5c	6c	6.57	8.5c	11.5c	17c	28c	28c						
Pounds Per Ft	0.24	0.42	0.57	0.86	1.13	1.68	2.28	2.28						
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*						
Aliquippa, Pa. J5	...	...	...	...	17.5	0.25	20.5	4.25	23	7.75	25.5	9		
Alton, Ill. L1	...	...	...	...	15.5	+1.75	18.5	2.25	21	5.75	23.5	7		
Benwood, W. Va. W10	16.5	+12	7.25	+18.25	+1.75	+26.25	17.5	0.25	20.5	4.75	23	7.75	25.5	7
Butler, Pa. F6	17.5	+11	9	+16.5	0.5	+24	...	...	...	...	...	...	...	...
Etna, Pa. N2	...	...	...	...	17.5	0.25	20.5	4.25	23	7.75	25.5	9		
Fairless Hills, Pa. N3	...	...	...	...	15.5	+1.75	18.5	2.75	21	5.75	23.5	7		
Fontana, Calif. K1	...	...	...	...	10.76	+6.5	13.76	+2.6	16.26	1	18.76	2.26		
Ind. Harbor, Ind. Y1	...	...	...	...	16.5	+0.75	19.5	3.25	22	6.75	24.5	8		
Lorain, O. N3	...	...	...	...	17.5	0.25	20.5	4.25	23	7.75	25.5	9		
Sharon, Pa. S4	17.5	+11	9	+16.5	0.5	+24	...	...	...	...	...	...	...	...
Sparrows Pt. Md. B2	23	+5.5	15	+10.5	7.6	+17	21.75	4.5	24.75	8.5	27.25	12	29.75	13.25
Youngstown R2, Y1	...	...	...	...	17.5	0.25	20.5	4.25	23	7.75	25.5	9		
Wheatland, Pa. W9	23	+5.5	15	+10.5	7.6	+17	23.75	6.5	26.75	10.5	29.25	14	31.75	15.25

Size-Inches	1½	2	2½	3	3½	4
List Per Ft	27.5c	37c	58.5c	76.5c	92c	\$1.09
Pounds Per Ft	2.73	3.68	5.83	7.62	9.20	10.89
	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	26	10	26.5	10.5	28	10.75
Alton, Ill. L1	24	8	24.5	8.5	26	8.75
Benwood, W. Va. W10	26	10	26.5	10.5	28	10.75
Etna, Pa. N2	26	10	26.5	10.5	28	10.75
Fairless Hills, Pa. N3	24	8	24.5	8.5	26	8.75
Fontana, Calif. K1	19.25	3.25	19.75	3.75	21.25	4
Ind. Harbor, Ind. Y1	25	9	25.5	9.5	27	9.75
Lorain, O. N3	26	10	26.5	10.5	28	10.75
Sharon, Pa. S4	26	10	26.5	10.5	28	10.75
Sparrows Pt., Md. B2	30.25	14.25	30.75	14.75	32.25	15
Youngstown R2, Y1	26	10	26.5	10.5	28	10.75
Wheatland, Pa. W9	32.25	16.25	32.75	16.75	34.25	17

\*Galvanized pipe discounts based on current price of zinc (12.50c, East St. Louis).

## Stainless Steel

Representative prices, cents per pound; subject to current lists of extras

Alsi Type	Revolving Ingots	Revolving Slabs, Billets	Forging Billets	Seamless Tube Billets	H.R. Strip	Shapes; H.R. & C.F. Bars; Wire	Plates	Sheets	C.R. Strip; Flat Wire
301	17.75	22.25	..	36.75	32.00	38.00	..	44.25	41.00
302	19.00	24.75	32.00	37.25	34.50	38.25	40.25	44.50	44.50
302B	20.25	26.50	33.00	37.25	37.75	38.25	40.25	48.00	48.00
303	..	28.75	34.75	40.00	..	41.00	..	..	..
304	20.25	26.00	33.75	39.00	37.25	40.25	43.00	47.25	47.25
304L	..	..	39.00	44.25	42.50	45.50	48.25	52.50	52.50
305	..	28.25	..	39.50	40.25	40.25	43.50	50.25	50.25
308	21.00	..	38.50	44.25	41.25	45.50	48.75	62.00	62.00
309	22.50	38.25	46.75	53.50	53.50	54.75	58.25	67.00	67.00
309S	31.50	41.00	51.00	59.00	65.50	60.25	63.75	74.00	74.00
310	37.25	48.00	62.25	72.25	68.50	73.50	76.25	78.75	78.75
314	..	..	..	..	..	..	..	..	..
316	31.50	40.25	51.25	59.50	63.25	60.75	64.00	68.25	68.25
316L	..	..	56.80	65.00	63.50	66.00	69.50	73.50	73.50
317	37.25	48.25	62.75	72.75	73.50	74.50	77.00	83.75	83.75
221	25.00	32.00	38.25	44.00	44.25	45.25	49.25	54.25	54.25
18-8CDTa	31.00	40.50	48.75	55.25	56.25	57.00	62.00	70.50	70.50
403	..	..	28.75	32.75	..	34.00	36.25	..	44.00
405	17.50	23.00	26.75	31.00	32.25	32.00	33.75	42.25	42.25
410	15.00	19.50	25.50	29.50	28.00	30.50	31.75	36.25	36.25
413	..	..	26.00	30.00	..	31.00	..	..	..
420	23.50	30.25	31.00	36.00	37.75	37.25	40.75	56.00	56.00
430	15.25	19.75	26.00	30.00	28.75	31.00	32.25	36.75	36.75
430F	..	..	26.50	30.50	..	31.50	..	..	..
431	16.00	20.50	26.50	30.50	29.75	31.50	33.00	38.00	38.00
431L	..	..	35.50	40.50	53.25	42.00	43.25	63.25	63.25

Stainless Steel Producers Are: Allegheny Ludlum Steel Corp.; Alloy Metal Wire Co. Inc.; Alloy Tube Div., Carpenter Steel Co.; American Steel & Wire Div., U. S. Steel Corp.; Armco Steel Corp.; Babcock & Wilcox Co.; Bethlehem Steel Co.; J. Bishop & Co.; G. O. Carlson Inc.; Carpenter Steel Co.; Charter Wire Products Co.; Cold Metal Products Co.; Crucible Steel Co. of America; Damascus Tube Co.; Wilbur B. Driver Co.; Driver-Harris Co.; Eastern Stainless Steel Corp.; Ellwood Ivins Steel Tube Works Inc.; Firth Sterling Inc.; Ft. Wayne Metals Inc.; Globe Steel Tubes Co.; Helical Tube Co.; Indiana Steel & Wire Co.; Ingersoll Steel Div., Borg-Warner Corp.; Jessop Steel Co.; Johnson Steel & Wire Co. Inc.; Joslyn Mfg. & Supply Co.; Kenmore Metals Corp.; Maryland Fine & Specialty Wire Co.; McLouth Steel Corp.; Metal Forming Corp.; McInnes Steel Co.; National-Standard Co.; National Tube Div., U. S. Steel Corp.; Newman-Crosby Steel Co.; Pacific Tube Co.; Page Steel & Tube Div., American Chain & Cable Co. Inc.; Pittsburgh Rolling Mills Inc.; Republic Steel Corp.; Rodney Metals Inc.; Rome Mfg. Co.; Rotary Electric Steel Co.; Sharon Steel Corp.; Sawhill Tubular Products Inc.; Simonds Saw & Steel Co.; Specialty Wire Co. Inc.; Spencer Wire Corp.; Stainless Wrold Products Inc.; Standard Tube Co.; Superior Steel Corp.; Superior Tube Co.; Timken Roller Bearing Co.; Trent Tube Co.; Tube Methods Inc.; Ulbrich Stainless Steels; United States Steel Corp.; Universal-Cyclops Steel Co.; Wallingford Steel Co.; Washington Steel Corp.

## Clad Steel

	Plates Carbon Base	Sheets Carbon Base
	10% 20%	20%
Stainless:		
302	..	28.00
304	28.30	29.75
304-L	30.30	..
310	41.30	..
316	33.40	42.75
316-L	37.80	..
316-CB	38.90	..
321	30.00	34.25
347	32.20	44.25
405	28.90	..
410	23.40	30.60
430	23.40	24.25
Inconel	47.90	63.90
Nickel	39.50	54.10
Monel	40.80	54.80
L-Nickel	41.70	58.50
Copper*	..	46.00
	Strip, Carbon Base	Both Sides
	10% Cold Rolled	
Copper*	28.60	33.00

\*Deoxidized. Production points: Stainless-clad sheets, New Castle, Ind. I-4; stainless-clad plates, Claymont, Del. C22, Coatesville, Pa. L7, New Castle, Ind. I-4 and Washington, Pa. J3; nickel, inconel, monel-clad plates, Coatesville L7; copper-clad strip, Carnegie, Pa. S18.

## Tool Steel

Grade	\$ per lb	Grade	\$ per lb
Regular Carbon	0.275	5% Cr Hot Work	0.430-0.460
Extra Carbon	0.330	W-Cr Hot Work	0.450
Special Carbon	0.390	V-Cr Hot Work	0.470
Oil Hardening	0.430	Hi-Carbon-Cr	0.770

W	Cr	V	Co	Mo	\$ per lb
20.25	4.25	1.6	12.25	..	4.090
18.25	4.25	1	4.75	..	2.305-2.475
18	4	2	9	..	2.675-2.6775
18	4	2	..	..	1.765
18	4	1	5	..	1.600
13.75	3.75	2	..	..	1.865
13.5	4	3	..	..	1.780
9	3.5	2	..	..	1.705
6	4	3	..	..	1.350
6	4	2	..	..	0.960
1.5	4	1	..	..	..

Tool steel producers include: A4, A8, B2, B3, C4, C9, C13, C18, D4, F2, J3, M14, S8, U4, V2 and V3.

# Pig Iron

F.o.b. furnace prices in dollars per gross ton, as reported to STEEL. Minimum delivered prices are approximate and do not include 3% federal tax.

	Basic	No. 2 Foundry	Malleable	Bessemer		Basic	No. 2 Foundry	Malleable	Bessemer
<b>Birmingham District</b>					<b>Youngstown District</b>				
Alabama, City, Ala. R2	54.50	55.00†	...	...	Hubbard, O. Y1	...	...	59.00	...
Birmingham R2	54.50	55.00†	...	...	Sharpsville, Pa. S6	58.50	...	59.00	59.50
Birmingham U6	...	55.00†	59.00†	...	Youngstown Y1	...	...	59.00	59.50
Woodward, Ala. W15	54.50	55.00†	59.00	...	Youngstown U5	58.50	...	...	59.50
Cincinnati, deld.	...	62.70	...	...	Mansfield, O., deld.	63.40	...	63.90	64.40
<b>Buffalo District</b>					Duluth I-3	58.50	59.00	59.00	59.50
Buffalo H1, R2	58.50	59.00	59.50	60.00	Erie, Pa. I-3	58.50	59.00	59.00	59.50
Tonawanda, N.Y. W12	58.50	59.00	59.50	60.00	Everett, Mass. E1	60.50	61.00	61.50	...
No. Tonawanda, N.Y. T9	...	59.00	59.50	60.00	Fontana, Calif. K1	62.00	62.50	...	...
Boston, deld.	69.15	69.65	70.15	...	Geneva, Utah C11	58.50	59.00	...	...
Rochester, N.Y. deld.	61.62	62.02	62.52	...	Granite City, Ill. G4	60.40	60.90	61.40	...
Syracuse, N.Y. deld.	62.62	63.12	63.62	...	Ironton, Utah C11	58.50	59.00	...	...
<b>Chicago District</b>					LoneStar, Texas L6	52.00	52.50*	52.50	...
Chicago I-3	58.50	59.00	59.00	59.50	Minnequa, Colo. C10	60.50	61.00	61.50	...
Chicago R2	58.50	...	59.00	...	Rockwood, Tenn. T3	...	55.00†	59.00	...
Gary, Ind. U5	58.50	...	59.00	...	Toledo, O. I-3	58.50	59.00	59.00	59.50
So. Chicago, Ill. Y1	58.50	59.00	59.00	59.50	Cincinnati, deld.	64.26	64.76	...	...
So. Chicago, Ill. U5, W14	58.50	...	59.00	59.50	*Low phos. southern grade.				
Milwaukee, deld.	60.67	61.17	61.17	61.67	†Phos., 0.30 max.				
Muskegon, Mich., deld.	...	65.30	65.30	...	‡Intermediate (Phos. 0.31-0.69%), \$56.				
<b>Cleveland District</b>					<b>PIG IRON DIFFERENTIALS</b>				
Cleveland A7, R2	58.50	59.00	59.00	59.50	<b>Silicon:</b> Add 50 cents per ton for each 0.25% Si or percentage thereof over base grade, 1.75-2.25%, except on low phos iron on which base is 1.75-2.00%.				
Akron, O., deld.	61.25	61.75	61.75	62.25	<b>Manganese:</b> Add 50 cents per ton for each 0.50% manganese over 1% or portion thereof.				
Lorain, O. N3	58.50	...	...	59.50	<b>Nickel:</b> Under 0.05% no extra; 0.50-0.74%, inclusive, add \$2 per ton and each additional 0.25%, add \$1 per ton.				
<b>Mid-Atlantic District</b>					<b>BLAST FURNACE SILVERY PIG IRON, Gross Ton</b>				
Bethlehem, Pa. B2	60.50	61.00	61.50	62.00	(Base 6.00-6.50% silicon; add \$1 for each 0.5% Si; 75 cents for each 0.50% Mn over 1%)				
New York, deld.	...	64.78	65.28	...	Jackson, O. G2, J1	...	...	...	\$67.50
Newark, deld.	63.52	64.02	64.52	65.02	Buffalo H1	...	...	...	68.75
Birdsboro, Pa. B10	60.50	61.00	61.50	62.00	<b>ELECTRIC FURNACE SILVERY PIG IRON, Gross Ton</b>				
Chester, Pa. C31	54.50	55.00	55.50	...	(Base 14.01-14.50% silicon; add \$1 for each 0.50 Si to 18%; \$1 for each 0.50% Mn over 1%; \$2 per gross ton premium for 0.045% max P)				
Philadelphia, deld.	56.16	56.66	57.16	...	Niagara Falls, N.Y. P15	...	...	...	\$80.50
Steelton, Pa. B2	60.50	61.00	61.50	62.00	Keokuk, Iowa, (Open-hearth & Fdry, freight allowed K2)	...	...	...	87.50
Swedeland, Pa. A3	60.50	61.00	61.50	62.00	Keokuk, O.H. & Fdry, 12½ lb piglets, 16% Si, frgt allowed K2	...	...	...	90.50
Philadelphia, deld.	62.16	62.66	63.16	63.66	<b>LOW PHOSPHORUS PIG IRON, Gross Ton</b>				
Troy, N.Y. R2	60.50	61.00	61.50	62.00	Lyles, Tenn. T3 (Phos. 0.035 max.)	...	...	...	\$72.50
<b>Pittsburgh District</b>					Steelton, Pa. B2 (Phos. 0.035 max.)	...	...	...	66.50
Neville Island, Pa. P6	58.50	59.00	59.00	...	Philadelphia, deld.	...	...	...	70.05
Pittsburgh (N&S sides),	...	...	...	...	Troy, N.Y. R2 (Phos. 0.035 max.)	...	...	...	66.50
Alquippa, deld.	...	60.37	60.37	60.87	Cleveland A7 (Intermediate) (Phos. 0.036-0.075 max.)	...	...	...	63.50
McKees Rocks, deld.	...	60.04	60.04	60.54	Duluth I-3 (Intermediate) (Phos. 0.036-0.075 max.)	...	...	...	63.50
Lawrenceville, Homestead,	...	...	...	...	Erie, Pa. I-3 (Intermediate) (Phos. 0.036-0.075 max.)	...	...	...	63.50
Wilmerding, Monaca, deld.	...	60.66	60.66	61.16					
Verona, Trafford, deld.	60.69	61.19	61.19	61.69					
Brackenridge, deld.	60.95	61.45	61.45	61.95					
Bessemer, Pa. U5	58.50	...	59.00	59.50					
Chairton, Rankin, So. Duquesne, Pa. U5	58.50	...	...	...					
McKeesport, Pa. N3	58.50	...	...	59.50					
Midland, Pa. C18	58.50	...	...	...					

# Warehouse Steel Products


Representative prices, cents per pound subject to extras, f.o.b. warehouse. City delivery charges are 20 cents per 100 lb except Buffalo, Cleveland, 30 cents; Chicago, Milwaukee, St. Louis, St. Paul, Detroit, Cincinnati, Pittsburgh, 25 cents; Philadelphia, New York, Baltimore, Boston, San Francisco, Los Angeles, and Portland, Ore., 10 cents; Atlanta, Houston, Seattle, Spokane, Wash., no charge.

	SHEETS				STRIP		BARS				Standard Structural Shapes	PLATES	
	Hot Rolled	Cold Rolled	Gal. 10 Ga.†	Stainless Type 302	H.R.*	C.R.*	H.R. Rds.	C.F. Rds.‡	H.R. Alloy 4140††§	Carbon		Floor	
Atlanta .....	6.79	7.75	8.37	43.43	7.05	...	6.92	8.89	....	7.08	7.09	8.83	
Baltimore .....	7.03	8.32	9.00	....	7.65	...	7.61	8.62 <sup>a</sup>	13.44	7.93	7.21	8.87	
Birmingham ...	6.76	7.80	8.85	....	6.95	...	7.00	9.35	....	7.20	7.05	9.10	
Boston .....	7.70	8.81	10.27	45.67	7.96	...	7.83	9.53	13.45	8.13	7.89	9.36	
Buffalo .....	6.80	7.90	9.77	....	7.15	...	7.10	7.90	13.10	7.40	7.15	7.70	
Charlotte, N. C.	6.95	7.80	8.89	....	6.90	...	7.10	8.37	....	7.10	7.10	8.37	
Chicago .....	6.80	7.93	8.50	46.05	7.06	...	7.08	7.75	12.85	7.28	6.99	8.46	
Cincinnati .....	6.92	7.92	8.90	46.10	7.30	...	7.32	8.05	14.09	7.75	7.28	8.71	
Cleveland .....	6.80	7.93	8.85	....	7.16	...	7.14	7.85	12.91	7.61	7.16	...	
Detroit .....	6.99	8.12	8.78	43.50	7.34	...	7.36	8.04	13.05	7.75	7.27	8.65	
Erie, Pa. ....	6.35	7.38	8.30	....	6.70	...	6.50	7.45 <sup>a</sup>	....	6.69	6.52	7.64	
Houston .....	7.85	8.75	10.49	....	8.15	...	8.25	9.85	14.00	8.20	7.80	...	
Los Angeles ...	8.05	10.00	11.00	....	8.35	...	8.05	11.25	14.25	8.30	8.05	10.25	
Milwaukee ....	6.89	8.02	8.50	....	7.15	...	7.17	7.94	12.94	7.45	7.08	8.55	
Moline, Ill. ....	6.73	7.73	8.85	....	6.97	...	6.86	7.60	....	7.04	6.87	...	
New York .....	7.46	8.68	9.44	44.95	8.07	...	7.96	9.48	13.28	7.99	7.76	9.19	
Norfolk, Va. ...	7.25	...	...	....	7.65	...	7.65	9.50	....	7.95	7.45	8.95	
Philadelphia ...	7.14	8.42	9.35	45.98	7.67	9.02	7.64	8.46	13.16	7.74	7.37	8.69	
Pittsburgh .....	6.80	7.93	9.20	48.67	7.16	...	7.08	7.85	13.10	7.28	6.99	8.46	
Portland, Oreg..	7.80	8.80	10.65	....	8.00	...	7.95	11.80	15.00	8.15	7.75	...	
Richmond, Va. ...	7.00	...	9.47	....	7.65	...	7.70	8.85	....	7.95	7.20	9.10	
St. Louis .....	7.09	8.22	9.19	43.89	7.35	...	7.37	8.14	13.14	7.68	7.28	8.76	
St. Paul .....	7.46	8.59	9.16	....	7.72	...	7.74	8.51	13.51	7.94	7.65	...	
San Francisco...	8.10	9.55	9.90	51.65	8.35	...	8.05	11.20	14.25 <sup>a</sup>	8.25	8.05	10.25	
Seattle .....	8.55	10.40	10.80	54.00	8.65	...	8.35	11.70	14.60	8.30	8.20	10.10	
Spokane .....	8.55	11.00 <sup>7</sup>	10.80	....	9.05	...	8.35	11.80	15.35	8.30	8.20	10.60	
Washington .....	7.50	8.79	7.97	....	8.12	...	8.08	9.09	....	8.40	7.68	9.34	

\*Prices do not include gage extras; †prices include gage and coating extras (based on 12.50-cent zinc), except in Birmingham (coating extra excluded); ‡includes 35-cent special bar quality extras; \*\*¾-in. and heavier; ††as annealed; ‡‡under ¾-in.

Base quantities, 2000 to 4999 lb except as noted: Cold-rolled strip and cold-finished bars, 2000 lb and over except in Seattle, 2000 to 999 lb and in Los Angeles, 6000 lb and over; stainless sheets, 8000 lb except in New York and Boston, 10,000 lb. and in San Francisco, 2000 to 4999 lb; hot-rolled products on West Coast, 2000 to 9999 lb; ½—500 to 9999 lb; ¾—400 to 999 lb; 1—1000 lb and over; 1½—1000 lb and over; 2—1500 to 3999 lb; 3—2000 to 3999 lb; 4—f.o.b. local delivery in lots of 10,000 lb and over.





**SUPERSONIC... the Douglas F4D "Skylark"**  
breaks the sound barrier at speeds of over 750 m.p.h.


## **...and GISHOLT SUPERFINISH** **breaks another cost barrier!**

Do you think of SUPERFINISH as an expensive process? Then it's high time you know the facts.

Here's an excellent case in point... on the record-breaking Douglas "Skylark." Among the most precise parts on this supersonic jet are the slide valves. They're ground from the solid, first on a cylindrical grinder, then on a centerless grinder. Then they're transferred to a Gisholt Superfinisher where the bearing sur-

faces get a finish of 3 micro-inches, r.m.s. Former time for hand-lapping ran from 2½ to 3 hours per piece. The Gisholt SUPERFINISHER does it in 45 seconds! Think of it: less than 1/200th of the time! And think what that does to costs!

If SUPERFINISH can improve your product, as probably it can, better get the facts. The complete story is in the booklet "Wear and Surface Finish." Ask us for your copy.



Approximate diam. of slide valves (lower left) is ½" with reduced diam. of ¼" between collars, or bearing surfaces. Parts are handled on the Gisholt Superfinisher in only 45 seconds per piece.

THE GISHOLT ROUND TABLE



represents the collective experience of specialists in the machining, surface-finishing and balancing of round and partly round parts. Your problems are welcomed here.




# **GISHOLT**

**MACHINE COMPANY**

Madison 10, Wisconsin

**TURRET LATHES • AUTOMATIC LATHES • SUPERFINISHERS • BALANCERS • SPECIAL MACHINES**





Pittsburgh Steel Corp.

Competition with slit sheet is the main reason why . . .

## Strip Producers Back Down

LOOK TO COLD-ROLLED STRIP for prime evidence that old-fashioned competition still flourishes in the steel industry.

Consumers and several smaller producers didn't like the new prices posted by the largest steel producer in the wake of the labor settlement in early July. When the dust settled, it (and others) had to change course and revise downward to meet sturdy competition.

Here's how it happened: When steelmakers announced new price schedules in early July, U. S. Steel upped the tag on cold-rolled carbon strip steel \$14 a ton—to \$129 a ton at American Steel & Wire Division mills in Cleveland. Other leading producers followed suit, reflecting increased labor costs.

**Quick Reaction**—Consumers and several eastern and midwestern producers refused to fall into step. In the East, producers advanced prices

\$10 a ton because of pressure from consumers that felt the \$14 increase was too steep to pass on to their customers. In the Midwest, Detroit Steel Corp., Detroit, announced an increase in base price of \$10 a ton. Sharon Steel Corp., Sharon, Pa., reported a base price of 6.25 cents per pound at Sharon, the same level established by Detroit at Portsmouth, O.

Republic Steel Corp. and American Steel & Wire met rivals by lopping \$4 off the announced \$14 at Cleveland. Weirton and Great Lakes Steel Corp. also trimmed prices to meet the trend.

**Sheet Rivalry**—Underlying this competition between producers is the bid by narrow slit sheet for some applications of cold-rolled strip (see STEEL, Oct. 25, 1954, p. 249).

At the end of World War II, many warehouses in important industrial cities began to install slitters, to furnish sheet in narrow widths for fab-

ricators that couldn't afford the equipment. With warehouse competition tightening in peacetime, distributors reduced slitting costs, while the differential between strip and sheet price increased. Strip costs more. It's made under precise rolling practices with more accurate width tolerances than slit sheet, has a specified temper and a variety of brighter, smoother finishes.

**Change to Sheet**—With hundreds of applications using strip, many fabricators have switched to slit sheet when they require a narrow band of steel with sheet instead of premium strip characteristics. The tendency to switch gets stronger each time the price differential rises.

Some sheet producers claim narrow slit sheet can serve about 85 per cent of the needs for narrow cold-rolled steel. While strip producers dispute this, slit sheet use has made substantial progress in the last ten years.

**Percentage Declines**—The result of this trend is that cold-finished strip makes up a smaller percentage of total steel shipments now than at any time since World War II. Some 1,281,993 tons were shipped in 1954, or 2 per cent of total shipments. This compares with 2,166,111 tons in 1953, comprising 2.7 per cent of the total, reports the American Iron & Steel Institute.

Don't underestimate over-all demand for cold-rolled strip in the many applications which call for a high-quality product. Among large consumers are producers of electric weld tubing, summer furniture, auto-makers, refrigerators and other appliances. Shoe shanks and lipstick cases are typical small-volume applications. Most of these consumers need strip's bright finish and close tolerances. But some will switch to slit sheet if the price differential between it and strip widens too far.

**Heavy Sales**—The cold-rolled strip market seldom has been stronger, and producers intend to keep sales healthy. "Orders are heavy in the third quarter, and we have yet to feel the full weight of automotive orders for next year's models," reports Sharon Steel.

Adds U. S. Steel: "There is no open space in the third quarter for sheet or strip orders. We look for a good fourth quarter, too. Inventories are generally low. Consumers can't stay out of the market for long."

## Sheets, Strip . . .

Sheet & Strip Prices, Pages 107 & 108

Sellers of hot and cold-rolled sheets are experiencing no important cut-backs in orders from consumers. And retrenchments have more than offset new demands from other consum-



ing areas. Some mills are so oversold that they are being forced to trim fourth-quarter requests of customers as much as 30 to 35 per cent in some cases.

The scheduling problems resulting from being oversold are so complicated some producers haven't committed themselves definitely for the final quarter. On the other hand, a portion of those fully booked for the entire period are considering opening books for first-quarter 1956 business. Some are on a district quota basis for the period, consumers being allotted steel largely on the basis of their historic buying pattern.

In allocating fourth quarter sheet tonnages to consumers, most mills in the Chicago area were forced to take into account carry-overs of at least a month or more. Some users appear unhappy because their shipments can't be increased.

One large producer which regards itself out of the market for the remainder of the year reports that only in a few cases has it not received full specifications from customers on such tonnage as it will be able to supply in fourth quarter. This tight situation applies not only to hot and cold-rolled sheets but to galvanized and specialties as well. Most makers of silicon sheets and enameling stock haven't any tonnage left for the remainder of the year.

The situation in galvanized is just about as tight, and threatening to make galvanized supply still tighter is the government request for bids (Aug. 5) on 11,000 of 14,000 new grain bins. Steel for these would command priority.

Stainless steel strip sellers are booked into October, but they can make better deliveries on stainless sheets—four to six weeks.

Narrow carbon strip, hot and cold rolled, is in tighter supply. At least one large producer has nothing to offer before November shipment, promises having jumped from around early September almost overnight.

Sheet demand from builders of railroad equipment, now sharply on the upswing, is posing special problems. Ship steel demand prospects also are improving. Most tonnage for ships, of course, is plates and structurals, but heavier demand for plates may mean larger and longer plate runs on the continuous mills now largely devoted to sheet production.

With regard to shipbuilding, 144,610 tons of shipping were under construction in the U. S. in the quarter ending in June. This was an increase of 30,850 tons over that in the March quarter, and a substantial increase is indicated for coming months. In fact, the proposed shipbuilding program is expected to bring this country up

among the leading shipbuilding nations.

A leading producer that early in July advanced its price on tight co-operation hoops from \$4.475 to \$5.325 base, last week cut back its increase to \$4.75 for an increase of \$5.50 per ton over the price in effect at the time of the initial change. Demand wouldn't support the higher price.

New England users of carbon sheets and specialties have some orders in for the remainder of this year with one month in the fourth quarter blanked out. Numerous users are asking for twice the tonnage ordered in second and third quarters, with duplicate inquiries increasing.

## Steel Bars . . .

Bar Prices, Page 106

Producers of hot-rolled carbon bars are well behind on their commitments as they accept orders for the fourth quarter. Few, if any, will be able to take more than two months of tonnage for production and shipment in the closing months of the year.

In alloys, the situation is somewhat different. Most sellers of hot-rolled alloy bars are current on commitments and wide open for fourth quarter bookings. They can no longer book much tonnage for delivery before the fourth quarter, however, though they have plenty of capacity available for October, November and December.

This also is true in large measure with cold-finished carbon and alloy bars. Producers can accept orders for stainless bar shipments in four to six weeks.

Hot carbon bar production still is being retarded by a lack of steel. This, combined with continued strong demand, accounts for the extended deliveries on practically all sizes and shapes. Merchant bar promises are becoming more extended. One eastern seller is talking October on sizes 1½-in. and under and has only limited tonnage available on the larger sizes for September shipment.

Some cold-finished bar mills are closed for vacations. This will put them two weeks farther behind schedule on back orders. Hot-rolled barmakers at Pittsburgh also are having trouble keeping up with orders; early third quarter customers will have to wait a week or two longer for deliveries.

As producers revise shipping schedules they report the possibility of a large carry-over of unfilled orders from third to fourth quarter. With some makers setting aside October to care for this overflow, fourth quarter promises to be unusually active.

Some contract machine shops on the West Coast are complaining that

prime aircraft manufacturers are pulling more subcontracting work into their own shops, leaving the machine shops working at about 60 per cent of capacity. Missile work, however, is increasing rapidly.

The Air Force has ordered a step-up in production of two new supersonic jet fighter planes—the F-101 Voodoo produced by McDonnell Aircraft Corp. and the F-104, built by Lockheed. The Air Force has awarded Curtiss-Wright Corp. contracts involving an investment of \$40,900,000 for J-65 jet engines and the Ford Motor Co. a \$25,700,000 contract for J-57 jet engines.

Cold-drawn bar converters in New England are hampered by delayed shipments of hot-rolled stock. Several mills are booked through the fourth quarter on sheets and are holding off acceptances on hot-rolled bars. With schedules already tangled and at least one month due to be blanked out in the fourth quarter, more producers are booking new tonnage with caution. This has had an adverse effect on cold drawers. Replacement buying is heavier, with deliveries moving out. Most bar supply problems stem from lack of hot-rolled in competition with other products for available semifinished steel. Production of forged and screw machine products is increasing.

## Plates . . .

Plate Prices, Page 106

Plates are becoming so tight with Chicago area mills that some makers consider them in the same stridency bracket as sheets. Every form of plate fabrication is pressing for more tonnage with slim prospects of getting it.

Plate demand is being augmented sharply by swelling freight car requirements. Latest awards in the East include 4000 for the Pennsylvania and 3500 for the Norfolk & Western. In addition, the Pennsylvania is stepping up its repairs from 100 to 175 cars daily.

Shipwork also is more promising, with the Maryland Shipbuilding & Dry Dock Co., Baltimore, apparently low on a Navy cargo ship. Its bids to the Maritime Commission were \$10,218,398 on a fixed price basis, and \$9,685,188 on an adjusted price basis.

The larger of the two mills of the Claymont, Del., plate producer will be down for a few weeks due to a cracked main housing. Operations on the smaller mill, which can handle thicknesses up to 2 in. and a plate up to 6600 lb, are being stepped up for rolling additional tonnage.

The two mills had been on an alternating schedule due to a shortage

**1105...YES, ELEVEN-O-FIVE**

**is the new-strength wire in Roebling's**

*Royal Blue*

WIRE **1105** ROPE

AS SIZES and constructions go, Royal Blue is like the ropes you have used until now...but the likeness ends there.

Royal Blue is made of Roebling's new 1105 wire, the strongest, toughest wire developed up to now for use in any wire rope.

Royal Blue Wire Rope is as enduring as the wire from which it is made.

*Write us for full facts on Royal Blue Wire Rope, or contact your Roebling distributor.*

**ROEBLING**

Subsidiary of The Colorado Fuel  
and Iron Corporation



JOHN A. ROEBLING'S SONS CORPORATION, TRENTON 2, N. J. BRANCHES: ATLANTA, 934 AVON AVE. • BOSTON, 51 SLEEPER ST. • CHICAGO, 5525 W. ROOSEVELT RD. • CINCINNATI, 3253 FREDONIA AVE. • CLEVELAND, 13225 LAKEWOOD HEIGHTS BLVD. • DENVER, 4801 JACKSON ST. • DETROIT, 915 FISHER BLDG. • HOUSTON, 6216 NAVIGATION BLVD. • LOS ANGELES, 5340 E. HARBOR ST. • NEW YORK, 19 RECTOR ST. • ODESSA, TEXAS, 1920 E. 2ND ST. • PHILADELPHIA, 230 VINE ST. • SAN FRANCISCO, 1740 17TH ST. • SEATTLE, 900 1ST AVE. S. • TULSA, 321 N. CHEYENNE ST. • EXPORT SALES OFFICE, 19 RECTOR ST., NEW YORK 6, N. Y.





of ingots. Books of this producer had not been opened for September tonnage when the mill broke down on July 19.

Platemakers generally are booking fourth quarter tonnage, but on a restricted basis due to arrearages. In some cases, a month or more is being blanked out in the fourth quarter. In other instances, the tonnage available for the entire quarter is pared down on a monthly basis.

Railroad demand is bound to take up any slack that may develop from other consuming directions. Right now the roads are disappointed because they cannot obtain steel for their car programs more quickly. They are going ahead on later schedules than they had planned. Ship needs, for new construction and repairs, are gaining momentum.

Pittsburgh district mills report large volume inquiry for freight cars. The producers, however, have difficulty filling requests. Fabricators that order now for the third quarter are being disappointed. One major district producer is accepting no tonnage for shipment prior to October. Other area mills are taking orders for the middle of the fourth quarter, with some as much as five weeks behind schedule on shipments.

Many New England plate fabricators recognized the growing load on the plate mills too late. They are short of heavy sheared plates and are running into increased requirements from larger consumers for the fourth quarter, notably the railroads. Considerable carbuilding volume was placed, contingent on availability of plates in last quarter. The roads got the promise, but some of the promised tonnage will be at the expense of other buyers. Tank plate sizes and grades are not too far extended.

Consolidated Western Steel Division, U. S. Steel Corp., has been awarded 1000 tons of plates and an additional 1000 tons of miscellaneous steel items for the Mayfield dam at Tacoma, Wash.

## Wire . . .

Wire Prices, Pages 108 & 109

Business in manufacturers wire is brisk. Delivery promises range from 10 to 12 weeks in some cases, and 11 to 13 weeks on the annealed and processed items.

Wire rod supply is reported extremely tight.

Deliveries on some merchant wire products range eight to ten weeks, but on bale ties and nails, three-to-four-week delivery is offered.

More fourth quarter volume is being placed in New England, notably grades for automobile and upholstery springs. For the most part,

third quarter open capacity is in fine wire which has overexpanded capacity. Flat tempered steel stock is sold through November and more rod tonnage is being booked for the closing quarter.

The wire mills generally are not falling behind on shipments to the extent experienced in other finished steel products. This is attributed to earlier and continued selective scheduling.

## Tool Steel . . .

Tool Steel Prices, Page 110

Jessop Steel Co., Washington, Pa., increased base prices and extras 5.8 per cent on saw steels used in the lumbering industry on July 22. Extras of less than 5 cents a pound were increased  $\frac{1}{2}$ -cent per pound. For example, the base price on 0.70 per cent nickel saw steel was increased from 29 cents per pound to 30 $\frac{1}{2}$ -cents on circles of 0.090-in. gage and less. Circles of the same grade over 0.090-in. gage were increased from 35 $\frac{1}{2}$  to 37 $\frac{1}{2}$ -cents per pound.

## Revises Export Prices

United States Steel Export Co., New York, has revised its export prices on tight cooperage hoops to 5.18c, cold-finished bars to 6.34c—freight included to New York, Philadelphia, or Baltimore, effective July 22.

## Structural Shapes . . .

Structural Shape Prices, Page 106

Structural shape supply, especially wide flange sections, is the tightest in many months. All producing mills are behind on shipping commitments. Some won't be able to get current before the end of the year, and then only by limiting acceptance of new tonnage.

Fabricators regard steel supply as their No. 1 problem. While orders momentarily are relatively light in the New York market, considerable work is under consideration. In addition to a heavy amount of bridge construction, there is a good diversity of other building, such as schools, apartments, office and commercial structures. Industrial building is on the light side, as has been the case for some time.

Construction firms are using up inventories quickly, and they're having difficulty replenishing supplies. There's much bridge building to be finished this year, and the trend among builders is to close down for two week vacations rather than work at half speed for four weeks.

Fabricating plants in the Pacific

Northwest report their estimators busy figuring many new projects. Competition, however, is extremely keen.

Less tonnage is being estimated for fabrication in New England. The slack stems from a slump in new bridge inquiry, with orders booked for 60,000 tons for the Massachusetts turnpike. A substantial part of this tonnage is plain material, and it will reach fabricating shops at higher prices to meet firm contracts booked when steel prices were lower. Wide flange beams are most extended in deliveries with the mills steadily falling behind schedules. Heavy bookings of sheet and bearing piles have pushed shipments out five months. Larger fabricators are into January on deliveries against new contracts.

## Reinforcing Bars . . .

Reinforcing Bar Prices, Page 106

Producers of reinforcing bars in the Pacific Northwest are operating steadily, with backlogs substantial and new inquiry developing in small lots. Awards last week exceeded 1000 tons. Prospects for the next 90 days are described as excellent, with several important projects still unplaced.

Award of 3450 tons of reinforcing to Steel Fabricators Inc. for Tacoma's Mayfield dam was reported last week, but the project is being delayed by litigation.

## Tubular Goods . . .

Tubular Goods Prices, Page 110


A \$2-million modernization program at its seamless pipe mill in Welland, Ont., will be completed shortly by Page-Hersey Tubes Ltd., Canada's only producer of seamless pipe. When completed, the plant will turn out  $\frac{1}{2}$  to 7-in. seamless tubes. Seamless casing and oil and gas tubing also will supplement its line of resistance welded casing.

The only relatively soft spot in tubular goods sales is in electricweld tubing, Pittsburgh district mills report. But volume is described as fair. Other pipe products are selling well, including specialty tubing. It has been showing rapid improvement following dull demand in the early months of this year.

Jones & Laughlin Steel Corp. reports increasing demand for cold-drawn electricweld tubing with a mirrorlike inside finish. J. & L. adds it is producing tubing with an inside finish superior to many honed surfaces. The tubing is used in hydraulic and pressure cylinders.

The cast iron pipe market continues active with municipal requirements pressing tonnage on the pipe shops. Many projects involving less

# How Detroit Steel gets roll grinding speed and accuracy



The 36" x 16'0 Farrel HD roll grinder above, in operation at the Portsmouth division of Detroit Steel Corporation, has shown its ability to cut roll grinding time substantially. This is true for both heavy roughing and fine finishing.

Rolls are obtained with a perfect surface, free from marks of any kind. Straight, convex or concave contours are ground to exact symmetry and accuracy.

Contributing to grinding accuracy is an automatic crowning device which grinds a mathematically accurate curve. Easily and quickly set, it requires no manipulation dur-

ing operation. The same setting produces exactly the same curvature and permits fixed, uniform and easily controlled accuracy of contour in all rolls.

*You, too, can step up your roll grinding speed and accuracy with a Farrel Heavy Duty machine. Available in six standard sizes. Write for descriptive bulletin.*

## **FARREL-BIRMINGHAM COMPANY, INC.** ANSONIA, CONNECTICUT

Plants: Ansonia and Derby, Conn., Buffalo and Rochester, N. Y.

Sales Offices: Ansonia, Buffalo, New York, Akron, Chicago, Fayetteville (N. C.), Los Angeles, Houston

FB-994

# *Farrel-Birmingham*®

## **FARREL ROLLING MILL MACHINERY**

Rolls • Rolling Mills • Rod Mill Tables and Manipulating Equipment • Universal Mill Spindles • Rod Coilers • Gears • Mill Pinions • Pinion Stands • Gear Drives of Any Capacity • Flexible Couplings • Roll Grinding Machines • Roll Calipers



than 100 tons are included in sizable pending business in the Pacific Northwest. Sales and prospects indicate satisfactory last half volume.

The new pipe and conduit plant of the Canadian Western Pipe Mills Ltd., at Port Moody, near Vancouver, B. C., was formally opened recently, with 800 business, industrial and government leaders from western Europe, the United States and Canada in attendance.

## Warehouse . . .

Warehouse Prices, Page 111

Due to higher warehouse prices (generally effective around the middle of July), business booked by distributors last month established a new dollar record for the year. There wasn't much of a decline from the peak month of June on even a tonnage basis.

Warehouses still are being pressed for tonnage by mill buyers, reflecting the oversold position of producers. All popular sizes are being shipped out as rapidly as received. Plates appear to be the tightest single item, closely followed by shapes and bars.

Although many small fabricators are closing down for vacations, there's no reduction in distributors' bookings. Trade interests expected a midsummer slowdown, especially in view of

heavy consumer buying in the second quarter as protection against a long steel strike, but this has not materialized.

West Coast distributors say the posting of higher prices has not retarded sales. With construction active and general conditions favorable, they foresee continued good business during the balance of this year. Mills on the West Coast are in a position to make deliveries on practically all items in about 45 days.

Price competition in the Los Angeles area is keener, particularly in galvanized sheets. Demand for small diameter pipe is somewhat stronger.

## Iron Ore . . .

Iron Ore Prices, Page 121

Lake Superior iron ore consumption declined slightly in June as compared with May, reports the Lake Superior Iron Ore Association. Use during the month was 7,472,578 tons against 7,797,744 in May. In June, 1954, consumption amounted to only 5,396,131.

The decline in June was due partly to the shorter month. There were fewer active blast furnaces in the period, however, 182 on July 1 against 186 on June 1. On July 1 a year ago active furnaces numbered 131. Twenty-three stacks were idle on

July 1 as against 18 on June 1 and 72 on July 1 a year ago.

Cumulative consumption of ore to July 1 this year totaled 43,108,668 tons. In the first six months of last year, the figure was 34,772,756 tons.

Stocks of iron ore at lower lake docks and furnaces on July 1 amounted to 27,354,868 gross tons. This was an increase, compared with 21,900,527 tons on June 1, but is substantially under the 34,996,184 tons held in stock on July 1, 1954.

Shipments of iron ore on the Great Lakes in the week ended July 25 totaled 3,055,668 gross tons, reports the Lake Superior Iron Ore Association. This compares with movement of 2,350,032 tons in the like week of last year. Shipments for the season (to July 25) total 38,504,354 tons.

## Metallurgical Coke . . .


Metallurgical Coke Prices, Page 121

Foundry coke prices are higher. The advance is expected to become general. At Chicago oven coke is up \$1.25 a net ton, the new Chicago oven price being \$25.75 and the delivered price at that point \$27.25. Other new prices are Indianapolis and Terre Haute (Ind.) ovens, \$25.50; Milwaukee ovens, \$26.25. This is the first increase in coke prices since November, 1952.

## KARDONG CIRCLE BENDER

For Concrete Reinforcing Bars

This is a powerful and fast machine for heavy duty work in both fabricating plants or in the field where large tonnage is required. It will handle as high as 20 tons a day.




Circles of any size required in concrete reinforcing work from 18 inches in diameter up can be bent on this machine. It will bend bars with two or more radii on the same bar without stopping the machine.

Made in two sizes

Model "C" Capacity 1 1/4 inch  
Model "CA" Capacity 1 inch

Write for catalog of our complete line of reinforcing bar benders.

**KARDONG BROTHERS, INC.**  
MINNEAPOLIS 13, MINN.



**COST JUST A FRACTION OF METAL SPACERS**

**THE COLOR TELLS THE THICKNESS**

**ALWAYS RETAINS UNIFORMITY AND EVENNESS UNDER ALL NORMAL CONDITIONS**

*Save Time! Save Money!*

**ARTUS PLASTIC SLITTING MACHINE SHIMS**

**INDUSTRIAL PRODUCTS SUPPLIERS**

201 South Dean Street  
Englewood N. J.

# KEYSTONE

## Better Bar Steel Service


COLD FINISHED STEEL

**CARBON • ALLOY • LEADED**  
**ROUNDS • SQUARES • HEXAGONS • FLAT**

Serving the METAL WORKING INDUSTRY for over a Quarter Century.

Your inquiry will receive prompt attention.

**KEYSTONE DRAWN STEEL CO.**  
**SPRING CITY PENNSYLVANIA**



# Current Ferroalloy Quotations

## MANGANESE ALLOYS

**Electrolytic:** (19-21% Mn, 1-3% Si), Carlot or gross ton \$36, Palmerton, Pa.; \$37 Clairmont and Duquesne, Pa.

**Cast:** (18 to 19% Mn) \$34 per ton, Palmerton, Pa.; \$35 per ton, Clairmont and Duquesne, Pa.

**Standard Ferromanganese:** (Mn 74-76%, C 7% approx.). Base price per net ton \$190, Clairmont, Duquesne, Johnstown and Sheridan, Pa.; Alloy, Va.; Ashtabula, Marietta, Philo, O.; Sheffield, Ala.; Portland, Oreg., and Tacoma, Wash. Add or subtract \$2.00 for each 1% or fraction thereof of contained manganese over 9% or under 74%, respectively.

**Mn 78-81%:** Lump \$193 per net ton, f.o.b. Louisiana or Great Falls, Mont. Add \$2.60 for each 1% above 81%; subtract \$2.60 for each % below 76%, fractions in proportion to nearest 0.1%.

**Low-Carbon Ferromanganese, Regular Grade:** Mn 85-90%, C max. Carload, lump, bulk, max. 7% C, 29.85¢ per lb of contained Mn, carload packed 30.7¢, ton lots 31.8¢, less ton 3¢. Delivered. Deduct 1.5¢ for max 0.15% grade from above prices, 3¢ for max, 0.30%, 3.5¢ for max 0.50% C, and 6.5¢ for max 5% C—max 7% Si. **Special Grade:** (Mn 90% min, C 0.07% max, P 0.06% max). Add 2.05¢ to the above prices. Spot, add 0.25¢.

**Medium-Carbon Ferromanganese:** (Mn 80-85%, C 1.5% max). Carload, lump, bulk 21.35¢ per lb of contained Mn, carload packed 22.1¢, ton lot 23.2¢, less ton 24.4¢. Delivered. Spot, add 0.25¢.

**Manganese Metal:** 2" x D (Mn 95.5% min, Fe 4% max, Si 1% max, C 0.2% max). Carload, lump, bulk, 45¢ per lb of metal; packed, 45.75¢; ton lot 47.25¢; less ton lots 3.25¢. Delivered. Spot, add 2¢.

**Electrolytic Manganese:** Mn carloads, 3¢; 2000 lb to min carloads, 32¢; 250 lb to 999 lb 34¢. Premium for hydrogen-removed metal, 0.75¢ per lb. Prices are f.o.b. cars, Knoxville, Tenn., freight allowed to St. Louis or to any point east of Mississippi; or f.o.b. Marietta, O., freight allowed.

**Silicomanganese:** (Mn 65-85%). Contract, lump, bulk 1.50% C grade, 18-20% Si, 11.00¢ or lb of alloy, carload packed 11.75¢, ton lots 12.85¢, less ton 13.65¢. Freight allowed. For 2% C grade, Si 15-17%, deduct 0.2¢ from above prices. For 3% C grade, Si 12-14.5%, deduct 0.4¢ from above prices. Spot, add 0.25¢.

## TITANIUM ALLOYS

**Ferrotitanium, Low-Carbon:** (Ti 20-25%, Al 5% max, Si 4% max, C 0.10% max). Contract, ton lots 2" x D, \$1.50 per lb of contained Ti; less ton \$1.55. (Ti 35-43%, Al 1% max, Si 4% max, C 0.10% max). Ton lots \$1.35, less ton \$1.37 f.o.b. Niagara Falls, N. Y., freight allowed to St. Louis. Spot, add 5¢.

**Ferrotitanium, High-Carbon:** (Ti 15-18%, C 3-8%). Contract \$177 per ton, f.o.b. Niagara Falls, N. Y., freight allowed to destination east of Mississippi river and north of Baltimore and St. Louis.

**Ferrotitanium, Medium-Carbon:** (Ti 17-21%, C 4.5-5%). Contract \$195 per ton, f.o.b. Niagara Falls, N. Y., freight not exceeding St. Louis rate allowed.

## CHROMIUM ALLOYS

**High-Carbon Ferrochrome:** Contract, c.l., lump, bulk 24.75¢ per lb of contained Cr; carload packed 25.5¢, ton lot 28.5¢, less ton 28.2¢. Delivered. Spot, add 0.25¢.

**Low-Carbon Ferrochrome:** (Cr 67-72%). Contract, carload, lump, bulk, C 0.025% max. Simplex 34.50¢ per lb contained Cr, 0.03% C, 6.50¢, 0.04% C 35.00¢, 0.06% C 34.50¢, 0.10% C 34.00¢, 0.15% C 33.75¢, 0.20% C 33.50¢, 0.50% C 33.25¢, 1% C 33.00¢, 1.50% C 32.85¢, 2% C 32.75¢. Carload packed add 1.1¢, ton lot add 2.2¢, less ton add 3.9¢. Delivered. Spot, add 0.25¢.

**Foundry Ferrochrome, High-Carbon:** (Cr 62-68%, C 5-7%). Contract, c.l. 8 M x D, bulk, 3.25¢ per lb contained Cr. Packed, c.l. 7.15¢, ton 28.50¢, less ton 30.25¢. Delivered. Spot, add 0.25¢.

**Foundry Ferrochrome, Low-Carbon:** (Cr 50-44%, Si 28-32%, C 1.25% max). Contract, carload, packed, 8 M x D, 18.35¢ per lb of alloy, ton lot 19.2¢; less ton lot, 20.4¢, delivered. Spot, add 0.25¢.

**Low-Carbon Ferrochrome Silicon:** (Cr 34-41%, Si 42-49%, C 0.05% max). Contract, carload, lump, 4" x down and 2" x down, bulk, 24.75¢ per lb of contained chromium plus 12¢ per pound of contained silicon; 1" x down, bulk 24.90¢ per pound of contained chromium plus 12.2¢ per pound of contained silicon. F.o.b. plant; freight allowed to destination.

**Chromium Metal:** (Min 97% Cr and 1% Fe). Contract, 1" x D; packed, max 0.50%, carload \$1.16, ton lots \$1.18; less ton \$1.20. Delivered. Spot, add 5¢. Prices on 0.10 per cent carbon grade, add 9¢ to above prices.

## VANADIUM ALLOYS

**Ferrovanadium:** Open-hearth Grade (V 35-55%, Si 8-12% max, C 3-3.5% max). Contract, any quantity, \$3.00 per lb of contained V, Delivered. Spot, add 10¢. **Crucible-Special Grades** (V 50-55%, Si 2-3.5% max, C 0.5-1% max) \$3.10. **Primus and High Speed Grades** (V 50-55%, Si 1.50% max, C 0.20% max) \$3.20.

**Grainal:** Vanadium Grainal No. 1, \$1 per lb; No. 6, 68¢; No. 79, 50¢, freight allowed.

**Vanadium Oxide:** Contract, less carload lots \$1.23 per lb contained V<sub>2</sub>O<sub>5</sub>, freight allowed. Spot, add 5¢.

## SILICON ALLOYS

**25-30% Ferrosilicon:** Contract, carload, lump, bulk, 20.0¢ per lb of contained Si, packed 21.40¢; ton lot 22.50¢ f.o.b. Niagara Falls, freight not exceeding St. Louis rate allowed.

**50% Ferrosilicon:** Contract, carload, lump, bulk, 12¢ per lb of contained Si, carload packed 13.6¢, ton lot 15.5¢, less ton 16.7¢. Delivered. Spot, add 0.45¢.

**Low-Aluminum 50% Ferrosilicon:** (Al 0.40% max). Add 1.7¢ to 50% ferrosilicon prices.

**65% Ferrosilicon:** Contract, carload, lump, bulk, 13.5¢ per pound contained silicon; carload packed 14.85¢; ton lots, 13.05¢; less ton, 17.4¢, delivered. Spot, add 0.35¢.

**75% Ferrosilicon:** Contract, carload, lump, bulk, 14.4¢ per lb of contained Si, carload packed 15.7¢, ton lot 16.85¢, less ton 18.1¢. Delivered. Spot, add 0.3¢.

**90% Ferrosilicon:** Contract, carload, lump, bulk, 17.25¢ per lb of contained Si, carload packed 18.45¢, ton lot 19.4¢, less ton 20.45¢. Delivered. Spot, add 0.25¢.

**Silicon Metal:** (Mn 97% Si and 1% max Fe). C.l. lump, bulk, regular 18.5¢ per lb of Si, c.l. packed 19.7¢, ton lot 20.6¢, less ton 21.6¢. Add 0.5¢ for max 0.10% calcium grade. Deduct 0.5¢ for max 2% Fe grade analyzing min 96% Si. Spot, add 0.25¢.

**Alsilfer:** (Approx. 20% Al, 40% Si, 40% Fe). Contract, basis f.o.b. Niagara Falls, N. Y., lump, carload, bulk, 9.25¢ per lb of alloy, ton lots packed 10.15¢, 200 to 1999 lb 10.50¢, smaller lots 11¢.

## ZIRCONIUM ALLOYS

**12-15% Zirconium Alloy:** (Zr 12-15%, Si 30-43%, Fe 40-45%, C 0.20% max). Contract, c.l. lump, bulk 8.0¢ per lb of alloy, c.l. packed 8.75¢, ton lot 9.5¢, less ton 10.35¢. Delivered. Spot, add 0.25¢.

**35-40% Zirconium Alloy:** (Zr 35-40%, Si 47-52%, Fe 8-12%, C 0.50% max). Contract, carload, lump, packed 25.25¢ per lb of alloy, ton lot 26¢, less ton 27.25¢. Freight allowed. Spot, add 0.25¢.

## BORON ALLOYS

**Ferroboron:** (B 17.50% min, Si 1.50% max, Al 0.50% max, C 0.50% max). Contract, 100 lb or more 1" x D, \$1.20 per lb of alloy. Less than 100 lb \$1.30. Delivered, spot add 5¢. F.o.b. Washington, Pa., prices, 100 lb and over, are as follows: Grade A (10-14% B) 85¢ per pound; Grade B (14-18% B) \$1.20; Grade C (19% min B) \$1.50.

**Borasil:** (3 to 4% B, 40 to 45% Si). \$5.25 per lb contained B, delivered to destination.

**Bortam:** (B 1.5%-1.9%). Ton lots, 45¢ per lb; smaller lots, 50¢ per lb.

**Carbortam:** (B 1 to 2%). Contract, lump, carloads 9.50¢ per lb f.o.b. Suspension Bridge, N. Y., freight allowed same as high-carbon ferrotitanium.

## CALCIUM ALLOYS

**Calcium-Manganese-Silicon:** (Ca 16-20%, Mn 14-18% and Si 53-59%). Contract, carload, lump, bulk 20.0¢ per lb of alloy, carload packed 20.8¢, ton lot 22.3¢, less ton 23.3¢. Delivered. Spot, add 0.25¢.

**Calcium-Silicon:** (Ca 30-33%, Si 60-65%, Fe 1.50-3%). Contract, carload, bulk 19.0¢ per lb of alloy, carload packed 20.2¢, ton lot 22.1¢, less ton 23.6¢. Deld. Spot, add 0.25¢.

## BRICQUETTED ALLOYS

**Chromium Briquets:** (Weighing approx. 3½ lb each and containing exactly 2 lb of Cr). Contract, carload, bulk, 16.05¢ per lb of briquet, carload packed 16.95¢, ton lot 17.75¢, less ton 18.65¢. Deld. Add 0.25¢ for notching. Spot, add 0.25¢.

**Ferromanganese Briquets:** (Weighing approx. 3 lb and containing exactly 2 lb of Mn). Contract, carload, bulk 11.85¢ per lb of briquet, c.l. packaged 12.85¢, ton lot 13.65¢, less ton 14.55¢. Delivered. Add 0.25¢ for notching. Spot, add 0.25¢.

**Silicomanganese Briquets:** (Weighing approx. 3½ lb and containing exactly 2 lb of Mn and approx. ¼ lb of Si). Contract, c.l. bulk 12.45¢ per lb of briquet, c.l. packaged 13.45¢, ton lot 14.25¢, less ton 15.15¢. Delivered. Add 0.25¢ for notching. Spot, add 0.25¢.

**Silicon Briquets:** (Large size—weighing approx. 5 lb and containing exactly 2 lb of Si). Contract, carload, bulk 6.55¢ per lb of briquet. Packed c.l. 7.55¢, ton lot 8.35¢, less ton 9.25¢. Delivered. Spot, add 0.25¢.

(Small size—weighing approx. 2½ lb and containing exactly 1 lb of Si). Carload, bulk 6.7¢. Packaged c.l. 7.7¢, ton lot 8.5¢, less ton 9.4¢. Delivered. Add 0.25¢ for notching, small size only. Spot, add 0.25¢.

**Molybdenum-Oxide Briquets:** (Containing 2½ lb of Mo each) \$1.14 per pound of Mo contained, f.o.b. Langeloth, Pa.

## TUNGSTEN ALLOYS

**Ferrotungsten:** (70-80%), 5000 lb W or more \$3.80 per lb of contained W; 2000 lb W to 5000 lb W, \$3.90; less than 2000 lb W, \$4.02, f.o.b. Niagara Falls, N. Y.

## OTHER FERROALLOYS

**Ferrocolumbium:** (Cb 56-60%, Si 8% max, C 0.4% max). Contract, ton lot, 2" x D, \$6.80-\$6.90 per lb of contained Cb. Delivered. Spot, add 10¢.

**Ferrotantalum—Columbium:** (Cb 40% approx., Ta 20% approx., and Cb plus Ta 60% min, C 0.20% max.) Ton lots, 2" x D, \$4.65 per lb of contained Cb plus Ta, deld.; less ton lots \$4.70.

**Silicaz Alloy:** (Si 35-40%, Ca 9-11%, Al 6-8%, Zr 3-5%, Ti 9-11%, B 0.55-0.75%). Carloads packed 1" x D, 45¢ per lb of alloy, ton lot 47¢, less ton 49¢. Delivered.

**SMZ Alloy:** (Si 60-65%, Mn 5.7%, Zr 5-7%, Fe 20% approx.). Contract, carload, packed, ½" x 12 M, 17.5¢ per lb of alloy, ton lots 18.25¢, less ton 19.5¢. Deld. Spot, add 0.25¢.

**Graphidox No. 4:** (Si 48-52%, Ca 5-7%, Ti 9-11%). C.l. packed, 17.50¢ per lb of alloy, ton lots 18.50¢; less ton lots 20¢, f.o.b. Niagara Falls, N. Y.; freight allowed to St. Louis.

**V-3 Foundry Alloy:** (Cr 38-42%, Si 17-19%, Mn 8-11%). C.l. packed 16.6¢ per lb of alloy; ton lots 18.10¢; less ton lots 19.35¢, f.o.b. Niagara Falls; freight allowed to St. Louis.

**Siminal:** (Approx. 20% each Si, Mn, Al; bal. Fe). Lump, carload, bulk 15.50¢. Packed c.l. 16.50¢, 2000 lb to c.l. 16.75¢, less than 2000 lb 17.25¢ per lb of alloy. Delivered.

**Ferrophosphorus:** (23-25% based on 24% P content with unitage of \$4 for each 1% of P above or below the base); carloads, f.o.b. sellers' works, Mt. Pleasant, Siglo, Tenn. \$90 per gross ton.

**Ferromolybdenum:** (55-75%). Per lb contained Mo, in 200-lb containers, f.o.b. Langeloth, Pa., \$1.46 in all sizes except powdered which is \$1.57; Washington, Pa., furnace, any quantity \$1.46.

**Technical Molybdenum-Oxide:** Per lb contained Mo, f.o.b. Langeloth, Pa., \$1.23 in cans; in bags, \$1.24, f.o.b. Langeloth, Pa.; Washington, Pa., \$1.24.





## How Pittsburgh Red Center Construction Provides

**Faster cutting while maintaining  
smooth finish • Freedom from shedding  
• Perfect balance • Longer life**

In conventional brushes, when faster cutting action is desired, coarser wire is used. But increasing the wire gauge causes brittleness, destroying the wearing quality of the brush, and resulting in excessive scoring of the work.

Pittsburgh has solved this problem by maintaining the same ideal gauge wire in every brush, but increasing the fill and diameter of the hub and center plate of brushes designed for faster cutting. Thus, although cutting speed is increased, work remains unscored and the wire does not lose its inherent power to flex. These Red Center brushes last longer, maintain perfect balance throughout life, and do a better job all around.

This is just one example of superior Pittsburgh construction, engineered for both general and specific applications. For details of the complete line, write for free Catalog #54-W. Address: PITTSBURGH PLATE GLASS CO., *Brush Div.*, Dept. O-8, 3221 Frederick Ave., Baltimore 29, Maryland.

### PITTSBURGH



**Power Driven  
BRUSHES**

BRUSHES • PAINTS • GLASS • CHEMICALS • PLASTICS • FIBER GLASS

**PITTSBURGH PLATE GLASS COMPANY**

IN CANADA: CANADIAN PITTSBURGH INDUSTRIES LIMITED

# STRONGER STIFFER LIGHTER

Pattern 1RF Shown

## RIGID-tex

**the Design-Strengthened Metal  
40 Designs, More New Ones Coming**

See SWEETS Design File 1a/Ri or write us for more information.



**RIGIDIZED METALS  
CORPORATION**

6848 OHIO STREET • BUFFALO 3, N. Y.  
Sales Representatives in Principal Cities

### ABC OF IRON AND STEEL

*Fifth Edition, 440 pages, Illustrated*

**\$10.00**


POSTPAID

This book brings together the combined knowledge and experience of 31 outstanding authorities and takes one step by step through steelmaking. Representing years and years of constant work and study, "ABC" is the result of actual first-hand experience. It is written in simple, non-technical language, and hundreds of photographs of operations and equipment are included. The Penton Publishing Co., Book Department, 1213 W. 3rd St., Cleveland 13, O.

# COWLES

**GANG SLITTING KNIVES**

**OVER 30 YEARS EXPERIENCE**



**Standard for Service  
and Durability.  
Ground to extremely  
close Tolerances and  
Finish. Made by  
Toolmakers.**

**COWLES  
TOOL COMPANY**

2086 W. 110th ST. CLEVELAND 2, OHIO



## Ores

### Lake Superior Iron Ore

(Prices effective for the 1955 shipping season, gross ton, 51.50% iron natural, rail of vessel, lower lake ports)

Old range bessemer	10.40
Old range nonbessemer	10.25
Mesabi bessemer	10.25
Mesabi nonbessemer	10.10
Open-hearth lump	11.25
High phosphorus	10.00

### Eastern Local Iron Ore

Cents per unit, deld. E. Pa.  
Foundry and basic 52-62% concentrates contract

	17.00-18.00
--	-------------

### Foreign Iron Ore

Cents per unit, c.i.f. Atlantic ports

Swedish basic, 60-68%	20.00
N. African hematite (spot)	18.00-20.00
Brazilian iron ore, 63-69% (spot)	24.00-26.00

### Tungsten Ore

Net ton unit, before duty  
Foreign, wolframite, good commercial quality

	\$31.50-\$32.00
Domestic, scheelite, mine	63.00

### Manganese Ore

Mn 48%, nearby, 85c-87c per long ton unit, c.i.f. U. S. ports, duty for buyer's account; 46-47%, 75c-80c.

### Chromite Ore

Gross ton, f.o.b. cars New York, Philadelphia, Baltimore, Charleston, S. C., plus ocean freight differential for delivery to Portland, Oreg., Tacoma, Wash.

Indian and African

48% 2.8:1	nom. \$40.00-\$52.00
48% 3:1	42.00-44.00
48% no ratio	32.00-34.00

### South African Transvaal

44% no ratio \$19.00-\$20.00  
48% no ratio 31.00-32.00

### Domestic

Rail nearest seller  
18% 3:1 \$39.00

### Molybdenum

Sulphide concentrate, per lb of Mo content, mines, unpacked \$1.00

### Antimony Ore

Per unit of Sb content, c.i.f. seaboard  
56-60% \$3.50-\$3.80  
60-65% 3.80-4.25

### Vanadium Ore

Cents per lb V<sub>2</sub>O<sub>5</sub> content, deld. mills  
Domestic 31.00

## Refractories

### Fire Clay Brick (per 1000)

High-Heat Duty: Pueblo, Colo., \$94; Ashland, Grain, Hayward, Hinchins, Haldeman, Olive Hill, Ky., Athens, Troup, Tex., Beech Creek, Clearfield, Curwensville, Look Haven, Lunenburg, Oristown, West Decatur, Pa., Bessemer, Ala., Farber, Mexico, St. Louis, Vandalia, Mo., Ironton, Oak Hill, Parral, Portsmouth, O., Ottawa, Ill., Stevens Pottery, Ga., \$114; Salina, Pa., \$119; Niles, O., \$125; Los Angeles, Pittsburg, Calif., \$137.20.

### Silica Brick (per 1000)

Standard: Alexandria, Claysburg, Mt. Union, Sproul, Pa., Ensley, Ala., Portsmouth, O., \$120; Warren, Niles, O., Hays, Pa., \$125; Morrisville, Pa., \$123.50; E. Chicago, Ind., Joliet, Rockdale, Ill., \$130; Cutler, Utah, \$121.55; Los Angeles, \$127.85.  
Super Duty: Hays, Sproul, Pa., Warren, Windham, O., Athens, Tex., \$137; Morrisville, Pa., Niles, O., \$140; Joliet, Ill., \$143.

### Semisilica Brick (per 1000)

Clearfield, Pa., \$130; Philadelphia, \$116; Woodbridge, N. J., \$122.

### Insulating Fire Brick (per 1000)

2300° F: Massillon, O., \$178.50; Clearfield, Pa., \$213; Augusta, Ga., Beaver Falls, Pa., Zenopolis, Pa., Mexico, Mo., \$206; Vandalia, Mo., \$214.10; Portsmouth, O., \$207.50; Bessemer, Ala., \$212.80.

### Ladle Brick (per 1000)

Dry Pressed: Bessemer, Ala., \$64.60; Alsey, Ill., Chester, New Cumberland, W. Va., Freeport, Johnstown, Merrill Station, Pa., Mexico, Mo., \$77.50; Wellsville, O., \$81.50; Clearfield, Pa., Portsmouth, O., \$87; Peña, Ark., \$109; Los Angeles, \$110.25; Pittsburg, Calif., \$111.30.

### High-Alumina Brick (per 1000)

50 Per Cent: Clearfield, Pa., St. Louis, Mexico, Mo., \$181; Danville, Ill., \$169.30.  
60 Per Cent: St. Louis, Mexico, Vandalia, Mo., Clearfield, Pa., \$225; Danville, Ill., \$213.20.  
70 Per Cent: St. Louis, Mexico, Vandalia, Mo., \$260; Danville, Ill., \$258; Clearfield, Pa., \$267.

### Sleeves (per 1000)

Reesdale, Johnstown, Bridgeburg, Pa., \$147; Clearfield, Pa., \$148.50; St. Louis, \$159.30; Athens, Tex., \$155.

### Nozzles (per 1000)

Reesdale, Pa., \$234.70; Johnstown, Pa., \$240.70; Clearfield, Pa., \$241.40; St. Louis, \$259.45; Athens, Tex., \$247.70; Bridgeburg, Pa., \$267.50.

### Runners (per 1000)

Reesdale, Johnstown, Bridgeburg, Pa., \$183.50; Clearfield, Pa., \$185.50; St. Louis, \$195.80; Athens, Tex., \$191.80.

### Dolomite (per net-ton)

Domestic, dead-burned, bulk, Billmeyer, Blue Bell, Williams, Plymouth Meeting, York, Pa., Millville, W. Va., Bettsville, Millersville, Martin, Woodville, O., \$14.50; Gibsonburg, Nario, O., \$15; Thornton, McCook, Ill., \$15.10; Dolly Siding, Bonne Terre, Mo., \$13.65.

### Magnesite (per net ton)

Domestic, dead-burned, bulk, ¾-in. grains with fines: Chewelah, Wash., \$38; Luning, Nev., \$40.

## Metallurgical Coke

### Price per net ton

#### Beehive Ovens

Connellsville, furnace \$13.50-\$14.00  
Connellsville, foundry 16.50-17.00

#### Oven Foundry Coke

Kearny, N. J., ovens \$24.50  
Camden, N. J., ovens 24.00  
Everett, Mass., ovens \$26.05  
New England, deld. 25.75  
Chicago, ovens 27.25  
Chicago, deld. 25.50  
Terre Haute, Ind., ovens 26.25  
Milwaukee, ovens 25.50  
Indianapolis, ovens 27.10  
Cincinnati, deld. 25.50  
Painesville, O., ovens 27.43  
Cleveland, deld. 25.00  
Erie, Pa., ovens 22.65  
Birmingham, ovens 27.58  
Cincinnati, deld. 25.00  
Buffalo, ovens 26.25  
Buffalo, deld. 18.50  
Lone Star, Tex., ovens 24.00  
Philadelphia, ovens 24.00  
Sweden, Pa., ovens 26.00  
St. Louis, deld. 24.25  
St. Paul, ovens 24.00  
Portsmouth, O., ovens 26.62  
Cincinnati, O., deld. 25.50  
Detroit, ovens 26.50  
Detroit, deld. 27.06  
Pontiac, deld. 28.58  
Saginaw, deld. 28.58

\*Or within \$4.55 freight zone from works.

## Coal Chemicals

### Spot, cents per gallon, ovens

Pure benzol 36.00  
Toluol, one deg. 32.00-35.00  
Industrial xylol 32.00-35.00  
Per ton, bulk, ovens \$42-\$45  
Ammonium sulphate Birmingham area 42.00†

†With port equalization against imports.

Cents per pound, producing point  
Phenol, 40 deg. (U.S.P.), tank cars 18.00  
c.l. drums 19.00  
l.c.l. drums 19.50

## Fluorspar

Metallurgical grades, f.o.b. shipping point, in Ill., Ky., net tons, carloads, effective CaF<sub>2</sub> content 72.5%, \$35-\$36; 70%, \$32-\$33; 60%, \$28-\$29. Imported, net tons, duty paid, metallurgical grade: European, \$28-\$30; Mexican, \$25.50.

## Electrodes

Threaded with nipple, unboxed, f.o.b. plant

GRAPHITE		Per
Inches	Length	100 lb
Diam	24	\$47.75
2	30	30.75
2½	40	30.00
4	40	23.50
4	40	28.25
5½	60	25.50
6	60	25.25
7	60	22.75
8, 9, 10	60	26.00
12	72	22.50
14	60	21.50
16	72	22.00
17	60	21.50
18	72	21.50
20	72	21.25

### CARBON

8	60	11.40
14, 12, 10	60	11.10
14	72	10.25
17	60	10.25
17	72	9.85
20	84	9.85
24	92	9.85
24	72, 84	9.85
24	96	9.60
30	84	9.75
40, 35	110	9.50
40	100	9.50

TOOL WEAR...-75%  
MACHINING SPEED...+100%  
ON THIS GRAY IRON RING



...thanks to

**FERROCARBO®**

Users everywhere report similar experiences. In fact, on 67 machining tests in 11 large machine shops, castings of gray iron treated with FERROCARBO averaged 89.5% greater machinability per tool than untreated castings. These premium castings are finer-grained, denser, stronger, yet they COST YOU NO MORE...because your foundryman, using FERROCARBO, makes worthwhile savings in raw material costs.

FOR FREE BOOKLET on FERROCARBO, citing actual case histories of faster machining, with longer tool life, write The Carborundum Company, Dept. 53, Niagara Falls, N. Y. 64-53

**CARBORUNDUM®**

**LEWIS**  
**TRAVEL-CUT**  
(TRADEMARK)

automatic, high-speed  
heavy-duty

**WIRE STRAIGHTENING**  
and

**CUTTING MACHINES**

Sizes for .012" to ¾" WIRE  
ROUNDS & SHAPES

**THE LEWIS MACHINE CO.**

3450 E. 76 ST., CLEVELAND, O.



*Certified*

*Metal*

*Abrasives*

FOR USE IN BLAST CLEANING EQUIPMENT

**SAMSON SHOT**  
**ANGULAR GRIT**

PITTSBURGH CRUSHED STEEL CO., PITTSBURGH, PA.  
STEEL SHOT & GRIT CO., BOSTON, MASSACHUSETTS



**unlimited design  
freedom...plus  
vastly reduced  
costs**



## Save as much as 67% with intricate Arwood Investment Cast Parts

It is now possible, with the Arwood investment casting process, to economically produce shapes impractical to obtain by conventional methods. Often, many assemblies can be combined into a single casting, using unmachinable alloys. Applications are virtually unlimited.

Our engineers will be pleased to go over your parts problems with you and help cut your own costs. Why not submit parts or prints to us for quotations? Consultation is free of obligation, of course.

Write for free literature describing the investment casting process.

### CASE STUDY

**DESIGNATION:** Aircraft emergency door latch.

**METAL:** Stainless steel 410 (AMS 5350).

**PARTS:** Designed and cast as a single unit.

**QUALITY CONTROL:** Produced under X-ray control. Chemical and physical affidavits furnished. Test bars submitted.

**ADVANTAGES:** Investment casting, by eliminating all finishing operations except reaming of cast hole through pivot boss, reduced cost from over \$10.00 each to approximately \$3.50 each.


# ARWOOD

**PRECISION CASTING CORP.**

66 WASHINGTON STREET • BROOKLYN 1, N. Y.

PLANTS: Brooklyn, N. Y. • Groton, Conn. • Tilton, N. H. • Los Angeles, Calif.

# POOLE



A COPY OF CATALOG GIVING FULL DESCRIPTION AND ENGINEERING DATA SENT UPON REQUEST.


## FLEXIBLE COUPLINGS

POOLE FOUNDRY & MACHINE COMPANY

WOODBERRY, BALTIMORE, MD.



**famous** for accuracy and  
straightness of threads, low chaser costs,  
less downtime, more pieces per day.



THE EASTERN MACHINE SCREW CORP., 22-42 Barclay Street, New Haven, Conn.  
Pacific Coast Representative: A. C. Berbringer, Inc., 334 N. San Pedro St., Los Angeles, California. Canada: F. F. Barber Machinery Co., Toronto, Canada.



*To Lower  
your Overhead.*

**BROWNING ELECTRIC  
TRAVELING CRANES AND HOISTS**  
up to 125-TON CAPACITY

**VICTOR R. BROWNING & CO., INC.** WILLOUGHBY (Cleveland), OHIO

## INTRODUCTION TO THE STUDY OF HEAT TREATMENT OF METALLURGICAL PRODUCTS

By Albert Portevin

Fundamental knowledge and essential principles of heat treatment of steel are presented in simple and understandable manner. Research engineers, metallurgical students and steel plant metallurgists engaged in metallurgical investigations and the heat treatment of ferrous and non-ferrous metals will find this book of inestimable value.

246 pages  
69 illustrations

4 tables  
Price \$5.00 Postpaid

**THE PENTON PUBLISHING CO.**

Book Department, 1213 W. 3rd St., Cleveland 13, O.



## Scrap . . .

Scrap Prices, Page 124

**Philadelphia**—Further increases are noted in steel scrap. No. 1 heavy melting, No. 1 bundles and No. 1 busheling are holding at \$43, delivered; No. 2 heavy melting, regarded as the most scarce of all steel grades, is moving at \$38, delivered. No. 2 bundles have advanced to \$34-\$35, delivered; electric furnace bundles, to \$44.

Recent advances haven't greatly stimulated the intake at dealers' yards. This, combined with brisk trading, is keeping yard stocks of steel scrap at a minimum. Foreign inquiry is less pressing than a few weeks ago, but it is still a factor in keeping supply at low ebb.

**New York**—Scrap brokers have advanced buying prices on some of the major steel grades \$1 to \$1.50 a ton. They are offering \$37.50-\$38 for No. 1 heavy melting and No. 1 bundles and \$33-\$34 for No. 2 heavy melting. Borings and turnings, low phos and the cast grades are unchanged. Domestic consumers are active in the market, but foreign demand is off from what it was a few weeks ago.

**Boston**—The higher price for No. 1 heavy melting steel and bundles has

pulled up No. 2 steel by \$2.50 per ton and narrowed the differentials between the grades. No. 2 bundles, while 50 cents higher lags in the advance. Lighter industrial steel scrap advances are 50 cents to \$2. The higher prices on steel scrap are not duplicated in the cast grades. Volume of the latter moving is light, with prices barely holding.

**Pittsburgh**—Trade sources say if mills entered the market now with large-scale orders, they would have to pay between \$42 and \$45 a ton to attract sizable amounts of No. 1 heavy melting scrap. Last orders were placed at \$40 a ton. Brokers are paying \$42 a ton; good scrap is scarce at that price.

Other grades of scrap, notably punchings and plate scrap, heavy turnings, electric furnace bundles and cut structurals, are showing greater strength, too. Cast iron grades average \$1 a ton above last week.

**Cleveland**—Largely reflecting broker covering, the scrap market here continues to boil. Despite the absence of representative mill purchases of the steelmaking grades, dealers are marking their prices up \$1 per ton in anticipation of a strong demand through the remainder of the year. The cast iron grades also are higher on improving foundry demand.

**Buffalo**—Although local scrap prices are unchanged, stronger tendencies prevail, with indications higher prices are in the offing. Dealers are finding it difficult to get material to meet shipments against old orders. New out-district buying is anticipated.

**Chicago**—The scrap market here continues to boil. Shortage of good material may be at the bottom of the situation, but if so, the fact isn't fully evident. Nor does the shortage of blast furnace hot metal seem a logical explanation for this district, with 40 of 43 blast furnaces operating. About the only certainty in the situation is that a good many brokers are obliged to fill old orders with high-priced material.

**Detroit**—The scrap market continues strong in this area, with most brokers and dealers short on their orders. No. 1 heavy melting is quoted at \$34; No. 2 heavy melting, \$24; No. 1 bundles, \$35; No. 2 bundles, \$24; No. 1 busheling, \$34; short shovel turnings, \$20; punchings and plate scrap, \$42.

**Birmingham**—Scrap prices have finally started upward in this district, advancing from \$1 to \$3 on most items, with a jump of \$6 per ton on No. 2 bundles. Brokers predict still higher prices in view of export quotations at some South Atlantic and

QUANTITY  
PRODUCTION  
OF  
GREY IRON  
CASTINGS

ONE OF THE  
NATION'S LARGEST  
AND MOST MODERN  
PRODUCTION  
FOUNDRIES

ESTABLISHED 1866  
**THE WHELAND  
COMPANY**  
CHATTANOOGA 2, TENN.

## SAVE ON RAILS



### BUY "GUARANTEED RELAYERS"

Handle more cars better—spend less to install & maintain with Foster Relayers. "Open-stock" shipments, all sections 12# thru 175#. Switch Materials, Track items.

**LE FOSTER CO.**

PITTSBURGH 30    NEW YORK 7  
CHICAGO 4    HOUSTON 2    LOS ANGELES 5

"NONE BETTER"

**FOR PERFECT SOLDERING  
IN LESS TIME**

Use Rubylfluid soldering flux. Fast acting . . . easy to use . . . wets out freely . . . insures strong unions. Ask your jobber or write for special \$1.00 offer.

**RUBY CHEMICAL CO.**  
75 S. McDowell St.  
Columbus 8, Ohio

Rubylfluid

WARD  
STEEL  
CO.

We specialize in  
**FINISHED STEEL  
BARS—TUBES—STRIP**

**PROMPT WAREHOUSE  
SERVICE ONLY**

Most Complete Stock in  
America of  
**BLUE TEMPERED  
SPRING STEEL**

We believe that the way to sell is to carry a stock which permits satisfying any reasonable warehouse demand.

87A Rindge Ave. Ext. Phone UN 4-2460  
**CAMBRIDGE 40, MASS.**

Branches:  
3042-3058 W. 51st Street, CHICAGO, ILL.  
Phone: Grove Hill 6-2600  
Fenner Street, Providence, R. I.  
Phone: Gospee 1-5573, 1-8573



# Iron and Steel Scrap

Consumer prices, per gross ton.  
STEEL. Changes shown in italics.

except as otherwise noted, including broker's commission, as reported to

## STEELMAKING SCRAP COMPOSITE

July 27 .....	\$42.00
July 20 .....	40.17
June Avg. ....	35.44
July 1954 .....	27.42
July 1950 .....	37.04

Based on No. 1 heavy melting grade at Pittsburgh, Chicago and eastern Pennsylvania.

## YOUNGSTOWN

(Delivered consumer's plant)	
No. 1 heavy melting....	41.00-42.00
No. 2 heavy melting....	35.00-36.00
No. 1 bundles .....	41.00-42.00
No. 2 bundles .....	32.00-33.00
No. 1 busheling .....	41.00-42.00
Machine shop turnings..	24.00-25.00
Short shovel turnings..	29.00-30.00
Cast iron borings .....	29.00-30.00
Low phos. ....	44.00-45.00
Electric furnace bundles.	44.00-45.00
Railroad Scrap	
No. 1 R.R. heavy melt..	44.00-45.00

## CHICAGO

No. 1 heavy melting....	40.00-42.00
No. 2 heavy melting....	33.00-34.00
No. 1 factory bundles..	42.00-43.00
No. 1 dealer bundles..	37.00-38.00
No. 2 bundles .....	31.00-32.00
No. 1 busheling .....	40.00-42.00
Machine shop turnings..	25.00-26.00
Mixed borings, turnings.	27.00-28.00
Short shovel turnings..	27.00-28.00
Cast iron borings .....	27.00-28.00
Cut structural, 3 ft .....	43.00-44.00
Punchings & plate scrap.	44.00-45.00
Electric furnace bundles.	42.00-43.00

Cast Iron Grades	
No. 1 cupola .....	45.00-46.00
Stove plate .....	35.00-37.00
Unstripped motor blocks	32.00-33.00
Clean auto cast .....	49.00-50.00
Drop broken machinery	49.00-50.00

Railroad Scrap	
No. 1 R.R. heavy melt..	45.00-46.00
R.R. malleable .....	49.00-50.00
Rails, 2 ft and under..	54.00-55.00
Rails, 18 in. and under	55.00-56.00
Angles, splice bars .....	49.00-50.00
Rails, rerolling .....	61.00-62.00

Stainless Steel Scrap	
18-8 bundles & solids.	255.00-265.00
18-8 turnings .....	130.00-140.00
430 bundles & solids..	100.00-105.00
430 turnings .....	45.00-50.00

Chicago Mercantile Exchange	
(Week ended July 27)	
	High Low Close
No. 1 Heavy Melting	High Low Close
Oct. ....	39.00 39.00 39.00
Jan. ....	

Sales (160-ton units): 1 October.  
\*Nominal.

## DETROIT

(Brokers' buying prices; f.o.b. shipping point)	
No. 1 heavy melting....	34.00
No. 2 heavy melting....	24.00
No. 1 bundles .....	35.00
No. 2 bundles .....	24.00
No. 1 busheling .....	34.00
Machine shop turnings..	16.00
Mixed borings, turnings	16.00
Short shovel turnings..	20.00
Punchings & plate scrap.	42.00

Cast Iron Grades	
Charging box cast ....	32.00
No. 1 cupola .....	39.00
Stove plate .....	32.00
Heavy breakable cast..	32.00
Unstripped motor blocks	22.00
Clean auto cast .....	42.00
Malleable .....	35.00

## BIRMINGHAM

No. 1 heavy melting....	32.00-33.00
No. 2 heavy melting....	28.00-29.00
No. 1 bundles .....	31.00-32.00
No. 2 bundles .....	23.00-24.00
No. 1 busheling .....	32.00-33.00
Cast iron borings .....	15.00-16.00
Short shovel turnings..	24.00-25.00
Machine shop turnings..	18.00-19.00
Electric furnace bundles	32.00-33.00

Cast Iron Grades	
(F.o.b. shipping point)	
No. 1 cupola .....	45.00-46.00
Stove plate .....	42.00-43.00
Bar crops and plate ..	36.00-37.00
Structural plate, 2 ft ..	36.00-37.00
Unstripped motor blocks	35.50-36.50

Railroad Scrap	
No. 1 R.R. heavy melt..	35.00-36.00
Rails, 2 ft and under..	44.00-45.00
Rails, 18 in. and under	45.00-46.00
Rails, rerolling .....	43.00-44.00
Rails, random lengths..	40.00-41.00
Angles, splice bars .....	43.00-44.00
Std. steel axles .....	35.00-36.00

## PHILADELPHIA

(Delivered consumer's plant)	
No. 1 heavy melting....	43.00
No. 2 heavy melting....	38.00
No. 1 bundles .....	43.00
No. 2 bundles .....	34.00-35.00
No. 1 busheling .....	43.00
Electric furnace bundles.	44.00
Machine shop turnings..	26.00
Mixed borings, turnings.	26.00
Short shovel turnings..	29.00
Structurals & plate ....	45.00-46.00
Heavy turnings .....	39.00
Couplers, springs .....	
wheels .....	45.00-46.00
Rail crops, 2 ft under..	52.00-53.00

Cast Iron Grades	
No. 1 cupola .....	36.00
Malleable .....	46.00
Heavy breakable cast..	43.00
Drop broken machinery	45.00

## NEW YORK

(Brokers' buying prices)	
No. 1 heavy melting....	37.50-38.00
No. 2 heavy melting....	33.00-34.00
No. 1 bundles .....	37.50-38.00
No. 2 bundles .....	25.00-26.00
Machine shop turnings..	16.00-17.00
Mixed borings, short	
turnings .....	17.00-18.00
Short shovel turnings..	18.00-19.00
Low phos. (structural & plate)	38.00-39.00

Cast Iron Grades	
No. 1 cupola .....	32.00-33.00
Unstripped motor blocks	22.00-23.00
Heavy breakable .....	35.00-36.00

Stainless Steel	
18-8 sheets, clips, solids .....	245.00-250.00
18-8 borings, turnings..	120.00-125.00
430 sheets, clips, solids	105.00-110.00
410 sheets, clips, solids	85.00-90.00

## BOSTON

(Brokers' buying prices; f.o.b. shipping point)	
No. 1 heavy melting....	32.00-33.00
No. 2 heavy melting....	26.00-26.50
No. 1 bundles .....	32.00-33.00
No. 2 bundles .....	23.00-23.50
Machine shop turnings..	15.00-15.50
Mixed borings, turnings	15.50-16.00
Short shovel turnings..	17.50-18.00
No. 1 cast .....	30.00-31.00
Mixed cupola cast .....	28.00-29.00
No. 1 machinery cast ..	33.00-34.00

## BUFFALO

No. 1 heavy melting....	34.00-35.00
No. 2 heavy melting....	29.00-30.00
No. 1 bundles .....	34.00-35.00
No. 2 bundles .....	26.00-27.00
No. 1 busheling .....	34.00-35.00
Mixed borings, turnings	23.00-24.00
Machine shop turnings..	21.00-22.00
Short shovel turnings..	24.00-25.00
Cast iron borings .....	23.00-24.00
Low phos. ....	37.00-38.00

Cast Iron Grades	
(F.o.b. shipping point)	
No. 1 cupola .....	37.00-38.00
No. 1 machinery .....	42.00-43.00

Railroad Scrap	
Rails, random lengths ..	39.00-40.00
Rails, 2 ft and under ..	44.00-45.00
Railroad specialties ..	39.00-40.00

## CINCINNATI

(Brokers' buying prices; f.o.b. shipping point)	
No. 1 heavy melting....	37.50-38.50
No. 2 heavy melting....	32.50-33.50
No. 1 bundles .....	37.50-38.50
No. 2 bundles .....	28.50-29.50
No. 1 busheling .....	37.50-38.50
Machine shop turnings..	20.00-21.00
Mixed borings, turnings	19.50-20.50
Short shovel turnings..	24.00-25.00
Cast iron borings .....	21.00-22.00
Low phos., 18 in. ....	42.00-43.00

Cast Iron Grades	
No. 1 cupola .....	44.00-45.00
Heavy breakable cast..	38.00-39.00
Charging box cast .....	36.00-37.00
Drop broken machinery	48.00-49.00

Railroad Scrap	
No. 1 R.R. heavy melt..	40.00†
Rails, 18 in. and under	51.00-52.00
Rails, random lengths..	44.00-45.00

†Nominal

## ST. LOUIS

(Brokers' buying prices)	
No. 1 heavy melting....	32.00
No. 2 heavy melting....	30.00
No. 1 bundles .....	32.00
No. 2 bundles .....	25.50
Machine shop turnings..	18.00
Short shovel turnings..	20.00

Cast Iron Grades	
No. 1 cupola .....	41.00
Charging box cast ....	35.00
Heavy breakable cast..	35.00
Unstripped motor blocks.	35.00
Brake shoes .....	33.00
Clean auto cast .....	44.00
Stove plate .....	34.00

Railroad Scrap	
No. 1 R.R. heavy melt..	41.00
Rails, 18 in. and under.	50.00
Rails, random lengths..	45.00
Rails, rerolling .....	58.00
Angles, splice bars .....	43.00

## SEATTLE

(Delivered consumer's plant)	
No. 1 heavy melting....	33.00
No. 2 heavy melting....	29.00
No. 1 bundles .....	25.00
No. 2 bundles .....	23.00
No. 3 bundles .....	16.00-17.00
Machine shop turnings..	15.00-16.00
Mixed borings, turnings	15.00-16.00
Short shovel turnings..	15.00-16.00
Electric furnace, No. 1	39.00

Cast Iron Grades	
(F.o.b. shipping point)	
No. 1 cupola .....	36.00-40.00
Heavy breakable cast..	25.00
Unstripped motor blocks	30.00-32.00
No. 1 wheels .....	24.00-25.00
Stove plate (f.o.b. plant)	28.00-29.00
Brake shoes .....	28.00-29.00

Railroad Scrap	
(Delivered consumer's plant)	
Rails, random lengths..	34.00

## LOS ANGELES

No. 1 heavy melting ..	32.00
No. 2 heavy melting ..	30.00
No. 1 bundles .....	32.00
No. 2 bundles .....	25.00
Machine shop turnings	10.00

Cast Iron Grades	
(F.o.b. shipping point)	
No. 1 cupola .....	43.00-45.00

## SAN FRANCISCO

No. 1 heavy melting....	32.00
No. 2 heavy melting....	30.00
No. 1 bundles .....	32.00
No. 2 bundles .....	27.00
No. 1 busheling .....	32.00
Machine shop turnings..	12.00
Mixed borings, turnings	12.00
Short shovel turnings..	14.00
Cast iron borings .....	14.00
Cut structurals .....	34.00
Heavy turnings .....	12.00
Punchings & plate scrap	32.00


Cast Iron Grades	
No. 1 cupola .....	40.00-43.00
Charging box cast ....	35.00
Stove plate .....	37.00
Heavy breakable cast..	36.00
Unstripped motor blocks	30.00
Brake shoes .....	35.00
Clean auto cast .....	39.00
No. 1 wheels .....	39.00
Burnt cast .....	23.00
Drop broken machinery	48.00

## HAMILTON, ONT.

(Delivered prices)	
No. 1 heavy melting....	34.00
No. 2 heavy melting....	31.00
No. 1 bundles .....	34.00
No. 2 bundles .....	28.00
Mixed steel scrap .....	28.00
Mixed borings, turnings	16.00
Rails, remelting .....	43.00
Busheling, new factory:	
Prepared .....	32.00
Unprepared .....	28.00
Short steel turnings...	16.00
Cast Iron Grades†	
No. 1 machinery cast..	42.00-45.00


†F.o.b., shipping point.

# here's why...



## TORRINGTON


**DC needle bearings give high-capacity performance in minimum space**




**Unique construction**—accurately drawn, surface-hardened shell retains rollers and serves as outer raceway.



**Full complement** of small diameter rollers—precision-ground and through-hardened—assures top capacity by distributing load over large number of contacts.




**Turned-in lips** of the case-hardened outer shell keep dirt and grit out, lubricants in—while retaining trunion ends of rollers. All wear surfaces of outer race are case-hardened.




**No inner race** required on surface-hardened shafts—reduces space requirements, lowers unit costs.

**Simple assembly**—arbor press seats bearing in round housing bore. No collars, shoulders or retaining rings needed.



**Closed end type** DC Needle Bearings are available for stub shaft applications. The closed end provides a perfect seal at no extra cost.



Needle Bearings are made in a Precision Series for most applications and an Extra Precision Series where low radial play and minimum eccentricity are required. Easy lubrication through optional hole in shell or through hole in shaft assures long service life. Bearings can be pre-packed with suitable grease for those applications requiring grease lubrication.

See our new Needle Bearing Catalog in the 1955 Sweet's Product Design File—or write direct for Catalog No. 55.

**THE TORRINGTON COMPANY**  
Torrington, Conn. South Bend 21, Ind.


*District offices and distributors in principal cities of United States and Canada*

**TORRINGTON NEEDLE BEARINGS**

Needle • Spherical Roller • Tapered Roller • Cylindrical Roller • Ball • Needle Rollers



## UNIT MACHINING COST CUT 17% ON THIS GRAY IRON CASTING




...thanks to

**FERROCARBO®**

Users everywhere report similar experiences. In fact, on 67 machining tests in 11 large machine shops, castings of gray iron treated with FERROCARBO averaged 89.5% greater machinability per tool than untreated castings. These premium castings are finer-grained, denser, stronger, yet they **COST YOU NO MORE...** because your foundryman, using FERROCARBO, makes worthwhile savings in raw material costs.

FOR FREE BOOKLET on FERROCARBO, citing actual case histories of faster machining, with longer tool life, write The Carborundum Company, Dept. 52, Niagara Falls, N.Y. 94-52

**CARBORUNDUM®**



Your machining department for hardened and precision ground screw machine products. Send for brochure & equipment list.

**Ottawa**



**STEEL  
PRODUCTS  
INC.**

Grand Haven  
Michigan

Gulf ports, where exporters are offering \$36 for No. 1 heavy melting, \$34 for No. 2 heavy melting and up to \$30 for No. 2 bundles. Cast iron prices also are up \$1 a ton, with foundries placing sizable orders for No. 1 and stove plate.

**St. Louis**—Scrap prices continue strong. Supplies are dwindling. Vacation shutdowns steadily trim industrial scrap tonnage. Country shippers and dealers report their intake is less than usual this season because of farm activity and heat.

Railroad grades, especially rerollers, are in sharp demand, but offerings remain low. Four mills split up a 50-car offering last week to prevent skyrocketing prices.

**Seattle**—The scrap market is firm here, with No. 1 and No. 2 heavy melting steel holding steady at \$33 and \$29, respectively. Exports are providing strong support. Receipts are heavy, allowing some surplus for export.

**Los Angeles**—For the second consecutive month, scrap exports were heavy in July. At least three cargoes were shipped to Japan from the Los Angeles port. The big export push is expected to continue into August.

## Pig Iron . . .

Pig Iron Prices, Page 111

Pig iron demand continues active and is expected to come close to equaling the May volume this month. Prospects are that September volume will be fully abreast of it. June and July registered declines because of foundry closings for vacations.

Merchant pig iron sellers in the Cleveland district are booking much larger volume of business this summer than they had anticipated. They expect demand to be heavy well into the fourth quarter, especially with scrap prices rising steadily in recent weeks.

Keokuk Electro-Metals Co. increased all grades of electric furnace silvery pig iron \$2.50 a gross ton, f.o.b. Keokuk, Iowa, effective July 25.

There is no shortage of iron, blast furnace capacity being adequate to accommodate all anticipated needs. Blast furnaces operated at 94.7 per cent in June and 90 per cent in the first half of the year.

Production of pig iron came to 6,495,050 net tons in June and 37,168,706 tons in the first six months, while output of ferromanganese and spiegel-eisen came to 48,828 tons in June and 315,719 tons in the first half.

Total blast furnace output of 6,543,878 tons in June compared with 4,724,150 tons in the like 1954 period; 37,484,425 tons in the first six months of this year compared with

29,191,682 in the like period a year ago.

The bulk of iron consumers in New England are paying the lowest price for tonnage in the East, with the exception of those buying basic from the Chester, Pa., furnace. Mystic Furnace, under its mutual agreement contracts, did not advance \$2.50 a ton. Thus, the equalization point with Buffalo and Troy, N. Y., has broadened for the Everett, Mass., producer. The last named has a substantial stockpile, reducing production to the lowest draft point and still continue in blast.

## Rails, Cars . . .

Track Material Prices, Page 109

Orders for 800 steel boxcars have been placed with the Bessemer, Ala., plant of Pullman-Standard Car Mfg. Co. by the Central of Georgia Railway and its affiliate, Savannah & Atlantic Railway. Order exceeds \$5,500,000.

The Rutland Railroad, which in June a year ago ordered its first new freight equipment in 30 years, last week stepped up its rehabilitation program by ordering 100 fifty-ton 40-ft-6-in. boxcars from Pullman-Standard Car Mfg. Co., Chicago.

## STRUCTURAL SHAPES . . .

### STRUCTURAL STEEL PLACED

- 2400 tons, paper mill addition, Calhoun, Tenn., Bowaters Southern Paper Corp., to Bristol Steel & Iron Works Inc., Bristol, Va.
- 1700 tons, plant addition, Parish Pressed Steel Co., Reading, Pa., to Bethlehem Steel Co., Bethlehem, Pa.
- 1010 tons, ten-story office building, Fulton County Federal Savings & Loan Association, Atlanta, Ga., to Bristol Steel & Iron Works Inc., Bristol, Va., through J. A. Jones Construction Co.
- 1000 tons, Mayfield dam, Tacoma, Wash., to Consolidated Western Steel Corp., Seattle (project in litigation).
- 1000 tons, state turnpike bridgework, section 36-G, Carbon county, Pa., to Lehigh Structural Steel Co., Allentown, Pa.
- 500 tons, plant at Antioch, Calif., for the DuPont interests, to Consolidated Western Steel Division, U. S. Steel Corp., Pittsburgh.
- 450 tons, TWA hangar, Philadelphia Municipal Airport, through Baton Construction Co., general contractor, to Lehigh Structural Steel Co., Allentown, Pa.
- 450 tons, senior high school, New Canaan, Conn., to Schacht Steel Construction Inc., New York.
- 420 tons, buildings, airport, Prince George, Md., to Allied Structural Steel Co., Dover, Del.
- 300 tons, Seward terminal, Alaska railroad, to Isaacson Iron Works, Seattle; Mannix & Stolte, general contractor.
- 300 tons, plant addition, Armco Steel Corp., Ashland, Ky., to American Bridge Division, U. S. Steel Corp., Pittsburgh.
- 250 tons, public school, Topton, Pa., to Lehigh Structural Steel Co., Allentown, Pa.
- 200 tons, Navy hangar, Klamath Falls, Oreg., to Isaacson Iron Works, Seattle; D. M. Drake Co., Portland, Oreg., general contractor.
- 175 tons, DuPont expansion, Henry Clay, Del., to Bethlehem Fabricators, Bethlehem, Pa.
- 170 tons, parking facility No. 2, Orlando Parking Commission, Orlando, Fla., to Bristol Steel & Iron Works Inc., Bristol, Va., through Paul Smith Construction Co.
- 135 tons, 3-span stringer bridge, Manchester, N. H., to Bancroft & Martin Rolling Mills



## CLASSIFIED

### Positions Wanted

QUALIFIED AND EXPERIENCED SALES ENGINEER is open to represent your company in the Pittsburgh territory. Prefer heavy machinery, mechanical or hydraulic. Reply Box 283 STEEL, Penton Building, Cleveland 13, Ohio.

Man, Age 44, now employed as Welding Engineer, interested in changing positions either as WELDING ENGINEER or SALES ENGINEER. Have metallurgical background with experience in Foundry, Rolling Mill and Fabrication Shop. Widely acquainted in Government and industrial circles. Willing to relocate. Reply Box 288, STEEL, Penton Building, Cleveland 13, Ohio.

MANAGEMENT METALLURGICAL ENGINEER can take full responsibility for quality, production and economy of Electric Steel Making. Wide experience and thorough technical and operational knowledge of problems in melting of all grades of steel. Large and/or highly specialized mills preferred. Presently employed. Top references available. Reply Box 290, STEEL, Penton Building, Cleveland 13, Ohio.

Co., South Portland, Me.; Manchester Sand & Gravel Co., Manchester, general contractor. 100 tons, W-F beam bridge, Albany, N. Y., to Vermont Structural Steel Co., Burlington, Vt.; Olson Construction Co., Montpelier, Vt., general contractor. 100 tons, turnpike bridgework, section 38-H, Carbon county, Pa., to Lehigh Structural Steel Co., Allentown, Pa. 100 tons, DuPont expansion, Seaford, Del., to Belmont Iron Works, Edgelystone, Pa. 10 tons, Woodrow Wilson High School, Seattle, to Bethlehem Pacific Coast Steel Corp., Seattle; Mortensen Construction Co., Seattle, general contractor.

### STRUCTURAL STEEL PENDING

1000 tons, DeKalb avenue subway reconstruction, Board of Transportation, New York, bids Aug. 26. 650 tons, state bridgework, Philadelphia county, Pa.; bids Aug. 26. Also required are 207 tons of reinforcing steel. 500 tons, widening of two state bridges, Allegheny county, Pa.; bids Aug. 12. 280 tons, municipal bridge over the Schuylkill river, city line, Philadelphia; bids closed by Department of Streets, Aug. 26. 186 tons, state bridgework, Butler county, Pa.; bids Aug. 26. 100 tons, I-beam bridge, Conway, Vt.; bids in to Montpelier, Vt. Installed, four structures, towers, mess hall, quarters, etc., Glasgow, Mont., Air Base; bids to U. S. Engineer, Walla Walla, Wash., Aug. 17.

### REINFORCING BARS . . .

#### REINFORCING BARS PLACED

2450 tons, Mayfield dam, Tacoma, Wash., to Steel Fabricators Inc., Seattle; Arundel & Dixon, San Gabriel, Calif., general contractor (project in litigation). 185 tons, Seward terminal, Alaska railroad, to Bethlehem Pacific Coast Steel Corp.; Mannix & Stolte, general contractor. 106 tons, Pacific Telephone & Telegraph Co., dial telephone building, Seattle, to Bethlehem Pacific Coast Steel Corp.; Henrik Vallee Inc., Seattle, general contractor. 260 tons, viaduct and bridges, Waterbury, Conn., to Bethlehem Steel Co., Bethlehem, Pa.; Mariani Construction Co., New Haven, general contractor. 230 tons, treatment plant, Southwest Seattle District, to Steel Fabricators Inc., Seattle; Noble W. White, Seattle, general contractor at \$539,362. 175 tons, three composite beam bridges with skew spans, Derby-Ansonia, Conn., to Bethlehem Steel Co., Bethlehem, Pa.; Jarvis Construction Co., Manchester, Conn., general contractor. 113 tons, Washington state road project, King county, to Bethlehem Pacific Coast Steel Corp., Seattle; A. J. Cheff Construction Co., Seattle, general contractor. 88 tons, post exchange, Ft. Richardson, Alaska,

## CASH FOR USED TRANSFORMERS

Convert your used transformers to cash! Send us a description of them TODAY.

TRANSFORMERS AND COILS BUILT TO YOUR SPECIFICATIONS.

Send blueprints for prompt quotation.

TRANSFORMERS BOUGHT,  
SOLD AND REPAIRED

40 Years of Dependable Service

### THE ELECTRIC SERVICE CO.

5329 Hetzel St., Cincinnati 27, Ohio

**FOR SALE**  
**HASTELLOY W-3/16 INCH**  
**WELDING WIRE**  
10,000 pounds available

Reply Box 287, STEEL  
Penton Building Cleveland 13, Ohio



10 to 12 ft. lengths  
ALL METALS

Also Screw Machine  
Products to Order  
**EASTERN**

Machine Screw Corp.  
New Haven, Conn.  
Makers of H & G  
Die Heads

### WANTED—SURPLUS ROD & BAR

Stainless-Aluminum-Steel-Brass  
Any size; type and quantity. Cash  
for termination inventories.

Send lists to:

**COLLINS ENGINEERING COMPANY**  
9050 Washington Blvd.  
Culver City, California

**MOTORS • GENERATORS  
TRANSFORMERS  
NEW • REBUILT  
WORLD'S LARGEST INVENTORY  
ELECTRIC EQUIPMENT CO.  
PHONE STATION COLLECT GL 6783  
P O BOX 51 ROCHESTER 1 NEW YORK**

## CLASSIFIED

### Help Wanted

#### BUYER

Mechanical, for prominent mid-western steel company. Excellent opportunity for experienced steel mill buyer of mill and furnace equipment including spares, repairs and supplies; conveyors, forgings, castings, machining, etc. Our buyers know of this ad; all replies confidential. Reply Box 289, STEEL, Penton Building, Cleveland 13, Ohio.

### Employment Service

**SALARIED POSITIONS \$5,000 to \$35,000.** We offer the original personal employment service (established 45 years). Procedure of highest ethical standards is individualized to your personal requirements. Identity covered; present position protected. Ask for particulars. R. W. BIXBY, INC., 665 Brisbane Bldg., Buffalo 3, N.Y.

## RAILWAY EQUIPMENT

### FOR SALE

Used — As Is — Reconditioned

**RAILWAY CARS—**

**ALL TYPES**

"SERVICE-TESTED"

**FREIGHT CAR REPAIR PARTS**

For All Types of Cars

**LOCOMOTIVES**

Diesel, Steam, Gasoline

Diesel-Electric

**RAILWAY TANK CARS**

**STORAGE TANKS**

6,000—8,000 and 10,000-Gallon

Cleaned and Tested

**CRANES**

Overhead and Locomotive

**RAILS**

New or Relaying

**IRON & STEEL  
PRODUCTS, INC.**

General Office

13462 S. Brainard Ave.

Chicago 33, Illinois

Phone: Mitchell 6-1212

New York Office

50-d Church Street

New York 7, New York

Phone: BEekman 3-8230

"ANYTHING" containing IRON or STEEL"

## ASSISTANT SUPERINTENDENT

Wanted For

**TWO BLAST FURNACE  
OPERATIONS**

28½ feet, and 18½ feet

For details write or wire stating  
your personal qualifications and  
experience.

### DETROIT STEEL CORPORATION

Personnel Department

Box 371

Portsmouth, Ohio

## WANTED


By Eastern Electric Steel Foundry, SALES-  
MAN, SALES ENGINEER, or JUNIOR  
SALES EXECUTIVE capable of assuming  
responsibilities and duties of sales man-  
ager within five years. Must have prac-  
tical knowledge of steel foundry opera-  
tions. Preferred age 35-45. Submit de-  
tailed resume with reply.

Reply Box 281, STEEL

Penton Building

Cleveland 13, Ohio





*Over and over again...*

# FAIRFIELD

## SAVES YOU MORE ON TOP-QUALITY GEARS

*Fine Gears  
Made to Order*  
for all manner of  
industrial equipment

SPIRAL BEVEL  
STRAIGHT BEVEL  
HYPOID  
HERRINGBONE  
HELICAL  
DIFFERENTIALS  
SPUR  
WORMS AND WORM GEARS

- Send for your copy of illustrated bulletin describing Fairfield's facilities for making gears.

Fairfield is famous for repeat orders—and simply because quality is consistently high, and price is—well, just try to beat it!

How can Fairfield manage this unique position year after year? Truth is, it involves some tried-and-true mass-production methods plus some very special Fairfield ideas developed in the past 35 years of precision gear making.

Then, of course, Fairfield is ideally located with all facilities *under one roof*. Here you will find a complete metallurgical department, batteries of the most modern machines, testing laboratories, latest heat-treating equipment—all operated by skilled craftsmen working under expert engineering supervision.

There's another Fairfield service worth looking into—the expert recommendations on your particular gear problems. Your inquiry will receive prompt attention.

**FAIRFIELD  
MANUFACTURING CO.**



2313 SOUTH CONCORD ROAD • LAFAYETTE, INDIANA

to Bethlehem Pacific Coast Steel Corp.; E. M. Peterson, general contractor.

### REINFORCING BARS PENDING

300 tons, including shapes, Idaho state, Ada county, 447-ft highway bridge; bids to Boise, Idaho, July 26.  
207 tons, state bridgework, Philadelphia county, Pa.; bids Aug. 26.  
117 tons, including 55 tons of shapes, Washington state, Benton county project; Lewis Hopkins Co., Pasco, Wash., awarded at \$93,787.  
100 tons plus, Montana state highway projects: 698-ft Missouri river span; 152 and 120-ft spans, Valley county; 120-ft bridge, Gallatin county; bids to Helena, Mont., July 27.

### PLATES . . .

#### PLATES PLACED

4400 tons, sheet and H-piling for Seward terminal Alaska railroad; general contract to Mannix & Stolte; piling government-furnished; to Columbia-Geneva Steel Division, U. S. Steel Corp.  
2300 tons, Navy Purchasing Office, Washington, to Central Iron & Steel Co., Harrisburg, Pa.  
1000 tons, Mayfield dam, Tacoma, Wash., to Consolidated Western Steel Corp., Seattle (in litigation).  
513 tons, steel pipe, Hanford Works project, to Consolidated Western Steel Corp., Seattle; Harold Kaeser Co., Seattle, general award at \$165,250.  
275 tons, two elevated steel water tanks, Newton Centre, Mass., to Pittsburgh-Des Moines Steel Co., Pittsburgh.

#### PLATES PENDING

125 tons, 200,000-gal elevated water tank veterans' hospital, Excelsior Springs, Mo. bids Aug. 30, Veterans' Administration Washington.  
100 tons or more, three storage tanks, 25,000 bbl capacity each, for jet fuel, King Salmon Alaska Base; bids to U. S. Engineer Anchorage, Alaska, Aug. 18.

### RAILS, CARS . . .

#### LOCOMOTIVES PLACED

New York Central, 61 diesel locomotives, to the Electro-Motive Division, General Motors Corp., LaGrange, Ill.; forty-five are general purpose diesels of 1750-hp available for both road and switching service and 16 yard switchers of 900-hp.

#### LOCOMOTIVES PENDING

New York, New Haven & Hartford, ten 1200-hp diesel-electric switch engines, program authorized.

#### RAILROAD CARS PLACED

Central of Georgia, 800 steel boxcars to the Bessemer, Ala., plant of the Pullman Standard Car Mfg. Co. The order is to be completed in the second quarter of 1956.  
Pennsylvania, 4000 freight cars as follows: 1200 seventy-ton hopper cars to Bethlehem Steel Co.; 800 seventy-ton hopper cars to ACF Industries Inc.; 1000 boxcars, 50 seventy-ton flat cars and 100 seventy-ton gondola cars to its own shops at Altoona, Pa.; 400 seventy-ton covered hopper cars to the Pullman-Standard Car Mfg. Co.  
New York Central, 3000 fifty-ton box cars, its Dispatch Shops, East Rochester, N. Y. through typographical error this award was reported last week as involving only 300 cars.  
Chicago & North Western, 2075 freight cars with 1575 fifty-ton boxcars, going to the Michigan City, Ind., plant of the Pullman Standard Car Mfg. Co., Chicago, and 500 gondola cars going to the East Chicago plant of the General American Transportation Corp., Chicago.  
Canadian National, 1950 freight cars, awarded as follows: 1000 boxcars, Eastern Car Co. Ltd.; 500 boxcars and 200 gondola cars, Canadian Car & Foundry Co., and 250 boxcars, National Steel Car Corp., Ltd.  
Norfolk & Western, 3500 cars, to ACF Industries Inc., New York. List comprises 1500 coal cars, 1500 hopper cars and 500 gondolas.

#### RAILROAD CARS PENDING

New York, New Haven & Hartford, 500 steel boxcars, program authorized.


## Advertising Index

Allegheny Ludlum Steel Corporation .....	130	Industrial Products Suppliers .....	118
Allen-Bradley Co. ....	17, 18	Inland Steel Co. ....	34
Allis-Chalmers .....	Inside Front Cover	Iron & Steel Products, Inc. ....	127
Alloy Metal Wire Division, H. K. Porter Company, Inc. ....	105	Jones & Laughlin Steel Corporation .....	59
American Brass Co., The .....	62	Kardong Brothers, Inc. ....	118
American MonoRail Co. ....	95	Keystone Carbon Co., Powdered Metal Division .....	85
American Screw Co. ....	98	Keystone Drawn Steel Co. ....	118
American Welding & Manufacturing Co., The .....	28	Landis Machine Co. ....	24
American Zinc, Lead & Smelting Co. ....	103	Lewis Machine Co., The .....	121
American Zinc Sales Co. ....	103	Lincoln Electric Co., The .....	68
Arwood Precision Casting Corporation .....	122	National-Standard Co. ....	19
Atlas Car & Mfg. Co., The .....	10	National Steel Corporation .....	48
Baker-Raulang Co., The .....	3	Norgren, C. A., Co. ....	92
Behr-Manning Division of Norton Co. ....	8, 9	Norton Co., Behr-Manning Division .....	8, 9
Bethlehem Steel Co. ....	1	Ohio Crankshaft Co., The .....	2
Bixby, R. W., Inc. ....	127	Ottawa Steel Products, Inc. ....	126
Browning, Victor R., & Co., Inc. ....	122	Pangborn Corporation .....	129
Bullard Co., The .....	61	Pittsburgh Crushed Steel Co. ....	121
Carborundum Co., The .....	121, 126	Pittsburgh Plate Glass Co., Brush Division .....	120
Chicago Rawhide Manufacturing Co., Oil Seal Division .....	Inside Back Cover	Pittsburgh Steel Co. ....	14, 15
Cincinnati Cleaning & Finishing Machinery Co., Inc. ....	54	Poole Foundry & Machine Co. ....	122
Cincinnati Grinders, Inc. ....	44	Porter, H. K. Company, Inc., Alloy Metal Wire Division .....	105
Cincinnati Shaper Co., The .....	21	Reliance Steel Division, Detroit Steel Corporation .....	32
Cities Service Oil Co. ....	83	Republic Steel Corporation .....	22, 23
Cleveland Metal Abrasive Co., The .....	7	Rigidized Metals Corporation .....	120
Cleveland Tramrail Division, The Cleveland Crane & Engineering Co. ....	56	Robbins & Myers, Inc. ....	46
Cold Metal Products Co., The .....	79	Roebbing's, John A., Sons Corporation, A Subsidiary of The Colorado Fuel & Iron Corporation .....	115
Collins Engineering Co. ....	127	Ruby Chemical Co. ....	123
Cone Automatic Machine Co., Inc. ....	26	Ryerson, Joseph T., & Son, Inc. ....	31
Cooper Alloy Corporation .....	55	Saginaw Steering Gear Division, General Motors Corporation .....	11
Cowles Chemical Co. ....	96	Seymour Manufacturing Co., The .....	5
Cowles Tool Co. ....	120	Steel Shot & Grit Co. ....	121
Crocker-Wheeler Division, Elliott Co. ....	89	Thomas Flexible Coupling Co. ....	97
Crucible Steel Company of America .....	43	Timken Roller Bearing Co., The .....	Back Cover
Cullen-Friedstedt Co. ....	69	Torrington Co., The .....	125
Detrex Corporation .....	70	Tube Methods, Inc. ....	16
Detroit Steel Corporation, Reliance Steel Division .....	32	Udylite Corporation, The .....	66
Eastern Machine Screw Corporation, The .....	122, 127	Veeder-Root, Inc. ....	4
Eastman Kodak Co., X-ray Division .....	65	Verson Allsteel Press Co. ....	51
Easton Car & Construction Co. ....	52	Ward Steel Co. ....	123
Ederer Engineering Co. ....	25	Westinghouse Electric Corporation .....	20
Electric Equipment Co. ....	127	Wheland Co., The .....	123
Electric Service Co., The .....	127		
Elliott Co., Crocker-Wheeler Division .....	89		
Erie Bolt & Nut Co. ....	6		
Fairfield Manufacturing Co. ....	128		
Falk Corporation, The .....	101		
Farrel-Birmingham Co., Inc. ....	117		
Ferry, E. W., Screw Products, Inc., The .....	12		
Forster, L. B., Co. ....	123		
General Motors Corporation, Saginaw Steering Gear Division .....	11		
Gisholt Machine Co. ....	112		
Globe Steel Abrasive Co. ....	91		
Gould-National Batteries, Inc. ....	13		
Graver Tank & Mfg. Co., Inc. ....	27		
Great Lakes Steel Corporation .....	48		
Infin Corporation .....	69		
Johnson-Walker Refractories Co. ....	81		
Levi Duty Electric Co. ....	67		

Table of Contents, Page 5

Classified Advertising, Page 127

## PUZZLED by a dust problem?



## Pangborn can solve it for you!

Pangborn Unit Dust Collectors give thorough, efficient dust control at any individual operation. Requiring little floor space, they can be located anywhere. Use the Pangborn Dust Collector to:


- Reclaim valuable material
- Reduce dust damage to expensive machinery and finished products
- Cut plant housekeeping costs
- Speed production — improve working conditions

Investigate Pangborn Unit Dust Collectors now! Shipped assembled... \$545 and up. For details, write to: PANGBORN CORPORATION, 1600 Pangborn Blvd., Hagerstown, Md. *Manufacturers of Dust Control and Blast Cleaning Equipment.*

# Pangborn

## CONTROLS DUST






**"We need BIG  
Stainless Castings"**



**"Our Stainless Castings  
are Special"**

**"BIG"—"SPECIAL"—"TINY"—"INTRICATE"...**

**We can handle any job you have**



**Write for your copy:  
"ALLEGHENY METAL  
CASTINGS"**

32 pages of valuable and complete data on stainless castings: analyses, properties, technical data on handling and heat treatment, typical applications, how to order, etc.

**ADDRESS DEPT. S-68**

Our Buffalo Foundry produces high-alloy steel castings *exclusively* . . . principally for corrosion and heat resisting applications. We've had long and valuable experience (as a pioneer in both vertical-centrifugal and static stainless casting methods) with practically every type of service condition you can name, and we'll welcome the opportunity to take on any stainless, high-temperature or high-strength casting problems you have.

And not just as a matter of meeting

the service conditions, either. We're ready to handle any special shape or difficult-to-cast section your job may require . . . and any size of casting from a few ounces to several tons.

● *Let us quote on your requirement*  
You'll find Allegheny Metal casting unsurpassed for soundness, clean grained strength and easy machining qualities. Uniform, too, and reliable in supply. *Allegheny Ludlum Steel Corporation, Henry W. Oliver Building, Pittsburgh 22, Pennsylvania.*

You can make it BETTER with  
**Allegheny Metal**

WAD 5006 Warehouse stocks carried by all Ryerson Steel plants







**WELDING STEEL PLATES FOR WATER-SUPPLY FITTING**—This huge "Y," being welded from Bethlehem plates, is a typical example of a welded structure in which the fabricator's prime responsibility is making a sound weld. Bethlehem plates are uniform in quality, so that with good welding practice, sound welds are assured. Bethlehem plates come in a full range of sheared and universal mill sizes. Just write or phone the nearest Bethlehem district sales office for complete information.

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

*On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation. Export Distributor: Bethlehem Steel Export Corporation*







# MORE THAN 300 LEADING MANUFACTURERS

are already putting

## SKF TYPE "C" BEARINGS

in their  
products



*"Buffalo"* TYLER  
BELOIT  
HEWITT-ROBINS 

Here are the trade marks of a few of more than 300 leading manufacturers — companies who want extra bearing performance — who already are using the improved SKF Type "C" Spherical Roller Bearing announced less than a year ago.

There are two reasons why

First: They know that for over 40 years, SKF has been first with anti-friction developments that work.

Second: They obtain, size for size, up to 50% more capacity, 2 to 3½ times increased life with SKF's Type "C" Spherical than they can obtain with any other available design, and at no increase in cost.

75

SKF INDUSTRIES, INC., PHILADELPHIA 32, PA.  
— manufacturers of SKF and HESS-BRIGHT® bearings  
© 1954 — SKF Industries, Inc.

**SKF®**  
BALL AND ROLLER BEARINGS

JOY WORTHINGTON  
R. HOE & CO., INC.



DE LAVAL



babcock


Westinghouse

REEVES





# You buy right when you buy MACWHYTE wire rope products!




**Wire Rope** You are assured of getting the *right* rope at Macwhyte no matter what your equipment need . . . no matter how tough the going. There's no guesswork when you buy from a thousand and one types, sizes, and grades of wire rope.

Monarch Whyte Strand wire rope is available PREformed and Internally Lubricated, in Lang Lay, Regular Lay, and with Independent Wire Rope Core or Fiber Core. Ropes are made of Bright Steel, Galvanized Steel, Stainless Steel, and Monel Metal, and are supplied properly lubricated and fabricated to serve well under the severest service conditions. *Catalog G-16 is available.*

**Slings** Hundreds of sizes and types of Macwhyte wire rope slings are designed with the lightness, flexibility, and handling ease you need for efficient, low cost material handling. Three body styles are made: ATLAS Round-Braided, DREW Flat-Braided, MONARCH Single-Part. *Request Catalog S-8.*

**Wire Rope Assemblies** Many Safe-Lock wire rope assemblies are made in a wide range of sizes for machine parts, controls, and operating devices. Assemblies provide a unit of wire rope or aircraft control cable with permanently attached fittings made to specified length, size, load capacity. Assemblies are made to both industrial and aircraft standards. *Ask for Catalog 5201.*



# MACWHYTE

## WIRE ROPE · SLINGS · WIRE ROPE ASSEMBLIES


Macwhyte Company, 2912 Fourteenth Avenue, Kenosha, Wisconsin. *Manufacturers of:*

Internally Lubricated PREformed Wire Rope, Braided Wire Rope Slings, Aircraft Cables and Assemblies, Monel Metal, Stainless Steel Wire Rope, and Wire Rope Assemblies.

### MILL DEPOTS:

New York 4, 35 Water Street  
Pittsburgh 19, 704 Second Avenue  
Chicago 6, 228 So. Desplaines Street  
St. Paul 14, 2356 Hampden Avenue

Ft. Worth 1, P.O. Box 605  
Portland 9, 1603 N.W. 14th Avenue  
Seattle 4, 87 Holgate Street  
San Francisco 7, 141 King Street  
Los Angeles 21, 2035 Sacramento



*Recommendations on request*

10789W



# 11 TIMES THE SERVICE

Steel mill was using rag roll as pinch roll on a shear unit. It lasted about three months on the job. Oil, heat, cutting and pressure contributing toward short life. The G.T.M.—Goodyear Technical Man—recommended using a rubber-covered roll, specified compound and thickness to be used in covering the roll. This roll served 33 months—*11 times the service at a slightly lower original cost.*


Why not discuss your roll covering problems—or procurement of complete rolls—with the G.T.M., or write Goodyear, Industrial Products Div., Akron 16, Ohio.

## GOODYEAR INDUSTRIAL PRODUCTS



### -Specified TYPICAL ROLL APPLICATIONS FOR STEEL MILLS

PROCESSES	TYPES OF ROLLS	
Electrolytic Tin Line	Scrubber	Slitter
Carbon Steel Pickling	Wringer	Tension
Continuous Galvanizing Line	Pinch	Directional Carrying
Continuous Annealing Line	Hold-down	Coating



**YOUR GOODYEAR DISTRIBUTOR** can quickly supply you with Hose, Flat Belts, V-Belts, Packing, Tank Lining, Rubber-Covered Rolls. Look for him in the yellow pages of your Telephone Directory under "Rubber Products" or "Rubber Goods."

We think you'll like  
**THE GOODYEAR TELEVISION PLAYHOUSE**  
every other Sunday—NBC TV Network

# GOOD YEAR

THE GREATEST NAME IN RUBBER